

Date first production: 11/1/56

FILE NOTATIONS

Entered in FID File✓.....
Location Map Skipped✓.....
Card Indexed✓.....

Checked by Chief✓.....
Approval Letter✓.....
Disapproval Letter

7
4-21-75

COMPLETION DATA:

Date Well Completed 11/1/76

Location Inspected ..

OW..... WW..... TA.....

Bond released ..

GW..... OS..... FA.....

State or Fee Land ..

LOGS FILED

Driller's Log.....✓.....

Electric Logs (No.)✓.....

..... I..... Ford I Log..... CR-W..... Micro.....

ARC Sonic CR..... Log..... MR-L..... Sonic.....

CSLog..... CCLog..... Others.....



PETROLEUM PRODUCTS

PRODUCING DEPARTMENT
ROCKY MOUNTAINS-U. S.
DENVER DIVISION

February 10, 1975

TEXACO INC.
P. O. BOX 2100
DENVER, COLORADO 80201

ANETH UNIT WELL NO. H222
SE $\frac{1}{4}$ NE $\frac{1}{4}$ SEC. 22 T40S-R24E
SAN JUAN COUNTY, UTAH
6.34

Mr. P. T. McGrath (3)
District Engineer
U. S. Geological Survey
P. O. Box 959
Farmington, New Mexico 87401

Dear Mr. McGrath:

As requested by your office, the following information is provided for the drilling of Aneth Unit Well No. H222, San Juan County, Utah:

1. SURFACE CASING: 500' of 8-5/8" OD 24# K-55 ST&C, SH.
2. CASINGHEADS: 10-3/4" x 10" Series 600, 2000# pressure rating.
3. PRODUCTION CASING: 5935' of 5-1/2" OD 14 & 15.5# K-55 ST&C, SH.
4. BLOWOUT PREVENTER: 10" Series 600 with blind and pipe rams. See attached drawing.
5. AUXILIARY EQUIPMENT:
 - (a) Kelly cock will be used at all times and checked daily.
 - (b) Safety sub with full opening valve for drill pipe on floor.
6. ANTICIPATED BOTTOM HOLE PRESSURE: 2500 psi.
7. DRILLING FLUID: Water and salt mud.

Very truly yours,


Tommie Bliss
District Superintendent

DRD:RB

Attach.

cc: OGCC (2)

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☐OTHER ☐SINGLE
ZONE ☐MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Texaco Inc. Attention: T. Bliss

3. ADDRESS OF OPERATOR

P. O. Box 2100, Denver, Colorado 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

SE 1/4 NE 1/4 Sec. 22

At proposed prod. zone

2096' FNL & 776' FEL, Sec. 22

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

776'

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1200'

16. NO. OF ACRES IN LEASE

--

19. PROPOSED DEPTH

5935'

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4926' GR

22. APPROX. DATE WORK WILL START*

July 20, 1975

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8"	24#	500'	Circulate to surface.
7-7/8"	5-1/2"	14 & 15.5#	5935'	Cement 600' above pay zone.

DV collar to be run below DeChelly and cement to bottom of surface casing.

Propose to drill this infill well in order to gain optimum primary and secondary oil recovery from the Aneth Unit. Samples will be taken at 10' intervals from 5000' to TD. No cores or DSTs are planned. Logs will be run from surface casing to TD. Prospective zones will be perforated and acidized. Blowout preventer equipment will be as indicated on the attached exhibit, and will be tested at regular intervals. Necessary steps will be taken to protect the environment.

APPROVED BY DIVISION OF
OIL & GAS CONSERVATION

DATE APR 21 1975

BY

C. B. Fugate

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED Tommy Bliss TITLE District Superintendent DATE Feb. 10, 1975

(This space for Federal or State office use)

PERMIT NO.

B-037-50242

APPROVAL DATE

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY

USGS (3)

OGEC (2)

TB

ARM

Bureau of Indian Affairs

The Navajo Tribe

Farmington

SLC

Gulf (2)

Shell

Superior

Tenneco


USGS (1)

Durango

*See Instructions On Reverse Side

COMPANY Texaco Inc.Well Name & No. ANETH UNIT WELL NO. H222 Lease No. _____Location 2096 feet from North line and 776 feet from East lineBeing in San Juan County, Utah

Sec. 22, T.40S., R.24E., S.L.M.

Ground Elevation 4926

Scale -- 4 inches equals 1 mile


Surveyed March 6, 19 75

This is to certify that the above plat was prepared from field notes of actual surveys made by me or under my supervision and that the same are true and correct to the best of my knowledge and belief.

Seal:

Farmington, New Mexico

[Signature]
Registered Professional
Engineer and Land Surveyor.
Utah Surveyor No. 2533




ROAD AND LOCATION PLAT
ANETH UNIT WELL NO. H222
SAN JUAN COUNTY, UTAH

ANETH UNIT

LEGEND

- PRODUCING WELL •
- INJECTION WELL ◐
- BATTERY □
- HEADER ○
- ROAD —
- PUMPER ASSIGNMENT BOUNDRY —



ROAD AND LOCATION PLAT
ANETH UNIT WELL NO. H222
SAN JUAN COUNTY, UTAH

Minimum equipment requirements are:


1. Blowout preventers must be capable of being operated both mechanically and hydraulically. Controls must be located so that the blowout preventer can be operated outside the drilling rig substructure. All steel tubing and connections must be used between the hydraulic controls and the blowout preventer.

2. Pressure rating of the blowout preventer and associated connections must be proportional to depth and pressure expectations. Use Figure 1 as a guide in unknown areas.

3. Distance "A" must be sufficient to accommodate a Hydril preventer if required.

4. Chokes, valves, manifold piping and kill line must be flanged and designed equal to or above the pressure rating of the blowout preventer.

5. Kelly cock must be used at all times and should be checked daily.



NOTE: BLOWOUT PREVENTER MUST HAVE DOUBLE RAMS, ONE BLIND & ONE PIPE RAM OR THE EQUIPMENT MUST CONSIST OF TWO BLOWOUT PREVENTERS, ONE EQUIPPED WITH BLIND RAMS & THE OTHER WITH PIPE RAMS. ALWAYS PLACE THE BLIND RAMS IN THE TOP PREVENTER.

ANETH UNIT WELL NO. H222

SAN JUAN COUNTY, UTAH

APPROVED
[Signature]

TEXACO INC DENVER, COLORADO	
BLOWOUT PREVENTER ASSEMBLY STANDARD NO. 2	
DRAWN BY <u>MRD</u>	CHKD BY <u>J.L.L.</u>
DATE <u>11-8-51</u>	FILE <u>448020</u>
DIVISION <u>DRILLING</u>	DEPT. <u>1-10-51</u>



PETROLEUM PRODUCTS

PRODUCING DEPARTMENT
ROCKY MOUNTAINS-U. S.
DENVER DIVISION

April 15, 1975

TEXACO INC.
P. O. BOX 2100
DENVER, COLORADO 80201

**SURFACE USE DEVELOPMENT PLAN
ANETH UNIT WELL NO. H222
SE $\frac{1}{4}$ NE $\frac{1}{4}$ SEC. 22 T40S-R24E
SAN JUAN COUNTY, UTAH
6.34**

Mr. P. T. McGrath (3)
District Engineer
U. S. Geological Survey
P. O. Box 959
Farmington, New Mexico 87401

Dear Mr. McGrath:

As requested by your office, the Surface Use Development Plan for Aneth Unit Well No. H222, San Juan County, Utah, is as follows:

1. Existing roads and exit to the location are shown on the attached plats.
2. New access road 50' x 30' wide will be required. The road will run north from the location to an existing road, and the surface will be compacted soil. No cuts, culverts or cattleguards will be required.
3. Offset wells to the proposed well are shown on the attached plat.
4. Lateral roads in the vicinity of the location are shown on the attached plat.
5. The flowline for subject well will run approximately 1000' west to an existing header. See attached plat.
6. Water for drilling operations will be trucked from Texaco's fresh water supply tank, a distance of $\frac{1}{4}$ mile.

April 15, 1975

7. All waste material will be contained by earthen and steel pits. Earthen pits will be subsequently back-filled and buried.
8. No separate drill campsites are proposed.
9. There are no registered airstrips in the vicinity of the location.
10. The drillsite location will be laid bare and will be approximately 250' x 250' with natural drainage to the southeast. Proper grading will be used to control erosion, and the drilling pad surface will be compacted soil. A plat showing the location and rig layout is attached.
11. All surfaces not used in normal well servicing and maintenance will be cleaned and graded.
12. The wellsite is slightly sloping, sandy, barren ground sparsely covered with grass.

Very truly yours,



Tommie Bliss
District Superintendent

FMR:RB

Attach.

cc: Board of Oil & Gas Conservation
1350 West North Temple
Salt Lake City, Utah 84116

U. S. Geological Survey
P. O. Box 1809
Durango, Colorado 81301



- A. Drilling pad will be compacted soil.
- B. Surface is slightly sloping, sandy ground sparsely covered with grass.


LOCATION AND RIG LAYOUT PLAT

ANETH UNIT WELL NO. H222

SAN JUAN COUNTY, UTAH

COMPANY Texaco Inc.Well Name & No. ANETH UNIT WELL NO. H222 Lease No. _____Location 2096 feet from North line and 776 feet from East lineBeing in San Juan County, Utah

Sec. 22, T.40S., R.24E., S.L.M.

Ground Elevation 4926

Scale -- 4 inches equals 1 mile

Surveyed March 6, 19 75

This is to certify that the above plat was prepared from field notes of actual surveys made by me or under my supervision and that the same are true and correct to the best of my knowledge and belief.

Seal:

Farmington, New Mexico

E. F. [Signature]
Registered Professional
Engineer and Land Surveyor.
Utah Surveyor No. 2533

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

I-149-IND-8836

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1.

OIL WELL ☒ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR

TEXACO Inc.

Attention: G. L. Eaton

3. ADDRESS OF OPERATOR

P. O. Box 2100, Denver, Colorado 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

SE 1/4 NE 1/4 Sec. 22

2096' FNL & 776' FEL, Sec. 22

7. UNIT AGREEMENT NAME

Aneth Unit

8. FARM OR LEASE NAME

Unit

9. WELL NO.

H222

10. FIELD AND POOL, OR WILDCAT

Aneth Field

11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

Sec. 22 T40S-R24E

14. PERMIT NO.

43-037-30242

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

4926' GR

12. COUNTY OR PARISH

San Juan

13. STATE

Utah

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐

(Other)

PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐

(Other)

REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐Running Surface Casing ☒(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Well spud at 10:30 AM, 9-29-76.

10-1-76: Ran 12 joints, 548' of 8-5/8" OD 28.55# X-42 ST&C new casing.
Set at 545' KB and cemented with 300 sacks Class "B" with 1/4#
Flo-seal, 2% CaCl₂. Plug down at 3:00 PM, 9-30-76 w/1000 psi.
Cement circulated.

Tested BOP equipment at 800 psi for 30 minutes. No loss in pressure.

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE District Superintendent DATE Oct. 5, 1976

(This space for Federal or State office-use)

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

USGS (3) OGC (2) GLE ARM The Navajo Tribe Gulf (2) Shell
Farmington SLC Superior Tenneco

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)

Form approved.
Budget Bureau No. 42-R1424.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. I-149-IND-8836	
2. NAME OF OPERATOR TEXACO Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR P. O. Box 2100, Denver, Colorado 80201		7. UNIT AGREEMENT NAME Aneth Unit	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface SE 1/4 NE 1/4 Sec. 22 2096' FNL & 776' FEL, Sec. 22		8. FARM OR LEASE NAME Unit	
14. PERMIT NO. 43-037-30242		9. WELL NO. H222	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4926' GR		10. FIELD AND POOL, OR WILDCAT Aneth Field	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 22 T40S-R24E	
		12. COUNTY OR PARISH San Juan	13. STATE Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF	<input type="checkbox"/>	PULL OR ALTER CASING	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	MULTIPLE COMPLETE	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	ABANDON*	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	CHANGE PLANS	<input type="checkbox"/>
(Other)	<input type="checkbox"/>		<input type="checkbox"/>

SUBSEQUENT REPORT OF:

WATER SHUT-OFF	<input type="checkbox"/>	REPAIRING WELL	<input type="checkbox"/>
FRACTURE TREATMENT	<input type="checkbox"/>	ALTERING CASING	<input type="checkbox"/>
SHOOTING OR ACIDIZING	<input type="checkbox"/>	ABANDONMENT*	<input type="checkbox"/>
(Other)	<input checked="" type="checkbox"/> Running Prod. Casing		<input checked="" type="checkbox"/>

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

10-19-76: Ran 24 joints, 5-1/2" OD 15.5# K-55 ST&C Casing (811') and 125 joints of 5-1/2" OD 14# K-55 ST&C Casing (5130'). Total 5941', DV tool at 2950'. Set casing at 5935', cemented first stage with 300 sacks Class "B" with 6# Gilsonite, 7# Salt, 1/4# mud-kill, 3/4% CFR-2. Plug down at 3:00 PM, 10-18-76 with 1500 psi. Cemented second stage with 450 sacks (400 sacks of Lite and 50 sacks of regular). Plug down at 4:00 PM, 10-18-76 with 2000 psi. Released rig at 6:00 PM, 10-18-76.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE **District Superintendent** DATE **Oct. 21, 1976**

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

USGS (3) OGOC (2) GLE ARM The Navajo Tribe Gulf (2) Shell
Farmington SLC Superior Tenneco

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See other in-
structions on
reverse side)Form approved.
Budget Bureau No. 42-R355.5.

5. LEASE DESIGNATION AND SERIAL NO.

I-149-IND-8836

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

Aneth Unit

7. UNIT AGREEMENT NAME

Unit

8. FARM OR LEASE NAME

H222

10. FIELD AND POOL, OR WILDCAT

Aneth Field11. SEC., T., R., M., OR BLOCK AND SURVEY
OR AREA**Sec. 22 T40S-R24E**12. COUNTY OR
PARISH**San Juan**

13. STATE

Utah

19. ELEV. CASINGHEAD

4945' KB23. INTERVALS
DRILLED BY**Surf.-TD**

CABLE TOOLS

-25. WAS DIRECTIONAL
SURVEY MADE**No**

27. WAS WELL CORED

No

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ Other ☐

b. TYPE OF COMPLETION: NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other ☐

2. NAME OF OPERATOR
TEXACO Inc. Attention: G. L. Eaton

3. ADDRESS OF OPERATOR
P. O. Box 2100, Denver, Colorado 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface **SE 1/4 NE 1/4 Sec. 22**
At top prod. interval reported below **2096' FNL & 776' FEL, Sec. 22**
At total depth

14. PERMIT NO.

43-037-30242

DATE ISSUED

4-21-75

15. DATE SPUDDED

9-29-76

16. DATE T.D. REACHED

10-18-76

17. DATE COMPL. (Ready to prod.)

11-1-76

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*

4926' GR

20. TOTAL DEPTH, MD & TVD

5935'

21. PLUG, BACK T.D., MD & TVD

5837'22. IF MULTIPLE COMPL.,
HOW MANY***-**

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*

**Desert Creek Top: 5743'
Bottom: TD**

26. TYPE ELECTRIC AND OTHER LOGS RUN

FDC-CNL-GR, MSPL, Tri-Phase, Sonic

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8-5/8"	28.55#	545'	11"	300 sacks	
5-1/2"	14 & 15.5#	5935'	7-7/8"	300 sacks	
	DV Collar	2950'		450 sacks	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
None					2-7/8"	5817'	

31. PERFORATION RECORD (Interval, size and number)

**Desert Creek 5746-52' and 5799-5802'
with 2 jet shots per foot.**

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
5799-5802'	100 gal 15% HCl & 750 gal emulsion acid
5746-5752'	100 gal 15% HCl & 1500 gal emulsion acid

33.*

PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
11-1-76		Pumping 2½" x 1½" x 24' pump at 5782'				Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
11-4-76	24	-	→	81	72	4	890
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
-	-	→	-	-	-	42.5	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold

TEST WITNESSED BY

J. J. Presley

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

TITLE **District Superintendent**DATE **Nov. 16, 1976**

*(See Instructions and Spaces for Additional Data on Reverse Side)

USGS (3)	OGCC (2)	GLE ARM	The Navajo Tribe	Gulf (2)	Shell	Sun (2)
Farmington	SLC	Marathon	Superior	Tenneco	Exxon	Conoco

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments. **Items 22 and 24:** If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES:

SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	38. GEOLOGIC MARKERS	
				NAME	MEAS. DEPTH
No cores were taken.				Navajo	928'
				Chinle	1694'
No DST's were taken.				DeChelly	2832'
				Hermosa	4696'
				Ismay	5588'
				Desert Creek	5743'

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)Form approved.
Budget Bureau No. 42-R1424.
5. LEASE DESIGNATION AND SERIAL NO.

I-149-IND-8836

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		7. UNIT AGREEMENT NAME Aneth Unit	
2. NAME OF OPERATOR TEXACO Inc. Attention: G. L. Eaton		8. FARM OR LEASE NAME Unit	
3. ADDRESS OF OPERATOR P. O. Box 2100, Denver, Colorado 80201		9. WELL NO. H222	
4. LOCATION OF WELL (Report location clearly and in accordance with any State Requirements. See also space 17 below.) At surface SE $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 22 2096' FNL & 776' FEL, Sec. 22		10. FIELD AND POOL, OR WILDCAT Aneth	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 22 T40S-R24E		12. COUNTY OR PARISH San Juan	
13. STATE Utah		14. PERMIT NO. 43-037-30242	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4926' GR		16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data	

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☒(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

7-13-78: MIRUSU. pulled pump and rods. Tagged bottem@ 5841' K.B. Perf. 5755-65 & 5780-90' K.B. w/ 2JSPF. Ran tubing and packer and set RBP @ 5815' and pkr @ 5772' Pumped 250 gals. 28% HCL across prefs. 5780'-5802' K.B. Followed w/1000 gals 28% HCL PAE acid. Communication was noted. Pulled pkr. to 5696' K.B. pumped 1000gals. PAE acid. Moved RBP to 5772' K.B., pkr @ 5700' K.B. pumped 250 gals to perfs. w/ 3000 gals 28% PAE. Rerun Pruduction string and placed well on production.

	Oil	Water
Test Before:	6	5
Test After:	59	15

Successful ETWO

18. I hereby certify that the foregoing is true and correct

SIGNED

Alvin B. Mandy

TITLE

Field Foreman

DATE

7-24-78

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

USGS(4)

OGCC(3)

GLE

ARM

Superior

Navajo Tribe

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☒ gas well ☐ other ☐
2. NAME OF OPERATOR
Texaco Inc.
3. ADDRESS OF OPERATOR
P.O. Box EE, Cortez, CO 81321
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 2096' FNL & 776' FEL, Sec. 22
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF ☐
- FRACTURE TREAT ☐
- SHOOT OR ACIDIZE ☐
- REPAIR WELL ☐
- PULL OR ALTER CASING ☐
- MULTIPLE COMPLETE ☐
- CHANGE ZONES ☐
- ABANDON* ☐

SUBSEQUENT REPORT OF:

- ☐
- ☐
- ☐
- ☐
- ☐
- ☐
- ☐
- ☐

(other) Convert to Wtr. InjectionAPPROVED BY THE DIVISION OF
OIL, GAS, AND MININGDATE: 3/26/80BY: M. J. Windsor

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Texaco Inc. plans to convert Aneth Unit Well H222 from oil producing to water injection status. All work will be done in accordance with USGS and UOGCC regulations. Proposed procedure is as follows:

1. Pull production equipment and clean out to 5895' KB.
2. Perforate 5804-12, 5816-22, 5842-81 with 2 JSPF.
3. Run plastic-coated tubing and packer. Set packer at 5720' KB and inhibit tubing-casing annulus.
4. Place well on injection.
5. Run tracer survey after injection rate stabilizes and acidize if necessary.

In addition, a 350' injection line (2 7/8" cmt-lined steel) will be laid from H222 along existing lease roads.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Alvin R. Marx TITLE Field Foreman DATE 3-14-80

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

USGS(4) UOGCC(3) Navajo Tribe-Superior Oil-GLE-ARM

DIVISION OF
OIL, GAS & MINING

TEXACO

Texaco Inc.
P. O. Box EE
Cortez, CO 81321

April 21, 1980

U.S. Dept. of the Interior
Geological Survey
P. O. Box 959
Farmington, NM 87401

Mr. James F. Sims
District Oil and Gas Supervisor

Dear Mr. Sims:

Please refer to Texaco Inc.'s Sundry Notices of Intent to Convert to Water Injection Wells No. G115 and H222 and your letter dated April 17, 1980. The following information should complete the application for conversion as required by NTL-2B.

Approximately 38,000 BWPD is produced from the Desert Creek member of the Pennsylvanian Paradox formation and injected back into the same formation through approximately 130 WI wells. The latest analysis of this produced water (6-19-79) revealed 150,000 ppm dissolved solids, 376 ppm Cl⁻, and 453 ppm SO₄⁼. The wells are to have internally coated (Tubecoat TK-75) tubing and retrievable injection packers. The tubing-casing annulus of each well is to be treated with ½ gallon per barrel TC-6768A corrosion inhibitor. The wells should take approximately 500-1000 BWIPD at 1900 to 2250 psi WHP.

Radioactive injection surveys will be run on all conversions as their rates and pressures stabilize. Thereafter, periodic surveys will be run to assure that the injected water is confined to the proposed injection interval. Also, casing pressures will be monitored to insure against tubing and/or packer leaks or casing leaks. If pressure is noted on the backside and can't be bled off, the well will be shut-in until corrective action is taken to repair the cause of the backside pressure.

The only known aquifer in the area is a spring located approximately 3/8 mile southwest of Aneth Unit Well G115. Analysis of this water indicated 2000 ppm Cl⁻.

The following downhole information is available for the subject wells:

G115

TD=5805' PBTD=5720'

9 5/8", 32.3# csg set at 1478'. Hole size=12 1/4"

Cmt with 1000 sx reg cmt - circulated to surface

5 1/2", 14#(5500') and 15.5#(295') csg set at 5804'. Hole size=8 3/4"

Cmt with 500 sx reg cmt top at 5765'

S-22, 405, 24E

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☒ gas ☐
well well other2. NAME OF OPERATOR
Texaco Inc.3. ADDRESS OF OPERATOR
P.O. Box EE, Cortez, CO 813214. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 2096'FNL & 776'FEL, Sec. 22
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>
(other) Convert to water inj	<input type="checkbox"/>	<input type="checkbox"/>


17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

8-29-80: MIRUSU. Pulled rods, pump, and tubing. Circulate out bit cone. Ran bit and scraper to 5837' KB. Ran 2 3/8" plastic-coated tubing and 5 1/2" packer. Set packer at 5680' KB. Placed well on injection.

Test: 500 BWIPD, 0 psi

5. LEASE I-149-IND-8836	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME Navajo	
7. UNIT AGREEMENT NAME Aneth Unit	
8. FARM OR LEASE NAME Unit	
9. WELL NO. H222	
10. FIELD OR WILDCAT NAME Aneth	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 22, T40S, R24E	
12. COUNTY OR PARISH San Juan	13. STATE Utah
14. API NO.	
15. ELEVATIONS (SHOW DF, KDB, AND WD) 4944 DF	

(NOTE: Report results of multiple completion or zone change on Form 9-330.)



Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Alvin R. Mares TITLE Field Foreman DATE 9-15-80

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:


USGS(4) UOGCC(3) Navajo Tribe-Superior Oil-GLE-ARM

1. Attach qualitative and quantitative analysis of fresh water from 2 or more producing wells within 1 mile of injection well showing location of wells and date samples were taken, or statement as to why samples were not submitted.
2. Attach qualitative and quantitative analysis of representative sample of water to be injected.
3. Attach plat showing subject well and all known oil and gas wells, abandoned, drilling and dry holes within ½ mile, together and with name of operator.
4. Attach Drillers Log (Form DOGM-UIC-2). (Appropriate Surety must be on file with Conservation Division.)
5. Attach Electric or Radioactivity Log of Subject well (if released).
6. Attach schematic drawing of subsurface facilities including; Size, setting depth, amount of cement used measured or calculated tops of cement surface, intermediate (if any) and production casings; size and setting depth of tubing; type and setting depth of packer; geologic name of injection zone showing top and bottom of injection interval.
7. The original and 6 copies of application, and one complete set of attachments shall be mailed to the Division.
8. Deliver 1 copy of application to landowner on whose land injection well is located and to each operator of a producing leasehold within ½ mile of injection well.
9. Affidavit of mailing or delivery shall be filed not later than five days after the application is filed.
10. Notice that an application has been filed shall be published by the Division in a newspaper of general circulation in the county in which the well is located. The Division shall file proof of publication before the application is approved. The notice shall include name and address of applicant, location of proposed injection or disposal well, injection zone, injection pressure and volume. If no written objection is received within 15 days from date of publication the application will be approved administratively.
11. A well shall not be used for injection or disposal unless completed machine accounting Form DOGM-UIC-3b is filed September 1st, each year.
12. Approval of this application, if granted, is valid only as long as there is no substantial change in the operations set forth in the application. A substantial operation change requires the approval of a new application.
13. If there is less intervening thickness required by Rule I-5 (b) 4 attach sworn evidence and data.

CASING AND TUBING DATA

NAME OF STRING	SIZE	SETTING DEPTH	SACKS CEMENT	TOP OF CEMENT	TOP DETERMINED BY
Surface	8-5/8"	545'	300	SURF	Circ
Intermediate					
Production	5-1/2"	5935'	750	NA	
Tubing	2-3/8"	5673'	Name - Type - Depth of Tubing Packer OTIS 5-1/2" 5673'		
Total Depth	Geologic Name - Inj. Zone		Depth - Top of Inj. Interval		Depth - Base of Inj. Interval
5935'	DESERT CREEK		5746'		5802'

SKETCH - SUBSURFACE FACILITY



PLEASE TYPE OR USE BLACK INK ONLY

(To be filed within 30 days after drilling is completed) I-149-IND-8836

DEPARTMENT OF NATURAL RESOURCES AND ENERGY


DIVISION OF OIL, GAS, AND MINING

Room 4241 State Office Building

Salt Lake City, Utah 84114

API NO

640 Acres



Leases With Curvature
and Outline Lines

COUNTY San Juan SEC. 22 TWP. 40S RGE. 24E

COMPANY OPERATING Texaco Inc.

OFFICE ADDRESS P O Box EE

TOWN Cortez STATE CO ZIP 81321

FARM NAME Aneth Unit WELL NO. H222

DRILLING STARTED 9-29 19 76 DRILLING FINISHED 10-18 19 76

DATE OF FIRST PRODUCTION 11-1-76 COMPLETED 11-1-76

WELL LOCATED SW 1/4 SE 1/4 NE 1/4

3184 FT. FROM SL OF SEC. & 4504 FT. FROM WL OF SEC.

ELEVATION DERRICK FLOOR 4944 GROUND 4933

TYPE COMPLETION

Single Zone DESERT CREEK Order No. _____

Multiple Zone _____ Order No. _____

Comingled _____ Order No. _____

LOCATION EXCEPTION

Order No. _____ Penalty _____

OIL OR GAS ZONES

Name	From	To	Name	From	To
DESERT CREEK	5746'	5802'			

CASING & CEMENT

Casing Set				Cap. Test		Cement	
Size	Wgt	Grade	Feet	Psi	Size	Fillup	Top
8-5/8"	28.55 [#]	X-42	545'	1000	300	CIRC	SURF
5-1/2"	14.15 [#]	K-55	5935'	2000	750	NA	NA

TOTAL DEPTH 5935'

COMPLETION & TEST DATA BY PRODUCING FORMATION

FORMATION	Desert Creek	DESERT CREEK	DESERT CREEK
SPACING & ORDER NO.	40 acre	40 acre	40 ACRE
CLASSIFICATION (Oil; Gas; Dry; Inf. Well)	OIL	7113/78	IND
PERFORATED	5746-5752'	5755-65	
INTERVALS	5799-5802'	5780-90	
ACIDIZED?	5799-5802' 100 GAL 15% HCL \$ 750 GAL EMULSION 5746-5752'	5780-5802 w/ 1200 gals 28% HCL 5746-5772 w/ 14000 gals 28% 100 GAL 15% HCL \$ 1500 GAL EMULSION	
FRACTURE TREATED?		DAE-HCL	

INITIAL TEST DATA

Date

Oil bbl./day

Oil Gravity

Gas Cu. Ft./day

Gas-Oil Ratio Cu. Ft./Bbl.

Water Bbl./day

Pumping or Flowing

CHOKE SIZE

FLOW TURNING PRESSURE

11-4-76	7113/78	8-29-80
81	59	
42.5		
72,000 ^{CF}		
890		
4	15	500 BWIPD
PUMPING		
-		
-		

A record of the formations drilled through, and pertinent remarks are presented on the reverse.
(use reverse side)

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

Telephone 1-303-565-8401 John R. Mary Field Supt.
State of Colorado Name and title of representative of company

County of Montezuma 16th day of Dec. 1983
Subscribed and sworn before me this
My commission expires 10/25/87 Joe A. Roylil

728 N. Beech, Cortez, Co. 81321

PACKERS SET
DEPTH 5673' KB

FORM NO. DOGM-UIC-1

STATE OF UTAH
DIVISION OF OIL, GAS, AND MINING
ROOM 4241 STATE OFFICE BUILDING
SALT LAKE CITY, UTAH 84114
(801) 533-5771
(RULE 1-5)

IN THE MATTER OF THE APPLICATION OF

Texaco Inc.
ADDRESS P. O. Box EE
Cortez, Colorado ZIP 81321
INDIVIDUAL PARTNERSHIP CORPORATION XX
FOR ADMINISTRATIVE APPROVAL TO DISPOSE OR
INJECT FLUID INTO THE AU H222 WELL
SEC. 22 TWP. 40S RANGE 24E
San Juan COUNTY, UTAH

CAUSE NO. _____

ENHANCED RECOVERY INJ. WELL ☒
DISPOSAL WELL ☐

APPLICATION

Comes now the applicant and shows the Division the following:

1. That Rule 1-5 (b) 6 authorizes administrative approval of enhanced recovery injections or disposal operations.
2. That the applicant submits the following information.

Lease Name Aneth Unit	Well No. <u>H 222</u>	Field Aneth	County San Juan
Location of Enhanced Recovery Injection or Disposal Well <u>SE 1/4 - NE 1/4</u> Sec. <u>22</u> Twp. <u>40S</u> Rge. <u>24E</u>			
New Well To Be Drilled Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Old Well To Be Converted Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Casing Test Yes <input type="checkbox"/> No <input type="checkbox"/> Date <u>10-18-76</u>	
Depth-Base Lowest Known Fresh Water Within 1/2 Mile <u>1280'</u>	Does Injection Zone Contain Oil-Gas-Fresh Water Within 1/2 Mile YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>		State What Oil & Gas
Location of Aneth Unit Producing Injection Source(s) wells & San Juan River		Geologic Name(s) Desert Creek & Ismay and Depth of Source(s) +/- 5600'	
Geologic Name of Injection Zone Paradox: DESERT CREEK		Depth of Injection Interval <u>5746</u> to <u>5802</u>	
a. Top of the Perforated Interval: <u>5746'</u>	b. Base of Fresh Water: <u>1280'</u>	c. Intervening Thickness (a minus b) <u>4466'</u>	
Is the intervening thickness sufficient to show fresh water will be protected without additional data? (YES) NO			
Lithology of Intervening Zones Sandstone, limestone & anhydrite w/intermittent shale layers			
Injection Rates and Pressures Maximum <u>2,000</u> B/D <u>2,500</u> PSI			
The Names and Addresses of Those To Whom Copies of This Application and Attachments Have Been Sent <u>The Navajo Tribe</u> <u>Box 146</u> <u>Window Rock, Arizona 86515</u>			

State of Colorado,County of Montezuma,

Alvin R. Marx
Applicant

Field Supt.

Before me, the undersigned authority, on this day personally appeared Alvin R. Marx known to me to be the person whose name is subscribed to the above instrument, who being by me duly sworn on oath states, that he is duly authorized to make the above report and that he has knowledge of the facts stated therein, and that said report is true and correct.

Subscribed and sworn to before me this 16th day of Dec., 19 83

SEAL

My commission expires 10/25/87


Joe D. Roybal
Notary Public in and for Colorado
728 N. Beech, Cortez, Co. 81321
(OVER)

3

SAN JUAN COUNTY UTAH
TEXACO INC - OPERATOR
~~STATE OF UTAH - LANDOWNER~~

• PRODUCER 10

INSECTOR:




NL Treating Chemicals/NL Industries, Inc.

P.O. Box 1675, Houston, Texas 77001

WATER ANALYSIS REPORT

COMPANY TEXACO, INCORPORATED						SHEET NUMBER 1	
FIELD ANETH						DATE 5 APRIL 1	
WELL(S) NAME OR NO. INJECTION WATER				COUNTY OR PARISH SAN JUAN		STATE UTAH	
WATER SOURCE (FORMATION) PLANT		TEMP. F		WATER, BBL/DAY		OIL, BBL/DAY	
GAS, MMCF/DAY		DATE SAMPLED 6 APRIL 1982		TYPE OF WATER <input type="checkbox"/> PRODUCED <input checked="" type="checkbox"/> SUPPLY <input checked="" type="checkbox"/> WATERFLOOD <input type="checkbox"/> SALT WATER DIS			

WATER ANALYSIS PATTERN
(NUMBER BESIDE ION SYMBOL INDICATES me/l* SCALE UNIT)



DISSOLVED SOLIDS

DISSOLVED GASES

CATIONS	me/l*	mg/l*		
Total Hardness	392.0		Hydrogen Sulfide, H ₂ S	337.5 mg/l*
Calcium, Ca ⁺⁺	268.0	5360.0	Carbon Dioxide, CO ₂	185.0 mg/l*
Magnesium, Mg ⁺⁺	124.0	1519.0	Oxygen, O ₂	1.0 mg/l*
Iron (Total), Fe ⁺⁺⁺	0.5	10.0		
Barium, Ba ⁺⁺	—	1.0		
Sodium, Na ⁺ (calc.)	1035.1	23807.3		
ANIONS	me/l*	mg/l*	PHYSICAL PROPERTIES	
Chloride, Cl ⁻	1380.3	49000.0	pH	6.65
Sulfate, SO ₄ ⁻²	24.5	1175.0	Eh (Redox Potential)	N.D. MV
Carbonate, CO ₃ ⁻²	0.0	0.0	Specific Gravity	N.D.
Bicarbonate, HCO ₃ ⁻	4.0	244.0	Turbidity, JTU Units	N.D.
Hydroxyl, OH ⁻	0.0	0.0	Total Dissolved Solids (calc.)	8138.3 mg/l*
Sulfide, S ⁻²	18.8	300.0	Stability Index @ 77 F	+0.39
			@ 140 F	+1.32
			CaSO ₄ Solubility @ 77 F	306.6 me/l*
			@ 176 F	306.8 me/l*
			Max. CaSO ₄ Possible (calc.)	24.5 me/l*
			Max. BaSO ₄ Possible (calc.)	1.0 mg/l*
			Residual Hydrocarbons	N.D. ppm(V)

SUSPENDED SOLIDS (QUALITATIVE)

Iron Sulfide ☐ Iron Oxide ☐ Calcium Carbonate ☐ Acid Insoluble ☐

REMARKS AND RECOMMENDATIONS:

WATER SHOWS A TENDENCY TOWARD SCALING; PRIMARILY CALCIUM CARBONATE

* NOTE: me/l and mg/l are comm. used interchangeably for epm and respectively. Where epm and ppm used, corrections should be made specific gravity.

ENGINEER MARK BROTHERS	DIST. NO. 12	ADDRESS CARMINGTON, N.M.	OFFICE PHONE 505-325-5701	HOME PHONE 505-325-
----------------------------------	------------------------	------------------------------------	-------------------------------------	-------------------------------

TEXACO

INSTRUCTIONS - CANCEL LETTER(S) OF

SIGNED BY

☐ PERMANENT☐ ROUTINE☐ TEMPORARY

(LOCATION)

(DATE)

19

Subject: Water Analysis from
Navajo Aquifer

Aneth Unit H415

Location - SE 1/4 - SE 1/4 Sec 15, T40S, R24E

Sample Date - 1-17-59

Depth - Navajo Aquifer

Temp - 67°F

Ph - 8.7

Total Dissolved Solids - 2573 ppm

SiO₂ - 16 ppmCO₃⁼ - 130 ppmCa⁺ - 7 ppmHCO₃⁻ - 156 ppmMg⁺⁺ - 28 ppmSO₄⁼ - 599 ppmNa⁺ - 76 ppmCl⁻ - 757 ppm

Aneth Unit G422

Location - SW 1/4 - SE 1/4 Sec 22, T40S, R24E

Sample Date - 1-18-59

Depth - Navajo Aquifer

Temp - 67°F

Ph - 9.2

Total Dissolved Solids - 2823 ppm

SiO₂ - 17 ppmCO₃⁼ - 925 ppmCa⁺ - 6 ppmHCO₃⁻ - 912 ppmMg⁺⁺ - 8 ppmSO₄⁼ - 265 ppmNa⁺ - 915 ppmCl⁻ - 271 ppm* Note: these numbers were obtained from Texaco Files
in the Denver Division offices.

If letter requires reply prepare in triplicate, forwarding original and duplicate, and retain copy.

P.O. Box 2100

Denver, Colo.

80201

By

CHECKLIST FOR INJECTION WELL APPLICATION AND FILE REVIEW

Operator: Lehaco Well No. Ameths Unit H222
 County: San Juan T 40S R 24E Sec. 22 API# 43-037-30242
 New Well ☐ Conversion ☐ Disposal Well ☐ Enhanced Recovery Well ☒

	YES	NO
UIC Forms Completed	<u>✓</u>	<u> </u>
Plat including Surface Owners. Leaseholders, and wells of available record	<u>✓</u>	<u> </u>
Schematic Diagram	<u>✓</u>	<u> </u>
Fracture Information	<u>✓</u>	<u> </u>
Pressure and Rate Control	<u>✓</u>	<u> </u>
Adequate Geologic Information	<u>✓</u>	<u> </u>
Fluid Source	<u>Desert Creek - Jerry</u>	

Analysis of Injection Fluid	Yes <u>✓</u>	No <u> </u>	TDS <u>81385</u>
Analysis of Water in Formation to be injected into	Yes <u>✓</u>	No <u> </u>	TDS <u>81385</u>

Known USDW in area	<u>Marathon</u>	Depth <u>1280</u>
Number of wells in area of review	<u>8</u>	Prod. <u>5</u> P&A <u>0</u>
	Water <u>0</u>	Inj. <u>3</u>

Aquifer Exemption	Yes <u> </u>	NA <u>✓</u>
-------------------	-------------------	-------------

Mechanical Integrity Test	Yes <u> </u>	No <u>✓</u>
---------------------------	-------------------	-------------

Date <u> </u>	Type <u> </u>
--------------------	--------------------

Comments: _____

Reviewed by: CMJ

Utah Division of Oil, Gas, and Mining
Casing - Bradenhead Test

Operator: TEXACO INC. Field/Unit: GREATER ANETH
Well: H-222 Township: 40S Range: 24E Sect: 22
API: 43-037-30242 Welltype: INJW Max Pressure: 2500
Lease type: INDIAN Surface Owner: NAVAJO
Last MIT Date: 10/18/76 Witness: F Test Date: 6/2/87

CASING STRING	SIZE	SET AT	PRESSURE	OBSERVATIONS
---------------	------	--------	----------	--------------

Surface:	8 5/8	545	0	
----------	-------	-----	---	--

Intermediate:		0		
---------------	--	---	--	--

Production:	5 1/2	5935	125	did not flow down
-------------	-------	------	-----	-------------------

Other:		0		
--------	--	---	--	--

Tubing:	2 3/8			
---------	-------	--	--	--

Packer:		5673	2250	
---------	--	------	------	--

Recommendations:

recently worked over



STATE OF UTAH
NATURAL RESOURCES
Oil, Gas & Mining

Norman H. Bangerter, Governor
Dee C. Hansen, Executive Director
Dianne R. Nielson, Ph.D., Division Director

355 W. North Temple • 3 Triad Center • Suite 350 • Salt Lake City, UT 84180-1203 • 801-538-5340

June 12, 1987

CERTIFIED RETURN RECEIPT REQUESTED
POOL 861 910

Texaco, Incorporated
Post Office Box EE
Cortez, Colorado 81321

Attn: A.A. Kleier

Gentlemen:

RE: Mechanical Integrity of Injection Wells in the Ismay-Flodine
Park and Aneth Units

Recent field work and monthly reports have revealed probable tubing, packer and/or casing leaks in several injection wells located in the subject units. The following wells appear to have excessive casing pressure:

ANETH UNIT

B-312
C-124
E-413
F-222
F-422
G-120
G-136
H-222 405 24E Sec 22
H-227
H-410
H-427
F-423

ISMAY-FLODINE PARK UNIT

T-121
T-316
T-327
V-220
T-120

Please submit written notice of Texaco's efforts to maintain proper mechanical integrity in these wells, include an evaluation of existing conditions, and future plans and schedules for corrective actions.

Page 2
June 12, 1987
A.A. Kleier

Thank you for your continued cooperation. If you have any questions regarding this request or the operation of Class II injection wells in Utah, please call.

Sincerely,

A handwritten signature in dark ink, appearing to read "Gil Hunt", with a long horizontal flourish extending to the right.

Gil Hunt
UIC Manager

mfp
01340/77



Texaco

#222 405 24E Sec 22

RECEIVED
JUL 06 1987

DIVISION OF
OIL, GAS & MINING

TEXACO INC.
P. O. BOX EE
Cortez, CO. 81321
June 30, 1987

Mr. Gil Hunt
UIC Manager
State of Utah Natural Resources
355 W. North Temple Suite 350
Salt Lake City, Utah 84180

Dear Mr. Hunt,

In response to your attached letter dated June 12, 1987, Texaco is aware that some of our injection wells at our Aneth Unit and our Ismay Flodine Park Unit have revealed probable tubing and/or packer leaks. Texaco does not feel that casing leaks have developed since the casing and tubing pressure are the same. The casing pressure would be substantially less if a casing leak were present.

Texaco is presently attempting to perform 3 to 4 UIC repairs per month depending on manpower and budget. A well with a suspected casing leak is immediately shut in to prevent any possible environmental contamination. Our plans for the remainder of 1987 are to continue to repair several wells per month until all wells experiencing annulus pressure are repaired. Please note that Aneth Unit F222, H222 and H410 were worked on and repaired in June 1987. The IFPU V220 should be corrected to U220.

Texaco realizes the importance of maintaining the integrity of our injection wells. We will continue to work toward eliminating all wells with mechanical problems and attempt to identify on going failures in a timely manner. Texaco appreciates your cooperation regarding this matter and will continue to work closely with your department in correcting any inadequacies.

Please contact the Cortez office if you have any question regarding this matter.

Sincerely,

Alan A. Kleier

Alan A. Kleier

Attachment

cc: LAA
file

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
☐ Oil Well ☐ Gas Well ☒ Other **Injection well**

2. Name of Operator
Texaco Exploration and Producing, Inc.

3. Address and Telephone No.
3300 N. Butler, Farmington N.M. 87401 (505)325-4397

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
2096 FNL & 776 FEL Section 22-T40S-R24E

5. Lease Designation and Serial No.

I-149-IND-8836

6. If Indian, Allottee or Tribe Name

Navajo

7. If Unit or CA, Agreement Designation

Aneth Unit

8. Well Name and No.

H222

9. API Well No.

43037302420002

10. Field and Pool, or Exploratory Area

Desert Creek and Ismay

11. County or Parish, State

San Juan, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

Acid stimulation

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Texaco Exp. and Prod. Inc. proposes to acid stimulate the subject well to increase the injection rate. The procedure will be as follows:

1. MIRU pump truck. Pump 2175 gal. of 15% HCL with additives in 1 stage.
2. Shut in well and wait to recover load volume for 1 hour.
3. Backflow well to recover load volume into pit.
4. Return well to injection and monitor.

**Accepted by the State
of Utah Division of
Oil, Gas and Mining**

Date: 4-10-91

By: [Signature]

RECEIVED

APR 09 1991

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed [Signature] Title Area Manager Date 04/08/91

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

FM - Farmington (5), UOGCC (3), Navajo Tribe (1), AAK

LNS

DATE: 05/02/91

WELLS BY OPERATOR

PAGE: 96

ACCT NUM	COMPANY NAME	FLD NUM	FIELD NAME	TOWN SHIP	RANGE	SEC	QTR QTR	API NUMBER	PROD ZONE	WELL STATUS	ENTITY	WELL NAME
N0980	TEXACO INC	365	GREATER ANETH	S400	E240	7	SESW	4303715415	PRDX	WIW	99990	WEST ISMAY FED. 2 (ANETH
				S400	E240	7	SWNE	4303716308	PRDX	PA	99990	GULF-AZTEC FED. 6 (ANETH
				S400	E240	7	NWSE	4303716100	HRMS	WIW	99990	NAVAJO FED. 6-1 (ANETH G
				S400	E240	7	SENE	4303716118	HRMS	WIW	99990	NAVAJO FEDERAL 7-1 (ANETH
				S400	E240	7	SESE	4303716322	HRMS	WIW	99990	NAVAJO TRIBE FED. 5-1 (ANE
				S400	E240	8	SESE	4303716323	HRMS	WIW	99990	NAVAJO TRIBE L-3 (ANETH H
				S400	E240	8	SWNW	4303716284	DSCR	WIW	99990	NAVAJO FED. 9-1 (ANETH E
				S400	E240	8	NWSE	4303716101	PRDX	WIW	99990	NAVAJO TRIBE L-6 (ANETH G
				S400	E240	8	SESW	4303716298	PRDX	WIW	99990	NAVAJO TRIBE E-13 (ANETH
				S400	E240	8	SENW	4303716076	HRMS	WIW	99990	NAVAJO FED. 8-1 (ANETH F
				S400	E240	8	NWSW	4303716060	PRDX	WIW	99990	NAVAJO TRIBE E-15 (ANETH
				S400	E240	8	SENE	4303716119	HRMS	WIW	99990	NAVAJO TRIBE E-16 (ANETH
				S400	E240	8	NWNE	4303716305	DSCR	PA	99998	NAVAJO TRIBE E-17 (ANETH
				S400	E240	9	NWSW	4303716061	PRDX	WIW	99990	NAVAJO TRIBE E-14 (ANETH
				S400	E240	9	SESW	4303716082	PRDX	WIW	99990	NAVAJO TRIBE E-4 (ANETH F
				S400	E240	10	SESE	4303716125	PRDX	WIW	99990	NAVAJO TRIBE E-7 (ANETH H
				S400	E240	11	SWSE	4303715944	PRDX	WIW	99990	NAVAJO A-10/34-11 (ANETH
				S400	E240	11	SWSW	4303715940	PRDX	WIW	99990	NAVAJO A-11/14-11 (ANETH
				S400	E240	11	NESW	4303716295	PRDX	WIW	99990	NAVAJO A-12/23-11 (ANETH
				S400	E240	13	SWSW	4303715941	PRDX	WIW	99990	NAVAJO A-4/14-13 (ANETH E
				S400	E240	13	SWNW	4303715938	PRDX	WIW	99990	NAV. TRIBE A-13/12-13 (ANE
				S400	E240	14	SWNE	4303715943	PRDX	WIW	99990	NAVAJO A-7/32-14 (ANETH G
				S400	E240	14	SWNW	4303715939	PRDX	WIW	99990	NAVAJO A-6/12-14 (ANETH E
				S400	E240	14	NESW	4303715942	PRDX	WIW	99990	NAVAJO A-5/23-14 (ANETH F
				S400	E240	14	NENW	4303716422	PRDX	WIW	99990	ANETH F-114
				S400	E240	14	SWSE	4303715945	PRDX	WIW	99990	NAVAJO A-1/34-14 (ANETH G
				S400	E240	14	SWSW	4303716421	PRDX	WIW	99990	NAVAJO A-2 (ANETH E-414)
				S400	E240	14	NENW	4303716310	IS-DC	WIW	99990	NAVAJO A-9/41-14 (ANETH H
				S400	E240	15	NWSW	4303730213	DSCR	WIW	99990	ANETH E-315
				S400	E240	15	NESE	4303730312	DSCR	WIW	99990	ANETH H-315
				S400	E240	21	SENE	4303716122	PRDX	WIW	99990	NAVAJO TRIBE D-7 (ANETH H
				S400	E240	21	SESE	4303716330	PRDX	WIW	99990	NAVAJO TRIBE D-24 (ANETH
				S400	E240	22	NWNW	4303730215	DSCR	WIW	99990	ANETH E-122
				S400	E240	22	SENW	4303730373	DSCR	WIW	99990	ANETH F-222
				S400	E240	22	NWSW	4303716067	PRDX	WIW	99990	NAVAJO TRIBE D-19 (ANETH
				S400	E240	22	NENE	4303716117	PRDX	WIW	99990	NAVAJO TRIBE D-2 (ANETH H
				S400	E240	22	NWNE	4303730425	IS-DC	WIW	99990	ANETH G-122
				S400	E240	22	NWSE	4303720231	DSCR	WIW	99990	ANETH G-322X
				S400	E240	22	SENE	4303730242	DSCR	WIW	99990	ANETH H-222
				S400	E240	23	SENE	4303716123	PRDX	WIW	99990	NAVAJO TRIBE C-8 (ANETH H
				S400	E240	23	SESE	4303716128	PRDX	WIW	99990	NAVAJO TRIBE C-3 (ANETH H
				S400	E240	23	SENW	4303716079	PRDX	WIW	99990	NAVAJO TRIBE C-7 (ANETH F
				S400	E240	23	NWNE	4303716306	DSCR	WIW	99990	NAVAJO TRIBE C-1 (ANETH G
				S400	E240	23	SESW	4303716086	PRDX	WIW	99990	NAVAJO TRIBE C-17 (ANETH
				S400	E240	23	NENW	4303730235	IS-DC	WIW	99990	ANETH F-123
				S400	E240	24	SENW	4303716289	PRDX	WIW	99990	NAVAJO TRIBE C-16 (ANETH
				S400	E240	24	NWSW	4303716069	PRDX	WIW	99990	NAVAJO TRIBE C-10 (ANETH

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
☐ Oil Well ☐ Gas Well ☒ Other **Injection well**

2. Name of Operator
Texaco Exploration and Producing, Inc.

3. Address and Telephone No.
3300 N. Butler, Farmington N.M. 87401 (505)325-4397

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
2096 FNL & 776 FEL Section 22-T40S-R24E

5. Lease Designation and Serial No.

I-149-IND-8836

6. If Indian, Allottee or Tribe Name

Navajo

7. If Unit or CA, Agreement Designation

Aneth Unit

8. Well Name and No.

H222

9. API Well No.

43037302420002

10. Field and Pool, or Exploratory Area

Desert Creek and Ismay

11. County or Parish, State

San Juan, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other

Acid stimulation ✓

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

4/16/91 - MIRU Smith. Pumped 2175 gal. 15% HCL w/ additives in 1 stage. Flushed tubing with 1250 gal. of H2O.

Max. Pressure: 3700 psi.

Avg. Pressure: 3600 psi.

Avg. Rate: 2.2 BPM

SIP: 2800 psi.

Before: 89 BWIPD @ 2200 psi.

After: 120 BWIPD @ 1850 psi.

RECEIVED

MAY 06 1991

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed [Signature] Title **Area Manager**

Date 5/1/91

(This space for Federal or State office use)

Approved by _____
Conditions of approval, if any:

Title _____

Date _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

4 - Farmington (5), UOGCC (3), Navajo Tribe (1), AAK, MGB, EPA

LNS



Texaco Exploration and Production Inc
Midland Producing Division

P O Box 3109
Midland TX 79702-3109

May 22, 1991

RECEIVED

MAY 28 1991

DIVISION OF
OIL GAS & MINING

Division of Oil, Gas, and Mining
Attn: Ms. Lisha Romero
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

Gentlemen:

This is to advise that as a part of a reorganization of Texaco Inc., a Delaware corporation, the name of Texaco Producing Inc., a Delaware corporation and wholly owned subsidiary of Texaco Inc., has been changed to Texaco Exploration and Production Inc. Further, Texaco Exploration and Production Inc. will succeed to the rights, titles, interests and obligations of Texaco Inc.

This means that Texaco Exploration and Production Inc. will be the operator for all the oil and gas properties that were operated by Texaco Inc. and Texaco Producing Inc. We plan to abbreviate the name as Texaco E & P Inc. for purposes of submitting production reports, etc., via computer, and we suggest that for consistency you use that abbreviation also.

We have enclosed a Sundry Notice with a list of the wells which Texaco operates in Utah. Also attached is UIC Form 5 for transfer of injection authority. Please note that Texaco has two Divisions which operate wells in Utah. One is located in Denver, Colorado, and the other is in Midland, Texas. We have enclosed separate Sundry Notices and lists of wells for each Division. If you have questions concerning the Denver-operated wells, please call Roger Hadley at (303) 793-4833. If you have questions concerning the Midland-operated wells, please call Ken Miller at (915) 688-4834.

Please change any of your other records as necessary to reflect this change.

Yours very truly,

R. S. Lane
Assistant Division Manager

RKH/KMM-CC

Attachments

TRANSFER OF AUTHORITY TO INJECT - UIC FORM 5

RECEIVED

MAY 28 1991

Well name and number: _____		See Attached Listing	DIVISION OF OIL GAS & MINING
Field or Unit name: _____		API no. _____	
Well location: QQ _____ section _____ township _____ range _____ county _____			
Effective Date of Transfer: <u>6-1-91</u>			
CURRENT OPERATOR			
Transfer approved by:			
Name	<u>R. S. Lane</u>	Company	<u>Texaco Inc.</u>
Signature	<u><i>R. S. Lane</i></u>	Address	<u>P. O. Box 3109</u>
Title	<u>Attorney-in-Fact</u>	<u>Midland, TX 79702</u>	
Date	_____	Phone	<u>(915) 688-4100</u>
Comments: Correspondence Address: <u>Texaco Inc.</u> <u>3300 North Butler</u> <u>Farmington, NM 87401</u> <u>(505) 325-4397</u>			
NEW OPERATOR			
Transfer approved by:			
Name	<u>R. S. Lane</u>	Company	<u>Texaco Exploration and Production Inc.</u>
Signature	<u><i>R. S. Lane</i></u>	Address	<u>P. O. Box 3109</u>
Title	<u>Attorney-in-Fact</u>	<u>Midland, TX 79702</u>	
Date	_____	Phone	<u>(915) 688-4100</u>
Comments: Correspondence Address: <u>Texaco Exploration and Production Inc.</u> <u>3300 North Butler</u> <u>Farmington, NM 87401</u> <u>(505) 325-4397</u>			
(State use only)			
Transfer approved by <u><i>Neil Hunt</i></u>		Title <u><i>UIC Manager</i></u>	
Approval Date <u><i>6-26-91</i></u>			

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT— for such proposals

6. Lease Designation and Serial Number	
7. Indian Allottee or Tribe Name	
8. Unit or Communitization Agreement	
9. Well Name and Number	
10. API Well Number	
11. Field and Pool, or Wildcat	
12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA	

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other (specify) _____

2. Name of Operator
 Texaco Exploration and Production Inc.

3. Address of Operator
 3300 North Butler, Farmington, NM 87401

4. Telephone Number
 (505) 325-4397

5. Location of Well

Footage : _____
 QQ, Sec. T., R., M. : See Attached

County : _____
 State : UTAH

NOTICE OF INTENT
 (Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>Transfer of Plugging Bond</u> | |

Approximate Date Work Will Start _____

SUBSEQUENT REPORT
 (Submit Original Form Only)

- | | |
|---|---|
| <input type="checkbox"/> Abandonment * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>Change of Operator/Operator Name</u> | |

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

This submittal is for a change of operator (name change) for all of the attached wells. The new operator, Texaco Exploration and Production Inc., hereby accepts operating responsibility and liability under its good and sufficient bond or other security accepted by the Department for proper plugging and surface restoration of the attached wells. All contact personnel, office addresses and phone numbers will remain the same.

FORMER OPERATOR: TEXACO INC.

NEW OPERATOR: TEXACO EXPLORATION AND PRODUCTION INC.

SIGNED: *[Signature]*
 Attorney-in-Fact

SIGNED: *[Signature]*
 Assistant Division Manager

DATE: _____

DATE: _____

14. I hereby certify that the foregoing is true and correct

Name & Signature _____

Title Asst. Div. Manager Date _____

(State Use Only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUBMIT IN TRIPLED COPY
(Instructions on
reverse side)

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO.
2. NAME OF OPERATOR Texaco Exploration and Production Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR P.O. Box 46510, Denver, CO 80201		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface		8. FARM OR LEASE NAME
14. PERMIT NO.		9. WELL NO.
15. ELEVATIONS (Show whether SP, RT, GR, etc.)		10. FIELD AND POOL, OR WILDCAT
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
		12. COUNTY OR PARISH 13. STATE

MAY 28 1991
DIVISION OF
OIL GAS & MINING

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) Transfer of Plugging Bond <input checked="" type="checkbox"/>	

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) Transfer of Owner/Operator <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Texaco Inc. has assigned all its ownership rights in the subject well. As of January 1, 1991, Texaco Inc. is no longer the Operator of subject well. The New Operator Texaco Exploration and Production Inc. hereby accepts operating responsibility and liability under its good and sufficient bond or other security accepted by the Commission for proper plugging and surface restoration of the subject well.

Former Operator:

TEXACO INC.

Signed:

Attorney-In-Fact
for Texaco Inc.

Date:

3/1/91

New Operator:

Texaco Exploration and Production Inc.

Signed:

Title: Division Manager

Date:

3/1/91

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE Division Manager

DATE

3/1/91

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

COMMENTS OF APPROVAL, IF ANY:

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Routing:

1- LCR/GIL	✓
2- DTS-DTS	✓
3- VLC	✓
4- RJF	✓
5- RWM	✓
6- LCR	✓

Attach all documentation received by the division regarding this change.
Initial each listed item when completed. Write N/A if item is not applicable.

☐ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☒ Operator Name Change Only

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 1-1-91)
(TEXACO EXPLORATION AND PRODUCTION INC.)

TO (new operator)	TEXACO E & P INC.	FROM (former operator)	TEXACO INC.
(address)	3300 NORTH BUTLER	(address)	3300 NORTH BUTLER
	FARMINGTON, NM 87401		FARMINGTON, NM 87401
	BRENT HELQUIST		FRANK
	phone (505) 325-4397		phone (505) 325-4397
	account no. N 5700 (6-5-91)		account no. N 0980

Well(s) (attach additional page if needed):

Name: (SEE ATTACHED)	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec. _____	Twp. _____	Rng. _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

- See 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form). (5-28-91)
- N/A 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form).
- See 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) yes If yes, show company file number: #114097.
- See 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of Federal and Indian well operator changes should take place prior to completion of steps 5 through 9 below.
- See 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. (6-11-91)
- See 6. Cardex file has been updated for each well listed above.
- See 7. Well file labels have been updated for each well listed above. (will update when filing)
- See 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission.
- See 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

TY REVIEW

1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

ND VERIFICATION (Fee wells only)

1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond. #K0290791-4 80,000-Ins. Co. of N. America rec. 2-11-91.
2. A copy of this form has been placed in the new and former operators' bond files.
3. The former operator has requested a release of liability from their bond (yes/no) yes. Today's date _____ 19____. If yes, division response was made by letter dated _____ 19____. #m157448 80,000-Ins. Co. of N. America

ASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated _____ 19____, of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
2. Copies of documents have been sent to State Lands for changes involving State leases. 6-27-91

LMING

1. All attachments to this form have been microfilmed. Date: July 15 1991.

LING

1. Copies of all attachments to this form have been filed in each well file.
2. The original of this form and the original attachments have been filed in the Operator Change file.

MENTS

- 910606 Btm/Farmington N.M. - Duane Spencer (505) 327-5344 will follow up & call back.
- 910607 Btm/Farmington - Approved 4-2-91 "Company Merger" Includes Aneth Unit and Ismay Flodine Unit.
- 910607 St. Lands approved 4-15-91 "merger".



Chevron

Chevron U.S.A. Production Company
Mid-Continent Business Unit
P.O. Box 36366
Houston, TX 77236
Phone 713 754 2000

April 9, 2002

Mr. John Baza,
Associate Director of Oil and Gas
Utah Department of Natural Resources
Division of Oil, Gas & Mining
1594 W. North Temple St., Suite 1210
Salt Lake City, UT 84114-5801

RECEIVED

APR 12 2002

**DIVISION OF
OIL, GAS AND MINING**

Dear Mr. Baza:

As you may recall from our meeting last year, we planned to combine the assets of Chevron U.S.A. Inc. ("CUSA"), by merger, and Texaco Exploration and Production Inc. ("TEPI"), by assignment, into a new entity which we referred to as "Newco LP". Along the way, additional information came to light and it was decided that this proposed corporate restructure would not be preferable. Therefore, CUSA and TEPI have continued to operate as separate entities.

We are now planning a simpler restructuring process where TEPI will assign most of its assets/operatorship to CUSA effective May 1, 2002. We plan to use the existing CUSA bonds/letters of credit, operator identification numbers, etc., for the TEPI assets that will be assigned.

A task force of Land, Regulatory and Environmental Compliance personnel are finishing the work that was begun last year to assign TEPI's assets—using the same forms and procedures as before. We have "new faces" in this task force due to reassignments and departures. In some cases, it may be worthwhile to visit you and your staff in person where new people are involved or if we need to review/clarify your forms and procedures. Otherwise, we will endeavor to complete the work to assign TEPI's assets/operatorship to CUSA and deliver the requisite materials to you in a timely manner.

During discussions last year, our focus was on Land, Regulatory and Environmental matters. The Finance organization also desires to join in this effort. For State Tax, Royalty and Regulatory reporting purposes (applicable to production from May 2002 through December 2002), we intend to generate two reports and two payments.

However, the reporting company name and identification number will be CUSA's. Beginning with January 2003 production and thereafter, we will issue only one CUSA report and payment. We trust this plan meets with your approval. Any questions or comments should be directed to Rick Dunlavy (telephone 713/752-7411, rickdunlavy@chevrontexaco.com).

We appreciate the cooperation and guidance you provided us in the past, and we look forward to bringing these efforts to a conclusion.

Respectfully submitted,

A handwritten signature in dark ink, appearing to read "Don R. Sellars". The signature is fluid and cursive, with the first name "Don" and last name "Sellars" clearly distinguishable.

Don R. Sellars


Sr. Environmental Specialist

TRANSFER OF AUTHORITY TO INJECT


Well Name and Number Orangeville & Huntington, Emery County, Utah (See Attached Well List)		API Number
Location of Well Footage : See attached well locations County : Emery QQ, Section, Township, Range: State : UTAH		Field or Unit Name See Attached Well List Lease Designation and Number See Attached Well List

EFFECTIVE DATE OF TRANSFER: 5/1/2002


CURRENT OPERATOR

Company: Texaco Exploration and Production Inc	Name: Allen S. Robinson
Address: 3300 North Butler, Suite 100	Signature: 
city Farmington state NM zip 87401	Title: Attorney-In-Fact
Phone: (505) 325-4397	Date: April 30, 2002
Comments:	

NEW OPERATOR

Company: Chevron U.S.A. Inc.	Name: J. Scott Purdy
Address: P.O. Box 36366	Signature: 
city Houston state TX zip 79702	Title: Attorney-In-Fact
Phone: (915) 687-2000	Date: May 1, 2002
Comments:	

(This space for State use only)

Transfer approved by: 
Title: Tech Services Manager

Approval Date: 10/21/02

Comments:

RECEIVED

MAY 06 2002

DIVISION OF
OIL, GAS AND MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Operator Name Change</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: See Attached List of Wells
2. NAME OF OPERATOR: Chevron U.S.A. Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: BLM & State of Utah
3. ADDRESS OF OPERATOR: P.O. Box 36366 CITY Houston STATE TX ZIP 77236		7. UNIT or CA AGREEMENT NAME: Orangeville & Huntington
4. LOCATION OF WELL FOOTAGES AT SURFACE: See Attached List of Wells		8. WELL NAME and NUMBER: See Attached List of Wells
PHONE NUMBER: (281) 561-3443		9. API NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT:

COUNTY: Emery

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: <u>Operator Name Change (Merger)</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective May 1, 2002, Chevron U.S.A. Inc. is the new operator of the attached list of subject wells and leases that were previously operated by Texaco Exploration and Production Inc. The subject wells are located North of Orangeville and North of Huntington, Emery County, Utah. These Wells will be protected by the following surety bonds:

STATE OF UTAH Bond #: 103521627-0010 in the amount of \$80,000. (This bond will replace United Pacific Insurance Company bond number U89-75-80-0059. We respectfully request this bond be released and returned.)

BLM Nationwide Bond#: U89-75-81-0034 in the amount of \$300,000.

Key Contacts:

Ron Wirth - Operations Supervisor - 435 748-5395 x1
Texaco Exploration & Production Inc.

J. S. Purdy, Attorney-In-Fact

RECEIVED

MAY 06 2002

DIVISION OF
OIL, GAS AND MINING

NAME (PLEASE PRINT) <u>Allen S. Robinson</u>	TITLE <u>Attorney-In-Fact</u>
SIGNATURE <u></u>	DATE <u>April 30, 2002</u>

(This space for State use only)

Chevron U.S.A. Inc.
Permian Business Unit
Aneth Operations
San Juan County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.
Injection Wells

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main
N5700	11	400S	230E	4303716034	MESA 1 (ANETH C411)	1	I	WI
N5700	12	400S	230E	4303716272	BURTON 23-12 (ANETH B312)	1	A	WI
N5700	12	400S	230E	4303716274	BURTON 31-12 (ANETH C-112)	1	I	WI
N5700	12	400S	230E	4303716278	BURTON 42-12 (ANETH D212)	1	A	WI
N5700	12	400S	230E	4303730049	ANETH UNIT D-412	1	A	WI
N5700	12	400S	230E	4303730112	ANETH UNIT C-312	1	A	WI
N5700	13	400S	230E	4303715825	BURTON 22-13 (ANETH B-213)	1	A	WI
N5700	13	400S	230E	4303715827	BURTON 31-13 (ANETH C-113)	1	A	WI
N5700	13	400S	230E	4303715828	BURTON 33-13 (ANETH C-313)	1	A	WI
N5700	13	400S	230E	4303715830	BURTON 42-13 (D213)	1	A	WI
N5700	13	400S	230E	4303716279	BURTON 44-13 (ANETH D-413)	1	A	WI
N5700	13	400S	230E	4303730119	ANETH UNIT A-113	1	A	WI
N5700	13	400S	230E	4303730174	ANETH UNIT D113	1	A	WI
N5700	13	400S	230E	4303730297	ANETH B-413	1	A	WI
N5700	13	400S	230E	4303730299	ANETH UNIT A-313	1	A	WI
N5700	14	400S	230E	4303716032	ARROWHEAD 6 (ANETH B-114)	1	A	WI
N5700	14	400S	230E	4303716033	ARROWHEAD 3 (ANETH C-214)	1	A	WI
N5700	14	400S	230E	4303716035	ARROWHEAD 5 (ANETH C-414)	1	A	WI
N5700	14	400S	230E	4303716038	ARROWHEAD 4 (ANETH D-314)	1	A	WI
N5700	14	400S	230E	4303716273	ARROWHEAD 2 (ANETH B-314)	1	A	WI
N5700	14	400S	230E	4303716277	ARROWHEAD 1 (ANETH D-114)	1	A	WI
N5700	23	400S	230E	4303716271	A W RICE 2 (ANETH B-123)	1	A	WI
N5700	23	400S	230E	4303716276	A W RICE 3 (ANETH C-223)	1	A	WI
N5700	24	400S	230E	4303716270	FEDERAL A-1 (ANETH A-124)	1	A	WI
N5700	24	400S	230E	4303716275	FEDERAL 1 (ANETH C-124)	1	A	WI
N5700	07	400S	240E	4303715412	W ISMY FED 3 (ANETH E307)	1	A	WI
N5700	07	400S	240E	4303715415	W ISMAY FED 2 (ANETH F-407)	1	A	WI
N5700	07	400S	240E	4303716100	NAVAJO FED 6-1 (ANETH G-307)	1	A	WI
N5700	07	400S	240E	4303716118	NAVAJO FED 7-1 (ANETH H-207)	1	I	WI
N5700	07	400S	240E	4303716283	GULF-AZTEC FED 7 (ANETH E-207)	1	A	WI
N5700	07	400S	240E	4303716322	NAVAJO TRIBE FED 5-1 (ANETH H-407)	2	A	WI

Chevron U.S.A. Inc.
Permian Business Unit
Aneth Operations
San Juan County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.
Injection Wells

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main
N5700	07	400S	240E	4303730175	ANETH U E407	1	A	WI
N5700	08	400S	240E	4303716060	NAVAJO TRIBE E-15 (ANETH E-308)	2	A	WI
N5700	08	400S	240E	4303716076	NAVAJO FED 8-1 (ANETH F-208)	2	A	WI
N5700	08	400S	240E	4303716101	NAVAJO TRIBE L-6 (ANETH G-308)	2	A	WI
N5700	08	400S	240E	4303716119	NAVAJO TRIBE E-16 (ANETH H-208)	2	A	WI
N5700	08	400S	240E	4303716284	NAVAJO FED 9-1 (ANETH E-208)	2	A	WI
N5700	08	400S	240E	4303716298	NAVAJO TRIBE E-13 (ANETH F-408)	2	A	WI
N5700	08	400S	240E	4303716323	NAVAJO TRIBE L-3 (ANETH H-408)	2	A	WI
N5700	09	400S	240E	4303716061	NAVAJO TRIBE E-14 (ANETH E-309)	2	A	WI
N5700	09	400S	240E	4303716082	NAVAJO TRIBE E-4 (ANETH F-409)	2	A	WI
N5700	10	400S	240E	4303716125	NAVAJO TRIBE E-7 (ANETH H-410)	2	I	WI
N5700	11	400S	240E	4303715940	ANETH UNIT E-411	2	A	WI
N5700	11	400S	240E	4303715944	NAVAJO A-10/34-11 (ANETH G-411)	2	A	WI
N5700	11	400S	240E	4303716295	NAVAJO A-12/23-11 (ANETH F-311)	2	A	WI
N5700	13	400S	240E	4303715938	NAV TRIBE A-13 (ANETH E-213)	2	A	WI
N5700	13	400S	240E	4303715941	NAVAJO A-4 (ANETH E-413)	2	A	WI
N5700	14	400S	240E	4303715939	NAVAJO A-6 (ANETH E-214)	2	A	WI
N5700	14	400S	240E	4303715942	ANETH F-314	2	A	WI
N5700	14	400S	240E	4303715943	NAVAJO A-7/32-14 (ANETH G-214)	2	A	WI
N5700	14	400S	240E	4303715945	NAVAJO A-1/34-14 (ANETH G-414)	2	A	WI
N5700	14	400S	240E	4303716310	NAVAJO A-9/41-14 (ANETH H-114)	2	A	WI
N5700	14	400S	240E	4303716421	ANETH UNIT E414	2	A	WI
N5700	14	400S	240E	4303716422	ANETH UNIT F-114	2	A	WI
N5700	14	400S	240E	4303731381	ANETH UNIT H314X	2	I	WI
N5700	15	400S	240E	4303716116	ANETH G-415	2	A	WI
N5700	15	400S	240E	4303716296	NAVAJO TRIBAL E-8 (ANETH F-315)	2	A	WI
N5700	15	400S	240E	4303730213	ANETH E-315	2	A	WI
N5700	15	400S	240E	4303730312	ANETH H-315	2	A	WI
N5700	16	400S	240E	4303715832	STATE THREE 11-16 (ANETH E-116)	3	A	WI
N5700	16	400S	240E	4303716285	ST THREE 21-16 (ANETH F-116)	3	A	WI
N5700	16	400S	240E	4303716297	ST THREE 23-16 (ANETH F-316)	3	A	WI

Chevron U.S.A. Inc.
Permian Business Unit
Aneth Operations
San Juan County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.
Injection Wells

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main
N5700	16	400S	240E	4303716312	STATE THREE 42-16 (ANETH H-216)	3	A	WI
N5700	16	400S	240E	4303720230	ANETH H-416	3	A	WI
N5700	16	400S	240E	4303730094	ANETH E-316	3	A	WI
N5700	16	400S	240E	4303730107	ANETH G-316	3	A	WI
N5700	16	400S	240E	4303730333	ANETH F-416	3	A	WI
N5700	16	400S	240E	4303730344	ANETH G-116	3	A	WI
N5700	17	400S	240E	4303716049	ANETH UNIT E-117	2	A	WI
N5700	17	400S	240E	4303716062	NAVAJO TRIBAL G-7 (ANETH E317)	2	A	WI
N5700	17	400S	240E	4303716089	NAVAJO TRIBAL G-3 (ANETH G-117)	2	A	WI
N5700	17	400S	240E	4303716103	NAVAJO TRIBAL 1-X-G (ANETH G-317)	2	A	WI
N5700	17	400S	240E	4303716286	NAVAJO TRIBAL G-8 (ANETH F-217)	2	A	WI
N5700	17	400S	240E	4303716299	NAVAJO TRIBAL G-6 (ANETH F-417)	2	A	WI
N5700	17	400S	240E	4303716313	NAV TRIBAL L-4 (ANETH H-217)	2	A	WI
N5700	17	400S	240E	4303716326	NAVAJO TRIBAL L-1 (ANETH H-417)	2	A	WI
N5700	18	400S	240E	4303715083	NAVAJO TRIBAL FED U 3	2	A	WI
N5700	18	400S	240E	4303715413	ANETH U E-118 (W ISMY FED 1)	1	A	WI
N5700	18	400S	240E	4303716063	NAVAJO TRIBAL 4 (ANETH E-318)	1	A	WI
N5700	18	400S	240E	4303716090	NAVAJO TRIBE 2 (ANETH G-118)	2	A	WI
N5700	18	400S	240E	4303716104	NAVAJO TRIBE G-4 (ANETH G-318)	2	A	WI
N5700	18	400S	240E	4303716120	NAVAJO TRIBAL G-5 (ANETH H-218)	2	A	WI
N5700	18	400S	240E	4303716287	NAVAJO FED U 1 (ANETH F-218)	2	A	WI
N5700	18	400S	240E	4303716327	NAVAJO TRIBAL G-2 (ANETH H-418)	2	A	WI
N5700	18	400S	240E	4303730137	ANETH U E218	1	A	WI
N5700	18	400S	240E	4303730155	ANETH U F118	1	A	WI
N5700	19	400S	240E	4303716077	NAVAJO TRIBE D-26 (ANETH F-219)	2	A	WI
N5700	19	400S	240E	4303716091	NAVAJO TRIBE D-16 (ANETH G-119)	2	A	WI
N5700	19	400S	240E	4303716121	NAVAJO TRIBE D-3 (ANETH H-219)	2	A	WI
N5700	19	400S	240E	4303716280	NAVAJO FED U B-1 (ANETH E-119)	2	A	WI
N5700	19	400S	240E	4303716309	NAVAJO TRIBE D-25 (ANETH G-319)	2	A	WI
N5700	19	400S	240E	4303716328	NAVAJO TRIBE D-27 (ANETH H-419)	2	A	WI
N5700	20	400S	240E	4303716050	NAVAJO TRIBE D-10 (ANETH E-120)	2	A	WI

Chevron U.S.A. Inc.
Permian Business Unit
Aneth Operations
San Juan County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.
Injection Wells

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main
N5700	20	400S	240E	4303716065	NAVAJO TRIBE D-17 (ANETH E-320)	2	A	WI
N5700	20	400S	240E	4303716092	NAVAJO TRIBE L-5 (ANETH G-120)	2	A	WI
N5700	20	400S	240E	4303716105	NAVAJO TRIBE D-12 (ANETH G-320)	2	A	WI
N5700	20	400S	240E	4303716288	NAVAJO TRIBE D-8 (ANETH F-220)	2	A	WI
N5700	20	400S	240E	4303716300	NAVAJO TRIBE D-20 (ANETH F-420)	2	A	WI
N5700	20	400S	240E	4303716314	NAVAJO TRIBE L-2 (ANETH H-220)	2	A	WI
N5700	20	400S	240E	4303716329	NAVAJO TRIBE D-13 (ANETH H-420)	2	A	WI
N5700	21	400S	240E	4303716051	NAVAJO TRIBE D-4 (ANETH E-121)	2	A	WI
N5700	21	400S	240E	4303716066	NAVAJO TRIBE D-14 (ANETH E-321)	2	A	WI
N5700	21	400S	240E	4303716078	NAVAJO TRIBE D-6 (ANETH F-221)	2	A	WI
N5700	21	400S	240E	4303716084	NAVAJO TRIBE D-21 (ANETH F-421)	2	A	WI
N5700	21	400S	240E	4303716122	NAVAJO TRIBE D-7 (ANETH H-221)	2	A	WI
N5700	21	400S	240E	4303716330	NAVAJO TRIBE D-24 (ANETH H-421)	2	A	WI
N5700	21	400S	240E	4303730095	ANETH G-321X	2	A	WI
N5700	21	400S	240E	4303730335	ANETH G-121X	2	A	WI
N5700	22	400S	240E	4303716067	NAVAJO TRIBE D-19 (ANETH E-322)	2	A	WI
N5700	22	400S	240E	4303716085	NAVAJO TRIBE D-23 (ANETH F-422)	2	A	WI
N5700	22	400S	240E	4303716117	NAVAJO TRIBE D-2 (ANETH H-122)	2	A	WI
N5700	22	400S	240E	4303716127	NAVAJO TRIBE D-22 (ANETH H-422)	2	I	WI
N5700	22	400S	240E	4303720231	ANETH G-322X	2	A	WI
N5700	22	400S	240E	4303730215	ANETH E-122	2	A	WI
N5700	22	400S	240E	4303730242	ANETH H-222	2	A	WI
N5700	22	400S	240E	4303730373	ANETH F-222	2	A	WI
N5700	22	400S	240E	4303730425	ANETH G-122	2	A	WI
N5700	23	400S	240E	4303716068	NAVAJO TRIBE C-12 (ANETH E-323)	2	A	WI
N5700	23	400S	240E	4303716079	NAVAJO TRIBE C-7 (ANETH F-223)	2	A	WI
N5700	23	400S	240E	4303716086	NAVAJO TRIBE C-17 (ANETH F-423)	2	A	WI
N5700	23	400S	240E	4303716123	NAVAJO TRIBE C-8 (ANETH H-223)	2	A	WI
N5700	23	400S	240E	4303716128	NAVAJO TRIBE C-3 (ANETH H-423)	2	A	WI
N5700	23	400S	240E	4303716306	NAVAJO TRIBE C-1 (ANETH G-123)	2	A	WI
N5700	23	400S	240E	4303730235	ANETH F-123	2	A	WI

Chevron U.S.A. Inc.
Permian Business Unit
Aneth Operations
San Juan County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.
Injection Wells

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main
N5700	24	400S	240E	4303716069	NAVAJO TRIBE C-10 (ANETH E-324)	2	A	WI
N5700	24	400S	240E	4303716087	NAVAJO TRIBE C-13 (ANETH F-424)	2	A	WI
N5700	24	400S	240E	4303716111	NAVAJO TRIBE C-15 (ANETH G-324)	2	A	WI
N5700	24	400S	240E	4303716289	NAVAJO TRIBE C-16 (ANETH F-224)	2	A	WI
N5700	24	400S	240E	4303716331	NAVAJO TRIBE C-28 (ANETH H-424)	2	A	WI
N5700	25	400S	240E	4303716070	NAVAJO TRIBE C-21 (ANETH E-325)	2	A	WI
N5700	25	400S	240E	4303716080	NAVAJO TRIBE C-20 (F225)	2	A	WI
N5700	25	400S	240E	4303716095	ANETH UNIT G125	2	A	WI
N5700	25	400S	240E	4303716124	NAVAJO TRIBE C-11 (ANETH H-225)	2	A	WI
N5700	25	400S	240E	4303716129	NAVAJO TRIBE C-24 (ANETH H-425)	2	A	WI
N5700	25	400S	240E	4303716301	NAVAJO TRIBE C-32 (ANETH F-425)	2	A	WI
N5700	26	400S	240E	4303716054	NAVAJO TRIBE C-29 (ANETH E-126)	2	A	WI
N5700	26	400S	240E	4303716071	NAVAJO TRIBE C-30 (ANETH E-326)	2	A	WI
N5700	26	400S	240E	4303716113	NAVAJO TRIBE C-27 (ANETH G-326)	2	A	WI
N5700	26	400S	240E	4303716290	NAVAJO TRIBE C-23 (ANETH F-226)	2	A	WI
N5700	26	400S	240E	4303716302	NAVAJO TRIBE C-4 (ANETH F-426)	2	A	WI
N5700	26	400S	240E	4303716316	NAVAJO TRIBE C-19 (ANETH H-226)	2	A	WI
N5700	26	400S	240E	4303716332	NAVAJO TRIBE C-31 (ANETH H-426)	2	A	WI
N5700	26	400S	240E	4303730372	ANETH G-126X	2	A	WI
N5700	27	400S	240E	4303716223	ANETH 27-B2 (ANETH F-227)	2	I	WI
N5700	27	400S	240E	4303716307	ANETH 27-C-1 (ANETH G-127)	2	A	WI
N5700	27	400S	240E	4303716317	ANETH 27-D2 (ANETH H-227)	2	A	WI
N5700	27	400S	240E	4303716333	ANETH 27-D-4 (ANETH H-427)	2	A	WI
N5700	27	400S	240E	4303716782	ANETH 27-A-1 (ANETH E-127)	2	A	WI
N5700	28	400S	240E	4303716222	ANETH 28-A-1 (ANETH E-128)	2	A	WI
N5700	28	400S	240E	4303716224	ANETH 28-C-1 (ANETH G-128)	2	A	WI
N5700	28	400S	240E	4303716228	ANETH H-228	2	A	WI
N5700	29	400S	240E	4303716055	NAVAJO TRIBE S-2 (ANETH E-129)	2	A	WI
N5700	29	400S	240E	4303716097	NAVAJO TRIBE S-1 (ANETH G-129)	2	A	WI
N5700	29	400S	240E	4303716292	NAVAJO TRIBE S-4 (ANETH F-229)	2	I	WI
N5700	29	400S	240E	4303716318	NAVAJO TRIBE S-3 (ANETH H-229)	2	A	WI

Chevron U.S.A. Inc.
Permian Business Unit
Aneth Operations
San Juan County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.
Injection Wells

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main
N5700	34	400S	240E	4303716303	ANETH 34-B-4 (ANETH F-434)	2	A	WI
N5700	34	400S	240E	4303716319	ANETH 34-D2 (ANETH H-234)	2	I	WI
N5700	35	400S	240E	4303716293	NAVAJO TRIBE Q-5 (ANETH F-235)	2	A	WI
N5700	35	400S	240E	4303716304	NAVAJO TRIBE Q-8 (ANETH F-435)	2	A	WI
N5700	35	400S	240E	4303716320	NAVAJO TRIBE Q-4 (ANETH H-235)	2	A	WI
N5700	36	400S	240E	4303715485	NAVAJO 4 (ANETH E-136)	2	A	WI
N5700	36	400S	240E	4303715486	NAV TRB 2-A (G136)	2	A	WI
N5700	36	400S	240E	4303715487	NAVAJO 1 (ANETH H-236)	2	A	WI
N5700	36	400S	240E	4303716294	NAVAJO 3 (ANETH F-236)	2	A	WI
N5700	19	400S	250E	4303716140	ANETH UNIT L-419	2	A	WI
N5700	29	400S	250E	4303716131	NAVAJO TRIBE F-8 (ANETH J-129)	2	A	WI
N5700	30	400S	250E	4303716132	NAVAJO TRIBE F-9 (ANETH J-130)	2	A	WI
N5700	30	400S	250E	4303716134	NAVAJO TRIBE F-5 (ANETH J-330)	2	A	WI
N5700	30	400S	250E	4303716135	NAVAJO TRIBE F-2 (ANETH K-230)	2	A	WI
N5700	30	400S	250E	4303716137	NAVAJO TRIBE F-7 (ANETH K-430)	2	A	WI
N5700	30	400S	250E	4303716139	NAVAJO TRIBE F-6 (ANETH L-330)	2	A	WI
N5700	30	400S	250E	4303716141	NAVAJO TRIBE F-10 (ANETH M-230)	2	A	WI
N5700	30	400S	250E	4303716337	NAVAJO TRIBE F-11 (ANETH M-430)	2	A	WI
N5700	31	400S	250E	4303715946	NAVAJO TRIBE C11-31 (J131)	2	A	WI
N5700	31	400S	250E	4303716335	NAVAJO TRIBE C-22-31 (ANETH K-231)	2	A	WI

**THE
NAVAJO
NATION****MINERALS DEPARTMENT**

Post Office Box 1910

Window Rock, Arizona 86515

Phone: (928) 871-6587 • Fax: (928) 871-7095

KELSEY A. BEGAYE
PRESIDENT**TAYLOR MCKENZIE, M.D.**
VICE PRESIDENT

October 11, 2002

Mr. Don Sellars
Regulatory Specialist
ChevronTexaco
11111 S. Wilcrest
Houston, Texas 77099

Subject: Navajo Nation Assignment of Oil & Gas Lease

Dear Mr. Sellars:

Attached are fourteen (14) approved Navajo Nation Assignment of Oil and Gas Lease applications for assignment of interest from Texaco Exploration & Production, Inc. to Chevron U.S.A., Inc. (Chevron) for the following leases:

- | | | |
|---------------------|---------------------|----------------------|
| 1) I-149-IND-8834 | 6) I-149-IND-8839 | 11) 14-20-603-4035 |
| 2) I-149-IND-8835 | 7) 14-20-603-2057 | 12) 14-20-603-4037 |
| 3) I-149-IND-8836 | 8) 14-20-603-2059 | 13) 14-20-603-5043-A |
| 4) I-149-IND-8838 | 9) 14-20-603-4030-A | 14) 14-20-603-5446 |
| 5) I-149-IND-8839-A | 10) 14-20-603-4032 | |

If you have any questions, please call me or Mr. Brad Nesemeier at (928) 871-6587.

Sincerely,

Akhtar Zaman, Director
Minerals Department

Attachments
AZ/GLB/cab

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH
2. CDW
3. FILE

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change

X Merger

The operator of the well(s) listed below has changed, effective: **05-01-2002**

FROM: (Old Operator):	TO: (New Operator):
TEXACO EXPLORATION & PRODUCTION INC	CHEVRON USA INC
Address: 3300 NORTH BUTLER, STE 100	Address: P O BOX 36366
FARMINGTON, NM 87401	HOUSTON, TX 79702
Phone: 1-(505)-325-4397	Phone: 1-(915)-687-2000
Account No. N5700	Account No. N0210

CA No.

Unit: ANETH

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NAVAJO TRIBE D-21 (ANETH F-421)	21-40S-24E	43-037-16084	99990	INDIAN	WIW	A
NAVAJO TRIBE D-7 (ANETH H-221)	21-40S-24E	43-037-16122	99990	INDIAN	WIW	A
NAVAJO TRIBE D-24 (ANETH H-421)	21-40S-24E	43-037-16330	99990	INDIAN	WIW	A
ANETH G-321X	21-40S-24E	43-037-30095	99990	INDIAN	WIW	A
ANETH G-121X	21-40S-24E	43-037-30335	99990	INDIAN	WIW	A
NAVAJO TRIBE D-19 (ANETH E-322)	22-40S-24E	43-037-16067	99990	INDIAN	WIW	A
NAVAJO TRIBE D-23 (ANETH F-422)	22-40S-24E	43-037-16085	99990	INDIAN	WIW	A
NAVAJO TRIBE D-2 (ANETH H-122)	22-40S-24E	43-037-16117	99990	INDIAN	WIW	A
NAVAJO TRIBE D-22 (ANETH H-422)	22-40S-24E	43-037-16127	7000	INDIAN	WIW	I
ANETH G-322X	22-40S-24E	43-037-20231	99990	INDIAN	WIW	A
ANETH E-122	22-40S-24E	43-037-30215	99990	INDIAN	WIW	A
ANETH H-222	22-40S-24E	43-037-30242	99990	INDIAN	WIW	A
ANETH F-222	22-40S-24E	43-037-30373	99990	INDIAN	WIW	A
ANETH G-122	22-40S-24E	43-037-30425	99990	INDIAN	WIW	A
NAVAJO TRIBE C-3 (ANETH H-423)	23-40S-24E	43-037-16128	7000	INDIAN	WIW	A
NAVAJO TRIBE C-12 (ANETH E-323)	23-40S-24E	43-037-16068	99990	INDIAN	WIW	A
NAVAJO TRIBE C-7 (ANETH F-223)	23-40S-24E	43-037-16079	99990	INDIAN	WIW	A
NAVAJO TRIBE C-17 (ANETH F-423)	23-40S-24E	43-037-16086	99990	INDIAN	WIW	A
NAVAJO TRIBE C-8 (ANETH H-223)	23-40S-24E	43-037-16123	99990	INDIAN	WIW	A
NAVAJO TRIBE C-1 (ANETH G-123)	23-40S-24E	43-037-16306	99990	INDIAN	WIW	A

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-2-10) Sundry or legal documentation was received from the **FORMER** operator on: 05/06/2002
2. (R649-2-10) Sundry or legal documentation was received from the **NEW** operator on: 04/12/2002
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 10/16/2002
4. Is the new operator registered in the State of Utah: YES Business Number: 564408-0143
5. If **NO**, the operator was contacted on: N/A

6. (R649-9-2) Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: 10/11/2002

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 10/11/2002

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 10/21/2002

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 10/24/2002
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 10/24/2002
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: N/A

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: N/A

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 8975810026

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS: Chevron USA Inc merged with Texaco Exploration & Production Inc to form ChevronTexaco Inc
although all the Utah operations will be operated by Chevron USA Inc.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL
OIL WELL ☒ GAS WELL ☐ OTHER Injection wells

2. NAME OF OPERATOR:
Resolute Natural Resources Company

3. ADDRESS OF OPERATOR:
1675 Broadway, Suite 1950 CITY Denver STATE CO ZIP 80202

PHONE NUMBER:
(303) 534-4600

4. LOCATION OF WELL

FOOTAGES AT SURFACE: See Attachment

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

5. LEASE DESIGNATION AND SERIAL NUMBER:
See Attachment

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Navajo

7. UNIT or CA AGREEMENT NAME:
Aneth Unit

8. WELL NAME and NUMBER:
See Attachment

9. API NUMBER:
See Attach

10. FIELD AND POOL, OR WILDCAT:
Desert Creek

COUNTY: San Juan

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Change of Operator</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As of December 1, 2004, Chevron U.S.A. Inc. resigned as Operator of the Aneth Unit. The successor operator is Resolute Natural Resources Company.

NAME (PLEASE PRINT)

Janet Pasque

TITLE

Vice President

SIGNATURE

Janet Pasque

DATE

11/30/04

(This space for State use only)

APPROVED 12/29/2004

ER

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

UIC FORM 5

Well Name and Number
See attached exhibit.

API Number
See attached exhibit.

Location of Well

Field or Unit Name	Aneth Unit
--------------------	------------

Footage :

County : San Juan

QQ, Section, Township, Range:

State : UTAH

Lease Designation and Number
See attached exhibit.

CURRENT OPERATOR

N0210

Company: Chevron U.S.A. Inc.

Name: A. E. Wacker

Address: 1111 Bagby St.

Signature: A. E. Wacker

city Houston state TX zip 77002

Title: Attorney-in-Fact

Phone: (713) 752-6000

Date: 12/20/2004

Comments:

~~RECEIVED~~

DEC 22 2004

NEW OPERATOR

N2700

DIV. OF OIL, GAS & MINING

Company: **Resolute Natural Resources Company**

Name: Janet Vague xt

Address: 1675 Broadway, Suite 1950

Signature: Sam Kordian

city Denver state CO zip 80202

Title: Vice President

Phone: (303) 534-4600 *Xf*

Date: 12/21/04

Comments:

(This space for State use only)

Transfer approved by:

Approval Date:

Title:

Comments:

Title: VIC Geology

Comments: Transfer of Authority to Inject into the Aneth C214 and Aneth B14 contingent on this office receiving a corrective action plan for each well. Both ~~well~~ Aneth 214 failed 5 year test on 10/13/2004. Operator would not conduct scheduled 5 year test on Aneth B14. (considered a failure).

NUM	API NUM	Q1	Q2	SEC	TWSP	RNG	LEGAL	Lease	Status 12/1/04	NNEPA Well List	USEPA Well List	UIC Program
H222	4303730242	SE	NW	22	40S	24E		I-149-IND-8836	Active	H222	H222	Navajo Nation
F418	4303715083	SE	SW	18	T40S	R24E	650' FSL/1825' FWL	I-149-IND-8835	Active	F418	F418	Navajo Nation
E307	4303715412	NW	SW	7	T40S	R24E	1980' FSL/660' FWL	SL-067807	Active	E307	E307	Navajo Nation
E118	4303715413	NW	NW	18	T40S	R24E	660' FNL/660' FWL	SL-067807	Active	E118	E118	Navajo Nation
F407	4303715415	SE	SW	7	T40S	R24E	660' FSL/1980' FWL	SL-067807	Active	F407	F407	Navajo Nation
E136	4303715485	NW	NW	36	T40S	R24E	660' FNL/660' FWL	14-20-603-5444	Active	E136	E136	Navajo Nation
G136	4303715486	NW	NE	36	T40S	R24E	785' FNL/2040' FEL	14-20-603-5443	Active	G136	G136	Navajo Nation
H236	4303715487	SE	NE	36	T40S	R24E	1980' FNL/660' FEL	14-20-603-5443	P/A			Navajo Nation
B213	4303715825	SE	NW	13	T40S	R23E	3300' FSL/3300' FEL	SL-070968-A	Active			State of Utah
C113	4303715827	NW	NE	13	T40S	R23E	4602' FSL/1993' FEL	SL-070968-A	Active			State of Utah
C313	4303715828	NW	SE	13	T40S	R23E	1949' FSL/1991' FEL	SL-070968-A	Active			State of Utah
D213	4303715830	SE	NE	13	T40S	R23E	3263' FSL/660' FEL	SL-070968-A	Active			State of Utah
E116	4303715832	NW	NW	16	T40S	R24E	601' FNL/550' FWL	ML-3156	Active	E116	E116	Navajo Nation
E213	4303715938	SW	NW	13	T40S	R24E	2140' FNL/740' FWL	I-IND-149-8837	Active	E213	E213	Navajo Nation
E214	4303715939	SW	NW	14	T40S	R24E	1940' FNL/650' FWL	I-149-IND-8837	Active	E214	E214	Navajo Nation
E411	4303715940	SW	SW	11	T40S	R24E	500' FSL/820' FWL	I-149-IND-8837	Active	E411	E411	Navajo Nation
E413	4303715941	SW	SW	13	T40S	R24E	660' FSL/660' FWL	IND-149-8837	Active	E413	E413	Navajo Nation
F314	4303715942	NE	SW	14	T40S	R24E	1980' FSL/1980' FWL	I-149-IND-8837	Active	F314	F314	Navajo Nation
G214	4303715943	SW	NE	14	T40S	R24E	2140' FNL/2010' FEL	I-149-IND-8839	P/A			Navajo Nation
G411	4303715944	SW	SE	11	T40S	R24E	680' FSL/1950' FEL	I-149-IND-8837	Active	G411	G411	Navajo Nation
G414	4303715945	SW	SE	14	T40S	R24E	660' FSL/1980' FEL	I-149-IND-8837	Active	G414	G414	Navajo Nation
J131	4303715946	NW	NW	31	T40S	R25E	660' FNL/638' FWL	14-20-603-372	Active	J131	J131	Navajo Nation
B114	4303716032	NE	NW	14	T40S	R23E	660' FNL/1980' FWL	SL-070968	Shut-In			State of Utah
C214	4303716033	SW	NE	14	T40S	R23E	1890' FNL/1930' FEL	SL-070968	Shut-In			State of Utah
C411	4303716034	SW	SE	11	T40S	R23E	600' FSL/2010' FEL	SL-070968-B	P/A			State of Utah
C414	4303716035	SW	SE	14	T40S	R23E	760' FSL/2000' FEL	SL-070968	Active			State of Utah
D314	4303716038	NE	SE	14	T40S	R23E	1980' FSL/660' FEL	SL-070968	Active			State of Utah
E117	4303716049	NW	NW	17	T40S	R24E	520' FNL/645' FWL	I-149-IND-8835	Active	E117	E117	Navajo Nation
E120	4303716050	NW	NW	20	T40S	R24E	660' FNL/660' FWL	I-149-IND-8836	Active	E120	E120	Navajo Nation
E121	4303716051	NW	NW	21	T40S	R24E	660' FNL/760' FWL	I-149-IND-8836	Active	E121	E121	Navajo Nation
E126	4303716054	NW	NW	26	T40S	R24E	760' FNL/660' FWL	I-149-IND-8838	Active	E126	E126	Navajo Nation
E129	4303716055	NW	NW	29	T40S	R24E	660' FNL/660' FWL	14-20-603-4030	Active	E129	E129	Navajo Nation
E308	4303716060	NW	SW	8	T40S	R24E	1820' FSL/645' FWL	I-149-IND-8833	Active	E308	E308	Navajo Nation
E309	4303716061	NW	SW	9	T40S	R24E	1900' FSL/500' FWL	I-149-IND-8834	P/A			Navajo Nation
E317	4303716062	NW	SW	17	40S	24E	1980' FSL/660' FWL	I-149-IND-8835	Active	E317	E317	Navajo Nation
E318	4303716063	NW	SW	18	T40S	R24E	1980' FSL/660' FWL	SL-067807	Active	E318	E318	Navajo Nation
E319	4303716064	NW	SW	19	T40S	R24E	2040' FSL/680' FWL	I-149-IND-8836	P/A			Navajo Nation
E320	4303716065	NW	SW	20	T40S	R24E	2140' FSL/820' FWL	I-149-IND-8836	Active	E320	E320	Navajo Nation
E321	4303716066	NW	SW	21	T40S	R24E	2140' FSL/720' FWL	I-149-IND-8836	Active	E321	E321	Navajo Nation
E322	4303716067	NW	SW	22	T40S	R24E	1980' FSL/660' FWL	I-149-IND-8836	Active	E322	E322	Navajo Nation
E323	4303716068	NW	SW	23	T40S	R24E	1980' FSL/510' FWL	I-149-IND-8838	Active	E323	E323	Navajo Nation
E324	4303716069	NW	SW	24	T40S	R24E	1980' FSL/660' FWL	I-149-IND-8838	Active	E324	E324	Navajo Nation
E325	4303716070	NW	SW	25	T40S	R24E	1980' FSL/660' FWL	I-149-IND-8838	Active	E325	E325	Navajo Nation
E326	4303716071	NW	SW	26	T40S	R24E	1980' FSL/660' FWL	I-149-IND-8838	Active	E326	E326	Navajo Nation
F115	4303716074	NE	NW	15	T40S	R24E	690' FNL/2140' FWL	I-149-IND-8834	Active	F115	F115	Navajo Nation

F208	4303716076	SE	NW	8	T40S	R24E	2140' FNL/2050' FWL	I-149-IND-8833	Active	F208	F208	Navajo Nation
F219	4303716077	SE	NW	19	T40S	R24E	1820' FNL/2140' FWL	I-149-IND-8836	Active	F219	F219	Navajo Nation
F221	4303716078	SE	NW	21	T40S	R24E	1980' FNL/1980' FWL	I-149-IND-8836	Active	F221	F221	Navajo Nation
F223	4303716079	SE	NW	23	T40S	R24E	1980' FNL/1820' FWL	I-149-IND-8838	Active	F223	F223	Navajo Nation
F225	4303716080	SE	NW	25	T40S	R24E	2040' FNL/2080' FWL	I-149-IND-8838	Active	F225	F225	Navajo Nation
F409	4303716082	SE	SW	9	T40S	R24E	660' FSL/1980' FWL	I-149-IND-8834	Active	F409	F409	Navajo Nation
F421	4303716084	SE	SW	21	T40S	R24E	585' FSL/1990' FWL	I-149-IND-8836	Active	F421	F421	Navajo Nation
F422	4303716085	SE	SW	22	T40S	R24E	660' FSL/1980' FWL	I-149-IND-8836	Active	F422	F422	Navajo Nation
F423	4303716086	SE	SW	23	T40S	R24E	770' FSL/1955' FWL	I-149-IND-8838	Active	F423	F423	Navajo Nation
F424	4303716087	SE	SW	24	T40S	R24E	660' FSL/2100' FWL	I-149-IND-8838	Active	F424	F424	Navajo Nation
G117	4303716089	NW	NE	17	T40S	R24E	660' FNL/1980' FEL	I-149-IND-8835	Active	G117	G117	Navajo Nation
G118	4303716090	NW	NE	18	T40S	R24E	800' FNL/1910' FEL	I-149-IND-8835	Active	G118	G118	Navajo Nation
G119	4303716091	NW	NE	19	T40S	R24E	660' FNL/2140' FEL	I-149-IND-8836	Active	G119	G119	Navajo Nation
G120	4303716092	NW	NE	20	T40S	R24E	660' FNL/1980' FEL	I-149-IND-8833	Active	G120	G120	Navajo Nation
G125	4303716095	NW	NE	25	T40S	R24E	660' FNL/2140' FEL	I-149-IND-8838	Active	G125	G125	Navajo Nation
G129	4303716097	NW	NE	29	T40S	R24E	580' FNL/1905' FEL	14-20-603-4030	Active	G129	G129	Navajo Nation
G307	4303716100	NW	SE	7	T40S	R24E	1900' FSL/1995' FEL	SL-067807	Active	G307	G307	Navajo Nation
G308	4303716101	NW	SE	8	T40S	R24E	1975' FSL/1830' FEL	I-149-IND-8834	Active	G308	G308	Navajo Nation
G317	4303716103	NW	SE	17	T40S	R24E	1778' FSL/1900' FEL	I-149-IND-8835	Active	G317	G317	Navajo Nation
G318	4303716104	NW	SE	18	T40S	R24E	2125' FSL/1980' FEL	I-149-IND-8835	Active	G318	G318	Navajo Nation
G320	4303716105	NW	SE	20	T40S	R24E	1980' FSL/1980' FEL	I-149-IND-8836	Active	G320	G320	Navajo Nation
G324	4303716111	NW	SE	24	T40S	R24E	1980' FSL/1980' FEL	I-149-IND-8838	Active	G324	G324	Navajo Nation
G326	4303716113	NW	SE	26	T40S	R24E	1980' FSL/1980' FEL	I-149-IND-8838	Active	G326	G326	Navajo Nation
G415	4303716116	SW	SE	15	T40S	R24E	820' FSL/2400' FEL	I-149-IND-8834	Active	G415	G415	Navajo Nation
H122	4303716117	NE	NE	22	T40S	R24E	660' FNL/660' FEL	I-149-IND-8836	Active	H122	H122	Navajo Nation
H207	4303716118	SE	NE	7	T40S	R24E	1820' FNL/820' FEL	SL-067807	T/A			State of Utah
H208	4303716119	SE	NE	8	T40S	R24E	2140' FNL/660' FEL	I-149-IND-8833	Active	H208	H208	Navajo Nation
H218	4303716120	SE	NE	18	T40S	R24E	1980' FNL/660' FEL	I-149-IND-8835	Active	H218	H218	Navajo Nation
H219	4303716121	SE	NE	19	T40S	R24E	1945' FNL/607' FEL	I-149-IND-8836	Active	H219	H219	Navajo Nation
H221	4303716122	SE	NE	21	T40S	R24E	1980' FNL/660' FEL	I-149-IND-8836	Active	H221	H221	Navajo Nation
H223	4303716123	SE	NE	23	T40S	R24E	1820' FNL/730' FEL	I-149-IND-8838	Active	H223	H223	Navajo Nation
H225	4303716124	SE	NE	25	T40S	R24E	1980' FNL/660' FEL	I-149-IND-8838	Active	H225	H225	Navajo Nation
H410	4303716125	SE	SE	10	T40S	R24E	625' FSL/545' FEL	I-149-IND-8834	P/A			Navajo Nation
H422	4303716127	SE	SE	22	T40S	R24E	660' FSL/660' FEL	I-149-IND-8836	P/A			Navajo Nation
H423	4303716128	SE	SE	23	T40S	R24E	820' FSL/450' FEL	I-149-IND-8838	Active	H423	H423	Navajo Nation
H425	4303716129	SE	SE	25	T40S	R24E	660' FSL/660' FEL	I-149-IND-8838	Active	H425	H425	Navajo Nation
J129	4303716131	NW	NW	29	T40S	R25E	620' FNL/615' FWL	I-149-IND-8839	P/A			Navajo Nation
J130	4303716132	NW	NW	30	T40S	R25E	720' FNL/590' FEL	I-149-IND-8839	Shut-In	J130	J130	Navajo Nation
J330	4303716134	NW	SW	30	T40S	R25E	2060' FSL/800' FWL	I-149-IND-8839	Active	J330	J330	Navajo Nation
K230	4303716135	SE	NW	30	T40S	R25E	2075' FSL/2140' FWL	I-149-IND-8839	Shut-In	K230	K230	Navajo Nation
K430	4303716137	SE	SW	30	T40S	R25E	660' FSL/1980' FWL	I-149-IND-8839	Active	K430	K430	Navajo Nation
L330	4303716139	NW	SE	30	T40S	R25E	2120' FSL/1960' FEL	I-149-IND-8839	Active	L330	L330	Navajo Nation
L419	4303716140	SW	SE	19	T40S	R25E	660' FSL/1980' FEL	I-149-IND-8839	Active	L419	L419	Navajo Nation
M230	4303716141	SE	NE	30	T40S	R25E	1930' FNL/660' FEL	I-149-IND-8839	Active	M230	M230	Navajo Nation
E128	4303716222	NW	NW	28	T40S	R24E	660' FNL/660' FWL	14-20-603-2056	Active	E128	E128	Navajo Nation
F227	4303716223	SE	NW	27	T40S	R24E	1980' FNL/1980' FWL	14-20-603-2056	T/A			Navajo Nation
G128	4303716224	NW	NE	28	T40S	R24E	660' FNL/1980' FEL	14-20-603-2056	Shut-In	G128	G128	Navajo Nation

H228	4303716228	SE	NE	28	T40S	R24E	2080' FNL/560' FEL	14-20-603-2056	T/A			Navajo Nation
A124	4303716270	NW	NW	24	T40S	R23E	500' FNL/500' FWL	SL-0701010-C	Active			State of Utah
B123	4303716271	NE	NW	23	T40S	R23E	500' FNL/2140' FWL	SL-0701010	Active			State of Utah
B312	4303716272	NE	SW	12	T40S	R23E	3295' FNL/3348' FEL	SL-070968-A	Active	B312	B312	Navajo Nation
B314	4303716273	NE	SW	14	T40S	R23E	2030' FSL/2030' FWL	SL-070968	Active			State of Utah
C112	4303716274	NW	NE	12	T40S	R23E	658' FNL/1974' FEL	SL-070968-A	P/A			State of Utah
C124	4303716275	NW	NE	24	T40S	R23E	660' FNL/1980' FEL	SL-0701010-C	P/A			State of Utah
C223	4303716276	SW	NE	23	T40S	R23E	1820' FNL/1980' FEL	SL-0701010	P/A			State of Utah
D114	4303716277	NE	NE	14	T40S	R23E	660' FNL/760' FEL	SL-070968	Active			State of Utah
D212	4303716278	SE	NE	12	T40S	R23E	1860' FNL/656' FEL	SL-070968-A	Shut-In	D212	D212	Navajo Nation
D413	4303716279	SE	SE	13	T40S	R23E	660' FSL/661' FEL	SL-070968-A	Active			State of Utah
E119	4303716280	NW	NW	19	T40S	R24E	500' FNL/820' FWL	I-149-IND-8836	Active	E119	E119	Navajo Nation
E207	4303716283	SW	NW	7	T40S	R24E	2030' FNL 750 FWL		T/A	E207	E207	
E208	4303716284	SW	NW	8	T40S	R24E	1930' FNL/500' FWL	I-149-IND-8833	T/A			Navajo Nation
F116	4303716285	NE	NW	16	T40S	R24E	660' FNL/1980' FWL	ML-3156	Active	F116	F116	Navajo Nation
F217	4303716286	SE	NW	17	T40S	R24E	1890' FNL/1930' FWL	I-149-IND-8835	Active	F217	F217	Navajo Nation
F218	4303716287	SE	NW	18	T40S	R24E	1970' FNL/2060' FWL	I-149-IND-8835	Active	F218	F218	Navajo Nation
F220	4303716288	SE	NW	20	T40S	R24E	1980' FNL/1980' FWL	I-149-IND-8836	Active	F220	F220	Navajo Nation
F224	4303716289	SE	NW	24	T40S	R24E	1980' FNL/1980' FWL	I-149-IND-8838	Active	F224	F224	Navajo Nation
F226	4303716290	SE	NW	26	T40S	R24E	1950' FNL/1900' FWL	I-149-IND-8838	Active	F226	F226	Navajo Nation
F229	4303716292	SE	NW	29	T40S	R24E	2015' FNL/1930' FWL	14-20-603-4030	P/A	F229	F229	Navajo Nation
F235	4303716293	SE	NW	35	T40S	R24E	1825' FNL/2010' FWL	14-20-603-2059	Active	F235	F235	Navajo Nation
F236	4303716294	SE	NW	36	T40S	R24E	1980' FNL/1980' FWL	14-20-603-5444	Active	F236	F236	Navajo Nation
F311	4303716295	NE	SW	11	T40S	R24E	1820' FSL/1980' FWL	I-149-IND-8837	P/A			Navajo Nation
F315	4303716296	NE	SW	15	T40S	R24E	1980' FSL/2010' FWL	I-149-IND-8834	Active	F315	F315	Navajo Nation
F316	4303716297	NE	SW	16	T40S	R24E	2260' FSL/2140' FWL	ML-3156	Active	F316	F316	Navajo Nation
F408	4303716298	SE	SW	8	T40S	R24E	660' FSL/1980' FWL	I-149-IND-8833	Active	F408	F408	Navajo Nation
F417	4303716299	SE	SW	17	T40S	R24E	500' FSL/2140' FWL	I-149-IND-8835	Active	F417	F417	Navajo Nation
F420	4303716300	SE	SW	20	T40S	R24E	660' FSL/1980' FWL	I-149-IND-8836	Active	F420	F420	Navajo Nation
F425	4303716301	SE	SW	25	T40S	R24E	795' FSL/1960' FWL	I-149-IND-8838	Active	F425	F425	Navajo Nation
F426	4303716302	SE	SW	26	T40S	R24E	632' FSL/1867' FWL	I-149-IND-8838	P/A			Navajo Nation
F434	4303716303	SE	SW	34	T40S	R24E	815' FSL/1860' FWL	14-20-603-2056	P/A			Navajo Nation
F435	4303716304	SE	SW	35	T40S	R24E	820' FSL/1930' FWL	14-20-603-2059	T/A			Navajo Nation
G123	4303716306	NW	NE	23	T40S	R24E	660' FNL/1530' FEL	I-149-IND-8838	Active	G123	G123	Navajo Nation
G127	4303716307	NW	NE	27	T40S	R24E	660' FNL/1980' FEL	14-20-603-2056	Active	G127	G127	Navajo Nation
G319	4303716309	NW	SE	19	T40S	R24E	1920' FSL/2060' FEL	I-149-IND-8836	Active	G319	G319	Navajo Nation
H216	4303716312	SE	NE	16	T40S	R24E	3331' FSL/703' FEL	ML-3156	Active	H216	H216	Navajo Nation
H217	4303716313	SE	NE	17	T40S	R24E	2070' FNL/820' FEL	I-149-IND-8833	Active	H217	H217	Navajo Nation
H220	4303716314	SE	NE	20	T40S	R24E	2025' FNL/560' FEL	I-149-IND-8833	Active	H220	H220	Navajo Nation
H226	4303716316	SE	NE	26	T40S	R24E	1980' FNL/780' FEL	I-149-IND-8838	Active	H226	H226	Navajo Nation
H227	4303716317	SE	NE	27	T40S	R24E	1980' FNL/630' FEL	14-20-603-2056	Active	H227	H227	Navajo Nation
H229	4303716318	SE	NE	29	T40S	R24E	1820' FNL/660' FEL	14-20-603-4030	Shut-In	H229	H229	Navajo Nation
H234	4303716319	SE	NE	34	T40S	R24E	1980' FNL/660' FEL	14-20-603-2056	Active	H234	H234	Navajo Nation
H235	4303716320	SE	NE	35	T40S	R24E	2000' FNL/770' FEL	14-20-603-2059	Active	H235	H235	Navajo Nation
H407	4303716322	SE	SE	7	T40S	R24E	645' FSL/500' FEL	I-149-IND-8835	Active	H407	H407	Navajo Nation
H408	4303716323	SE	SE	8	T40S	R24E	500' FSL/530' FEL	I-149-IND-8834	Active	H408	H408	Navajo Nation
H417	4303716326	SE	SE	17	T40S	R24E	500' FSL/690' FEL	I-149-IND-8833	Active	H417	H417	Navajo Nation

H418	4303716327	SE	SE	18	T40S	R24E	660' FSL/660' FEL	I-149-IND-8835	Active	H418	H418	Navajo Nation
H419	4303716328	SE	SE	19	T40S	R24E	570' FSL/450' FEL	I-149-IND-8836	P/A			Navajo Nation
H420	4303716329	SE	SE	20	T40S	R24E	660' FSL/660' FEL	I-149-IND-8836	Active	H420	H420	Navajo Nation
H421	4303716330	SE	SE	21	T40S	R24E	500' FSL/750' FEL	I-149-IND-8836	Active	H421	H421	Navajo Nation
H424	4303716331	SE	SE	24	T40S	R24E	820' FSL/610' FEL	I-149-IND-8838	Active	H424	H424	Navajo Nation
H426	4303716332	SE	SE	26	T40S	R24E	710' FSL/510' FEL	I-149-IND-8838	Active	H426	H426	Navajo Nation
H427	4303716333	SE	SE	27	T40S	R24E	660' FSL/660' FEL	14-20-603-2056	Active	H427	H427	Navajo Nation
K231	4303716335	SE	NW	31	T40S	R25E	2014' FNL/2054' FWL	14-20-603-372A	Active	K231	K231	Navajo Nation
M430	4303716337	SE	SE	30	T40S	R25E	670' FSL/790' FEL	I-149-IND-8839	Active	M430	M430	Navajo Nation
E414	4303716421	SW	SW	14	T40S	R24E	750' FSL/620' FWL	I-149-IND-8837	Active	E414	E414	Navajo Nation
F114	4303716422	NE	NW	14	40S	24E	720' FNL/1870' FWL	I-149-IND-8839	Active	F114	F114	Navajo Nation
E127	4303716782	NW	NW	27	T40S	R24E	660' FNL/660' FWL	14-20-603-2056	P/A			Navajo Nation
H416	4303720230	SE	SE	16	T40S	R24E	150' FSL/660' FEL	ML-3156	Active	H416	H416	Navajo Nation
G322X	4303720231	NW	SE	22	T40S	R24E	1550' FSL/1720' FEL	I-149-IND-8836	Active	G322X	G322X	Navajo Nation
D412	4303730049	SE	SE	12	T40S	R23E	500' FSL/150' FEL	SL-070968-A	Active	D412	D412	Navajo Nation
E316	4303730094	NW	SW	16	T40S	R24E	2190' FSL/128' FWL	ML-3156	Active	E316	E316	Navajo Nation
G321X	4303730095	NW	SE	21	T40S	R24E	1900' FSL/1755' FEL	I-149-IND-8836	Shut-In	G321X	G321X	Navajo Nation
G316	4303730107	NW	SE	16	T40S	R24E	2320' FSL/1745' FEL	ML-3156	Active	G316	G316	Navajo Nation
C312	4303730112	NW	SE	12	T40S	R23E	1610' FSL/1800' FEL	SL-070968-A	Active	C312	C312	Navajo Nation
A113	4303730119	NW	NW	13	T40S	R23E	700' FNL/650' FWL	SL-070968-A	Active			State of Utah
E218	4303730137	SW	NW	18	T40S	R24E	1860' FNL/660' FWL	SL-067807	Active	E218	E218	Navajo Nation
F118	4303730155	NE	NW	18	T40S	R24E	619' FNL/2184' FWL	SL-067807	Active	F118	F118	Navajo Nation
D113	4303730174	NE	NE	13	T40S	R23E	578' FNL/619' FEL	SL-070968-A	Active			State of Utah
E407	4303730175	SW	SW	7	T40S	R24E	618' FSL/577' FWL	SL-067807	Active	E407	E407	Navajo Nation
E315	4303730213	NW	SW	15	T40S	R24E	2212' FSL/591' FWL	I-149-IND-8834	Active	E315	E315	Navajo Nation
E122	4303730215	NW	NW	22	T40S	R24E	528' FNL/660' FWL	I-149-IND-8836	Active	E122	E122	Navajo Nation
F123	4303730235	NE	NW	23	T40S	R24E	660' FNL/2046' FWL	I-149-IND-8838	Shut-In	F123	F123	Navajo Nation
B413	4303730297	SE	SW	13	T40S	R23E	660' FSL/1980' FWL	SL-070968-A	Active			State of Utah
A313	4303730299	NW	SW	13	T40S	R23E	1840' FSL/470' FWL	SL-070968-A	Active			State of Utah
H315	4303730312	NE	SE	15	T40S	R24E	1980' FSL/660' FEL	I-149-IND-8834	Active	H315	H315	Navajo Nation
F416	4303730333	SE	SW	16	T40S	R24E	1000' FSL/1980' FWL	ML-3156	Active	F416	F416	Navajo Nation
G121X	4303730335	NW	NE	21	T40S	R24E	790' FNL/1780' FEL	I-149-IND-8836	Active	G121X	G121X	Navajo Nation
G116	4303730344	NW	NE	16	T40S	R24E	660' FNL/1980' FEL	ML-3156	Active	G116	G116	Navajo Nation
G126X	4303730372	NW	NE	26	T40S	R24E	860' FNL/1780' FEL	I-149-IND-8838	Active	G126X	G126X	Navajo Nation
F222	4303730373	SE	NW	22	T40S	R24E	1920' FNL/1980' FWL	I-149-IND-8836	Active	F222	F222	Navajo Nation
G122	4303730425	NW	NE	22	T40S	R24E	570' FNL/1960' FEL	I-149-IND-8836	Active	G122	G122	Navajo Nation
H314X	4303731381	NE	SE	14	T40S	R24E	1950' FSL/570' FEL	I-149-IND-8837	Active	H314X	H314X	Navajo Nation

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

12/1/2004

FROM: (Old Operator):

N0210-Chevron USA, Inc.

PO Box 4791

Houston, TX 77210-4791

Phone: 1-(713) 752-7431

TO: (New Operator):

N2700-Resolute Natural Resources Company

1675 Broadway, Suite 1950

Denver, CO 80202

Phone: 1-(303) 534-4600

CA No.

Unit:

ANETH

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
ANETH UNIT H314X	14	400S	240E	4303731381	7000	Indian	WI	I
ANETH E-315	15	400S	240E	4303730213	99990	Indian	WI	A
ANETH H-315	15	400S	240E	4303730312	7000	Indian	WI	A
STATE THREE 21-16 (ANETH F-116)	16	400S	240E	4303716285	99990	State	WI	A
STATE THREE 23-16 (ANETH F-316)	16	400S	240E	4303716297	99990	State	WI	A
STATE THREE 42-16 (ANETH H-216)	16	400S	240E	4303716312	99990	State	WI	A
ANETH H-416	16	400S	240E	4303720230	99990	State	WI	A
ANETH E-316	16	400S	240E	4303730094	99990	State	WI	A
ANETH G-316	16	400S	240E	4303730107	99990	State	WI	A
ANETH F-416	16	400S	240E	4303730333	99990	State	WI	A
ANETH G-116	16	400S	240E	4303730344	99990	State	WI	A
ANETH G-321X	21	400S	240E	4303730095	99990	Indian	WI	A
ANETH G-121X	21	400S	240E	4303730335	99990	Indian	WI	A
ANETH G-322X	22	400S	240E	4303720231	99990	Indian	WI	A
ANETH E-122	22	400S	240E	4303730215	99990	Indian	WI	A
ANETH H-222	22	400S	240E	4303730242	99990	Indian	WI	A
ANETH F-222	22	400S	240E	4303730373	99990	Indian	WI	A
ANETH G-122	22	400S	240E	4303730425	99990	Indian	WI	A
ANETH F-123	23	400S	240E	4303730235	99990	Indian	WI	A
ANETH G-126X	26	400S	240E	4303730372	99990	Indian	WI	A
ANETH 27-A-1 (ANETH E-127)	27	400S	240E	4303716782	99990	Indian	WI	A

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 12/22/2004
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 12/13/2004
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 11/22/2004
- Is the new operator registered in the State of Utah: YES Business Number: 5733505-0143
- If **NO**, the operator was contacted on: _____
- (R649-9-2) Waste Management Plan has been received on: _____ requested
- Inspections of LA PA state/fee well sites complete on: 12/20/2004

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM not yet BIA not yet

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: not yet

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 12/29/2004
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 12/29/2004
3. Bond information entered in RBDMS on: n/a
4. Fee/State wells attached to bond in RBDMS on: n/a
5. Injection Projects to new operator in RBDMS on: separate list
6. Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: B001263

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: B001264

FEE & STATE WELL(S) BOND VERIFICATION:


1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number B001262
2. The **FORMER** operator has requested a release of liability from their bond on: not yet
The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

COMMENTS:


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: I-149-IND-8836
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
		7. UNIT or CA AGREEMENT NAME: ANETH
1. TYPE OF WELL Water Injection Well		8. WELL NAME and NUMBER: ANETH H-222
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		9. API NUMBER: 43037302420000
3. ADDRESS OF OPERATOR: 1675 Boradway Ste 1950 , Denver, CO, 80202		9. FIELD and POOL or WILDCAT: GREATER ANETH
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2096 FNL 0776 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 40.0S Range: 24.0E Meridian: S		COUNTY: SAN JUAN STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/12/2013 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute proposes to sidetrack the Aneth Unit H-222 to deepen the wellbore from 5555' to 7034' (MD), TVD = 5952'. Engineers and operations staff recommend this procedure to enhance the CO2 response within the injection area in Greater Aneth field. The workover should generate incremental production increase to justify the expense of the sidetrack. Drilling plan, including wellbore schematic, plat, topographic map and cut-away, as well as water permits for drilling water are attached.		
<div style="display: flex; justify-content: space-between;"> <div style="width: 30%;"> <p><i>Surf</i></p> <p>654093X</p> <p>4129159Y</p> <p>37.296298</p> <p>- 109.261456</p> </div> <div style="width: 30%; text-align: center;"> <p><i>BUL</i></p> <p>653836X</p> <p>4129480Y</p> <p>37.299228</p> <p>- 109.26428</p> </div> <div style="width: 30%; text-align: right;"> <p>Approved by the Utah Division of Oil, Gas and Mining</p> <p>Date: 04-12-13</p> <p>By: <i>[Signature]</i></p> </div> </div>		
NAME (PLEASE PRINT) Sherry Glass		PHONE NUMBER 303 573-4886
SIGNATURE N/A		TITLE Sr Regulatory Technician DATE 4/12/2013

T. 40 S., R. 24 E., S.L.M.**SURVEYOR'S STATEMENT:**

I, John A. Vukonich, of Farmington, New Mexico, hereby state: This plat was made from notes taken during an actual survey under my direct supervision on FEBRUARY 21, 2013, and it shows the location of ANETH UNIT H-22.

LEGEND

- ◆ SURFACE WELL LOCATION
- BOTTOM HOLE LOCATION
- ⊙ FOUND MONUMENT
- └ DENOTES 90° TIE



UTAH PLS No. 7219139-2201

DATE

EXHIBIT A

**PLAT OF PROPOSED WELL LOCATION
FOR
RESOLUTE NATURAL RESOURCES COMPANY**

P.O. BOX 3651
FARMINGTON, N.M.
(505) 334-0408

SCALE: 1" = 1000'**JOB No. 10450****DATE: 03/04/13**

**SURFACE: 2103' F/NL & 783' F/EL,
BOTTOM HOLE: 1036' F/NL & 1606' F/EL,
SECTION 22, T. 40 S., R. 24 E., SALT LAKE MERIDIAN
SAN JUAN COUNTY, UTAH**

Sidetrack
Aneth Unit H-222
2103' FNL & 783' FEL
Sec 22, T40S, R24E
San Juan County, Utah
API 43-037-30242

Formation Tops (KB 4,945)

Navajo	928'
Chinle	1,694'
DeChelley	2,832'
Organ Rock	2,930' (Est)
Hermosa	4,696'
Ismay	5,588'

Sidetrack Procedure (Proposed)


1. MIRU.
2. Mock MIT.
3. Pull injection equipment.
4. Run CBL & Csg Inspection Logs (5700' to Surface).
5. Set whipstock on CIBP (5562').
6. Drill 4-3/4" OH lateral from 5555' to 7034' (MD), (TVD = 5952'),
BHL: 1036' FNL & 1606' FEL of Sec. 22, T40S, R24E.
Note: Sfc Location: 2103' FNL & 783' FEL of Sec. 22, T40S, R24E
7. Acidize OH lateral w/ 5,000 gals of 20% HCL.
8. Run injection equipment.
9. Circulate packer fluid.
10. MIT

Sundry Number: 36692 API Well Number: 43037302420000

11.RWTI

RECEIVED: Apr. 12, 2013


**BEFORE DIGGING
CALL FOR UTILITY
LINE LOCATION!**



CUT	FILL	NET
879 Cu. Yd.	870 Cu. Yd.	9 Cu. Yd. (CUT)

NOTE:

THE EARTH QUANTITIES ON THIS DRAWING ARE ESTIMATED AND THE USE OF THIS IS AT THE RESPONSIBILITY OF THE USER.



A-A'

4950				
4940				
4930				
4920				
4910				

B-B'

4950				
4940				
4930				
4920				
4910				

C-C'

4950				
4940				
4930				
4920				
4910				

CROSS SECTIONS

HORIZONTAL: 1"=100'

VERTICAL: 1"=50'

EXHIBIT 1A

RESOLUTE
NATURAL RESOURCES

LEASE: **ANETH UNIT H-222**

FOOTAGES: **2103' FNL, 783' FEL (SURFACE)**
1036' FNL, 1606' FEL (BOTTOM HOLE)

SEC. **22** TWN. **40 S** RNG. **24 E** S.L.M.

LATITUDE: **N 37.2962265°** LONGITUDE: **W 109.2615504°**

ELEVATION: **4935**

SURVEYED: 02/21/13

REV. DATE:

APP. BY J.A.V.

DRAWN BY: H.S.


DATE DRAWN: 03/04/13

FILE NAME: 10450C01



P.O. BOX 3651
FARMINGTON, NM 87499
OFFICE: (505) 334-0408

Sundry Number: 36692 API Well Number: 43037302420000



**PROPOSED WELL LOCATION FOR
RESOLUTE NATURAL RESOURCES
ANETH UNIT H-222**

P.O. BOX 3651 FARMINGTON, N.M. (505) 334-0408	SCALE: 1" = 3000'	EXISTING ROAD  ACCESS/EGRESS 	EXHIBIT 2A
	JOB No. 10450		
	DATE: 03/04/13		


RESOLUTE

NATURAL RESOURCES

Tubing

Well Name: H222 Aneth Unit

API Number	Surface Legal Location	Section	Township	Range	Well Spud Date/Time	Field Name	State/Province	Working interest
43037302420000	SE NE	22	40S	24E		Aneth	Utah	61.77 Edit



Tubing

Tubing Description				Set Depth (ftKB)		Run Date		Pull Date		Edit
Tubing - Injection				5,521.9		7/13/2011				
jts	Item Description	OD (in)	ID (in)	Wt (lbs/ft)	Grade	Top Thread	Len (ft)	Top (ftKB)	Btm (ft)	Edit
1	Tubing Hanger	6	2.441	6.50	J-55		0.68	12.0	12.7	
1	Tubing TK FL	2 7/8	2.441	6.50	J-55		32.45	12.7	45.1	
1	Tubing Pup Joint 8', 6' TK FL	2 7/8	2.441	6.50	J-55		14.22	45.1	59.3	
1	Tubing TK FL 167 jts	2 7/8	2.441	6.50	J-55		5,420....	59.3	5,480.2	
1	Cross Over	3.67					0.62	5,480.2	5,480.8	
1	On-Off Tool T-2	4 1/2					1.73	5,480.8	5,482.5	
1	Packer AS1X	4 5/8					7.25	5,482.5	5,489.8	
1	Profile Nipple 1.78 R	3.06					1.00	5,489.8	5,490.8	
1	Tubing DuraSeal	2 3/8	1.995	4.60	J-55		31.15	5,490.8	5,521.9	


RESOLUTE

NATURAL RESOURCES

SCHEMATIC

Well Name: H222 Aneth Unit

API Number 43037302420000		Surface Legal Location SE NE		Section 22	Township 40S	Range 24E	Well Spud Date/Time	Field Name Aneth	State/Province Utah	Edit
Original KB Elevation (ft) 12.00		KB Ground Elevation (ft)			Total Depth (ft) (KB) 5,935.0			PBD (ft) (KB) Original Hole - 5839.0		



Sundry Number: 36692 API Well Number: 43037302420000

Navajo Department of Water Resources
Water Code Administration
P.O. Box 678
Fort Defiance, Arizona 86504
Ph. No. (928) 729-4132/Fax No. (928) 729-4421

APPROVED

WATER USE PERMIT

WUP NO: **06.0015**

VALID FROM **DEC 29 2005** to **DEC 29 2010**

NOTE: This permit is valid only upon signature of the Department of Water Resources Director. Please read Water Use Permit information sheet before completing this form.

APPLICANT: <u>Resolute Natural Resources</u>	
LAST NAME	FIRST, OR COMPANY NAME
MAILING ADDRESS: <u>Post Office Box 800</u>	
CITY: <u>Montezuma Creek</u>	STATE: <u>Utah</u> ZIP CODE: <u>84534</u>
CONTACT PERSON: <u>Roger Atcitty</u>	TELEPHONE NO: <u>435-651-3682 X-103</u>
Fax #: <u>435-651-3276</u>	
DATE RECEIVED: <u>NOV 23 2005</u>	DATE COMPLETED: <u>JAN 04 2006</u>
\$25.00 Filing Fee Received	Receipt No. _____ Initial <u>[Signature]</u>

IDENTIFIED WATER SOURCE TO BE USED			
() Spring No: _____ () Stream Name: _____			
() Stockpond Name/No: _____ () Lake/Reservoir Name: _____			
<input checked="" type="checkbox"/> Well No: <u>CUSA WW #15</u> () Injection Well No: _____			
Amount of water requested: <u>1,000 acre-ft</u>			
() Other Description/Name: _____ Grazing District: <u>12</u>			
Chapter: <u>Aneth</u> Chapter Code: <u>ANET</u>			
State:	() AZ/Arizona	() NM/New Mexico	<input checked="" type="checkbox"/> UT/Utah
County:	() AP/Apache	() MK/McKinley	<input checked="" type="checkbox"/> SJ/San Juan
	() NA/Navajo	() VL/Valencia	() KA/Kane
	() CO/Coconino	() BL/Bernalillo	
		() SD/Sandoval	
		() SO/Socorro	
		() RA/Rio Arriba	
		() SA/San Juan	
Quad. No: (7.5 min. Series) <u>4648</u>			
UTM COORDINATES: X (East) <u>648885</u> Y (North) <u>4125.345</u> ZONE <u>12</u>			
NE SE SW NW / NE SE SW NW / NE SE SW NW <u>31</u> <u>40S</u> <u>24E</u>			
10 Acre 40 Acre 160 Acre Section Township Range			

LAND STATUS

☒ TRUST ☐ FEE ☐ LEASE ☐ ALLOTMENT ☐ OTHER
WATERSHED NAME: San Juan River USGS WATERSHED CODE NO. 14080201

CONSUMPTIVE WATER USE NEEDED FOR

PRIMARY:

☐ Domestic ☐ Recreational
☐ Municipal ☐ Industrial
☐ Livestock ☐ Mining
☐ Irrigation Agriculture ☐ Commercial
☐ Wildlife and Fish ☒ Other Oil and Gas Production

DOMESTIC/MUNICIPAL:

Number of People: _____ Number of Homes: _____ Others: _____

TYPE OF LIVESTOCK:

☐ Horses No: _____ ☐ Goats No: _____
☐ Cattle No: _____ ☐ Sheep No: _____
☐ Other: _____ ☐ No: _____

N/A

TYPE OF CROPS:

☐ Row (ie., corn) Acres _____
☐ Forage-Hay-Pasture Acres _____
☐ Small Grains Acres _____
☐ Horticulture (ie., Fruits & Vegetables) Acres _____

N/A

TYPE OF WILDLIFE:

☐ Fish No: _____ ☐ Small Game No: _____
☐ Large Game No: _____ ☐ Birds No: _____
☐ Others No: _____

N/A

IF WATER IS USED FOR INDUSTRIAL OR MINING PURPOSES, ATTACH WATER SUPPLY PLAN
DESCRIBING SOURCE AND METHODS OF DIVERSION, CONVEYANCE AND USES.

SEASON OF MAXIMUM USE: ☒ Spring ☒ Summer ☒ Fall ☒ Winter

MAXIMUM RATE OF USE: 87.5 ☒ GPM ☐ CFS

EXPECTED DATE WATER USAGE TO BEGIN: 1/1/98 (renewed 1/1/03)

EXPECTED VOLUME OF WATER TO BE USED: 141 ac/ft (_____ gallons)

METHOD OF WATER DIVERSION:

☐ Instream Pump ☐ Gate or Gravity Flow
☒ Other: pump located at well

METHOD OF WATER CONVEYANCE:

☐ Ditch ☐ Canal ☒ Pipeline ☐ Truck
☐ Other: _____

ATTACH AN 8 1/2" X 11" MAP SHOWING EXACT LOCATION OF IDENTIFIED WATER SOURCE AND
SCENARIO/ LOCATION OF WHERE WATER IS TO BE USED.

RETURN FLOW OR DISCHARGE

AMOUNT OF WATER: N/A METHOD: ☐ Direct
☐ GPM ☐ CFS ☐ GPD ☐ Indirect
☐ Injection

IS DISCHARGE TREATED ☐ YES ☐ NO

IS QUALITY AFFECTED ☐ YES ☐ NO

FEDERAL/UIC PERMIT: N/A IS TEMPERATURE AFFECTED ☐ YES ☐ NO

NPDES PERMIT NUMBER: N/A

06.00

CONDITIONS

1. Purpose of definition "Department" means the Navajo Nation Department of Water Resources and "Permittee" means Resolute Natural Resources (Formerly Chevron U.S.A. Inc.) and its successors.
2. Permittee agrees to comply with the terms and conditions of the Water Use Permit and the Navajo Nation Water Code. Permittee understands and agrees that failure to comply with the permit shall result in forfeiture of this permit.
3. This permit may be revoked if:
 - A. Permittee is not in compliance with any conditions set forth in this permit.
 - B. Permittee is in violation of any provision of the Navajo Nation Water Code.
 - C. Insufficient water supplies are present for whatever reason or term.
 - D. For any other due cause as a result of negative findings from investigation that is performed by both Department and Permittee.
4. The total quantity of water withdrawn by the Permittee from all water supply wells in the alluvium of San Juan River for the secondary or tertiary recovery of oil shall not exceed 1,000 acre-feet in any year.
5. Permit is valid from January 1, 2006 through December 31, 2010 and shall expire on December 31, 2010 or at the completion of the proposed project or required water usage, whichever comes first. Permittee does not have authority to transfer, convey, or allocate the water subject to this permit to any third party or for any other to transfer, convey, or allocate the water subject to this permit to any third party or for any other project not specified herein. It is further agreed between the parties that this permit does not give the Permittee the right to haul water for hire on the Navajo Reservation, or on land subject to the jurisdiction of the Navajo Nation.
6. Permittee agrees to pay a water use fee of \$1,000.00 (one thousand dollars) per water supply well per year. A lump sum payment will be paid at the end of each year for anticipated water use for the coming year, beginning with 2006. Thereafter payment may be made in advance. The water use fee will increase by 100.00 (one hundred dollars) per water supply well per year in the event that the average posted price for West Texas Intermediate Crude Oil exceeds \$30.00 (thirty dollars) per barrel for more than 6 (six) months in any year. The Permittee will pay the additional amount to the Department with the next payment, if the said change in posted price occurred in the previous advance payment. A credit may be given to the Permittee for the amount paid in advance, if the water use fee for similar use is lowered by the Resources Committee. No amount of money will be refunded to the Permittee. The credited amount will be carried over to the next payment owed to the Navajo Nation. Permittee will pay the amount due in the beginning of each year to the Water Code Administration of the Department. Payment plans may be arranged between both parties in a written agreement.
7. Permittee agrees to provide water well development support to affected Chapters by paying directly to each Chapter \$250.00 (two hundred fifty dollars) per water well per year for wells located within each Chapter's boundaries. Permittee shall inform the Department of the payment as soon as the payment is made.
8. Permittee agrees to submit meter readings or other evidence showing the quantity of water withdrawn pursuant to this permit to the Water Code Administrator on a quarterly basis.
9. The Permittee shall monitor the effects of water use of the alluvial after by measuring static (non-pumping) water levels in at least three (3) of the water supply wells on a quarterly basis, and shall submit this water level data to the Department together with the information required in Condition 8. The Navajo Nation reserves the right to this permit due to adverse impacts on the water resources of the Navajo Nation resulting from the Permittee's activities, as determined by the Department.
10. The Navajo Nation may revoke this permit upon any breach by giving the Permittee notice of such revocation in writing no less than ten (10) days prior to the effective date of revocation, provided that if the Permittee remedies any such breach within said ten (10) day periods, the permit will remain in effect. Said notice shall state the grounds upon which the revocation is being made.

06.0015

11. Permittee agrees to obtain a separate Water Use Permit for each point of withdrawal of water prior to making use of any additional water source.
12. Permittee agrees to hold harmless and indemnify the Navajo Nation against any and all losses, costs, damages, claims, expenses or other liability whatsoever, rising out of, or connected with Permittee's services under this permit including but not limited to, any accident or injury to person or property.
13. All disputes arising from the subject matter of this permit or the performance thereof will be settled in the Navajo Nation Courts and under the laws of the Navajo Nation. Nothing herein shall be construed as a waiver of the sovereign immunity of the Navajo Nation, pursuant to 1 N.T.C. §351 et seq.
14. Permittee agrees to maintain the immediate area in a safe and sanitary manner, free of unnecessary debris.
15. Authorization granted under this permit is only for the stated use of the indicated water source location. Permittee is responsible for obtaining any applicable permit from the appropriate department/agency that may be required for the proposed work.
16. If permittee hires sub-contractors to haul water covered by Water Use Permit, Permittee must notify the Navajo Water Code Administration of sub-contractors in writing.
17. It is agreed that the Department reserves the right to limit the quantity of water that can be taken under this permit to the above stated amount or less and will give the Permittee 30 day notice before such action is imposed. Such limitations will be imposed at the discretion of the Department.
18. Permittee agrees to allow reasonable entry upon their premises by Navajo Nation Employees engaged in the administration of this permit.
19. The Department will allow the Permittee to continue to make irrigation water available to the Whitehorse High School, Montezuma Creek, Utah, and to those local residents currently using the water for livestock usage.
20. In the event the Department or the Navajo Nation subsequently reduces the cost of water use permits to other oil and gas industry members, then the Department or Navajo Nation shall grant to the Permittee a credit for the amounts that it has previously paid and apply such credit to future financial obligations owed by Texaco to the Nation for water use.
21. The permit shall be renewable each year for the next 5 years under the same terms and conditions as set forth herein.

Permittee's Signature

[Signature]

Date

Nov. 23-05

OFFICIAL USE ONLY

Recommendation:

☒ Yes () No

[Signature]
Water Code Administrator

Date

01-03-06

☒ Yes () No

[Signature]
Technical Reviewer

Date

12-29-05

Approved/Disapproved:

[Signature]
Director, Department of Water Resources

Date

1-4-06

If Disapproved State Reasons:

Sundry Number: 36692 API Well Number: 43037302420000

! /ajo Department of Water Resour
Water Code Administration
P.O. Box 678
Fort Defiance, Arizona 86504
Ph. No. (928) 729-4132/Fax No. (928) 729-4421

APPROVED

WATER USE PERMIT

P-06.0016

WUP NO: DEC 29 2005

VALID FROM DEC 29 2010 to

NOTE: This permit is valid only upon signature of the Department of Water Resources Director. Please read Water Use Permit information sheet before completing this form.

APPLICANT: <u>Resolute Natural Resources</u>	
LAST NAME	FIRST; OR COMPANY NAME
MAILING ADDRESS: <u>Post Office Box 800</u>	
CITY: <u>Montezuma Creek</u>	STATE: <u>Utah</u> ZIP CODE: <u>84534</u>
CONTACT PERSON: <u>Roger Atcitty</u>	TELEPHONE NO: <u>435-651-3682 X-103</u>
Fax #: <u>435-651-3276</u>	
DATE RECEIVED: <u>NOV 23 2005</u>	DATE COMPLETED <u>JAN 04 2006</u>
\$25.00 Filing Fee Received	Receipt No. Initial <u>[Signature]</u>

IDENTIFIED WATER SOURCE TO BE USED		
() Spring No: _____ () Stream Name: _____		
() Stockpond Name/No: _____ () Lake/Reservoir Name: _____		
X Well No: <u>CUSA WW #16</u> () Injection Well No: _____		
Amount of water requested: <u>1,000 acre-ft</u>		
() Other Description/Name: _____ Grazing District: <u>12</u>		
Chapter: <u>Aneth</u> Chapter Code: <u>ANET</u>		
State:	() AZ/Arizona	() NM/New Mexico
County:	() AP/Apache	() MK/McKinley
	() NA/Navajo	() VL/Valencia
	() CO/Coconino	() BL/Bernalillo
		() SD/Sandoval
		() SO/Socorro
		() RA/Rio Arriba
		() SA/San Juan
Quad. No: (7.5 min. Series) <u>4648</u>		
UTM COORDINATES: X (East) <u>648925</u> Y (North) <u>4125290</u> ZONE <u>12</u>		
NE SE SW NW / NE SE SW NW / NE SE SW NW		
10 Acre 40 Acre 160 Acre Section 31 Township 40S Range 24E		

LAND STATUS

☒ TRUST ☐ FEE ☐ LEASE ☐ ALLOTMENT ☐ OTHER
WATERSHED NAME: San Juan River USGS WATERSHED CODE NO. 14080201

CONSUMPTIVE WATER USE NEEDED FOR

PRIMARY:

☐ Domestic ☐ Recreational
☐ Municipal ☐ Industrial
☐ Livestock ☐ Mining
☐ Irrigation Agriculture ☐ Commercial
☐ Wildlife and Fish ☒ Other Oil and Gas Production

DOMESTIC/MUNICIPAL:

Number of People: _____ Number of Homes: _____ Others: _____

TYPE OF LIVESTOCK: ☐ Horses No: _____ ☐ Goats No: _____
N/A ☐ Cattle No: _____ ☐ Sheep No: _____
☐ Other: _____ ☐ No: _____

TYPE OF CROPS: ☐ Row (ie., corn) Acres _____
N/A ☐ Forage-Hay-Pasture Acres _____
☐ Small Grains Acres _____
☐ Horticulture (ie., Fruits & Vegetables) Acres _____

TYPE OF WILDLIFE: ☐ Fish No: _____ ☐ Small Game No: _____
N/A ☐ Large Game No: _____ ☐ Birds No: _____
☐ Others No: _____

IF WATER IS USED FOR INDUSTRIAL OR MINING PURPOSES, ATTACH WATER SUPPLY PLAN
DESCRIBING SOURCE AND METHODS OF DIVERSION, CONVEYANCE AND USES.

SEASON OF MAXIMUM USE: ☒ Spring ☒ Summer ☒ Fall ☒ Winter

MAXIMUM RATE OF USE: 87.5 ☒ GPM ☐ CFS

EXPECTED DATE WATER USAGE TO BEGIN: 1/1/98 (renewed 1/1/03)

EXPECTED VOLUME OF WATER TO BE USED: 141 ac/ft (_____ gallons)

METHOD OF WATER DIVERSION: ☐ Instream Pump ☐ Gate or Gravity Flow
☒ Other: pump located at well

METHOD OF WATER CONVEYANCE: ☐ Ditch ☐ Canal ☒ Pipeline ☐ Truck
☐ Other: _____

ATTACH AN 8 1/2" X 11" MAP SHOWING EXACT LOCATION OF IDENTIFIED WATER SOURCE AND
SCENARIO/LOCATION OF WHERE WATER IS TO BE USED.


AMOUNT OF WATER: N/A RETURN FLOW OR DISCHARGE METHOD: ☐ Direct
☐ GPM ☐ CFS ☐ GPD ☐ Indirect
☐ Injection
IS DISCHARGE TREATED ☐ YES ☐ NO
IS QUALITY AFFECTED ☐ YES ☐ NO IS TEMPERATURE AFFECTED ☐ YES ☐ NO
FEDERAL/UIC PERMIT: N/A NPDES PERMIT NUMBER: N/A

CONDITIONS

1. Purpose of definition "Department" means the Navajo Nation Department of Water Resources and "Permittee" means Resolute Natural Resources (Formerly Chevron U.S.A. Inc.) and its successors.
2. Permittee agrees to comply with the terms and conditions of the Water Use Permit and the Navajo Nation Water Code. Permittee understands and agrees that failure to comply with the permit shall result in forfeiture of this permit.
3. This permit may be revoked if:
 - A. Permittee is not in compliance with any conditions set forth in this permit.
 - B. Permittee is in violation of any provision of the Navajo Nation Water Code.
 - C. Insufficient water supplies are present for whatever reason or term.
 - D. For any other due cause as a result of negative findings from investigation that is performed by both Department and Permittee.
4. The total quantity of water withdrawn by the Permittee from all water supply wells in the alluvium of San Juan River for the secondary or tertiary recovery of oil shall not exceed 1,000 acre-feet in any year.
5. Permit is valid from January 1, 2006 through December 31, 2010 and shall expire on December 31, 2010 or at the completion of the proposed project or required water usage, whichever comes first. Permittee does not have authority to transfer, convey, or allocate the water subject to this permit to any third party or for any other to transfer, convey, or allocate the water subject to this permit to any third party or for any other project not specified herein. It is further agreed between the parties that this permit does not give the Permittee the right to haul water for hire on the Navajo Reservation, or on land subject to the jurisdiction of the Navajo Nation.
6. Permittee agrees to pay a water use fee of \$1,000.00 (one thousand dollars) per water supply well per year. A lump sum payment will be paid at the end of each year for anticipated water use for the coming year, beginning with 2006. Thereafter payment may be made in advance. The water use fee will increase by 100.00 (one hundred dollars) per water supply well per year in the event that the average posted price for West Texas Intermediate Crude Oil exceeds \$30.00 (thirty dollars) per barrel for more than 6 (six) months in any year. The Permittee will pay the additional amount to the Department with the next payment, if the said change in posted price occurred in the previous advance payment. A credit may be given to the Permittee for the amount paid in advance, if the water use fee for similar use is lowered by the Resources Committee. No amount of money will be refunded to the Permittee. The credited amount will be carried over to the next payment owed to the Navajo Nation. Permittee will pay the amount due in the beginning of each year to the Water Code Administration of the Department. Payment plans may be arranged between both parties in a written agreement.
7. Permittee agrees to provide water well development support to affected Chapters by paying directly to each Chapter \$250.00 (two hundred fifty dollars) per water well per year for wells located within each Chapter's boundaries. Permittee shall inform the Department of the payment as soon as the payment is made.
8. Permittee agrees to submit meter readings or other evidence showing the quantity of water withdrawn pursuant to this permit to the Water Code Administrator on a quarterly basis.
9. The Permittee shall monitor the effects of water use of the alluvial area by measuring static (non-pumping) water levels in at least three (3) of the water supply wells on a quarterly basis, and shall submit this water level data to the Department together with the information required in Condition 8. The Navajo Nation reserves the right to this permit due to adverse impacts on the water resources of the Navajo Nation resulting from the Permittee's activities, as determined by the Department.
10. The Navajo Nation may revoke this permit upon any breach by giving the Permittee notice of such revocation in writing no less than ten (10) days prior to the effective date of revocation, provided that if the Permittee remedies any such breach within said ten (10) day periods, the permit will remain in effect. Said notice shall state the grounds upon which the revocation is being made.

11. Permittee agrees to obtain a separate Water Use Permit for each point of withdrawal of water prior to making use of any additional water source.
12. Permittee agrees to hold harmless and indemnify the Navajo Nation against any and all losses, costs, damages, claims, expenses or other liability whatsoever, rising out of, or connected with Permittee's services under this permit including but not limited to, any accident or injury to person or property.
13. All disputes arising from the subject matter of this permit or the performance thereof will be settled in the Navajo Nation Courts and under the laws of the Navajo Nation. Nothing herein shall be construed as a waiver of the sovereign immunity of the Navajo Nation, pursuant to 1 N.T.C. §351 et seq.
14. Permittee agrees to maintain the immediate area in a safe and sanitary manner, free of unnecessary debris.
15. Authorization granted under this permit is only for the stated use of the indicated water source location. Permittee is responsible for obtaining any applicable permit from the appropriate department/agency that may be required for the proposed work.
16. If permittee hires sub-contractors to haul water covered by Water Use Permit, Permittee must notify the Navajo Water Code Administration of sub-contractors in writing.
17. It is agreed that the Department reserves the right to limit the quantity of water that can be taken under this permit to the above stated amount or less and will give the Permittee 30 day notice before such action is imposed. Such limitations will be imposed at the discretion of the Department.
18. Permittee agrees to allow reasonable entry upon their premises by Navajo Nation Employees engaged in the administration of this permit.
19. The Department will allow the Permittee to continue to make irrigation water available to the Whitehorse High School, Montezuma Creek, Utah, and to those local residents currently using the water for livestock usage.
20. In the event the Department or the Navajo Nation subsequently reduces the cost of water use permits to other oil and gas industry members, then the Department or Navajo Nation shall grant to the Permittee a credit for the amounts that it has previously paid and apply such credit to future financial obligations owed by Texaco to the Nation for water use.
21. The permit shall be renewable each year for the next 5 years under the same terms and conditions as set forth herein.

Permittee's Signature




Date

NW. 23-05

OFFICIAL USE ONLY

Recommendation:

☒ Yes () No
Water Code Administrator

Date

01-03-06

☒ Yes () No
Technical Reviewer

Date

12-29-05

Approved/Disapproved:


Director, Department of Water Resources

Date

1-4-06

If Disapproved State Reasons:

Sundry Number: 36692 API Well Number: 43037302420000

Navajo Department of Water Resources
Water Code Administration
P.O. Box 678
Fort Defiance, Arizona 86504
Ph. No. (928) 729-4132/Fax No. (928) 729-4421

APPROVED

WATER USE PERMIT

WUP NO: **06.0017**

DEC 29 2005

VALID FROM DEC 29 2005 to DEC 29 2010

NOTE: This permit is valid only upon signature of the Department of Water Resources Director. Please read Water Use Permit information sheet before completing this form.

APPLICANT: <u>Resolute Natural Resources</u>	
LAST NAME	FIRST; OR COMPANY NAME
MAILING ADDRESS: <u>Post Office Box 800</u>	
CITY: <u>Montezuma Creek</u>	STATE: <u>Utah</u> ZIP CODE: <u>84534</u>
CONTACT PERSON: <u>Roger Atcitty</u>	TELEPHONE NO: <u>435-651-3682 X-103</u>
Fax #: <u>435-651-3276</u>	
DATE RECEIVED: <u>NOV 23 2005</u>	DATE COMPLETED <u>JAN 04 2006</u>
\$25.00 Filing Fee Received	Receipt No. <u> </u> Initial <u>JA</u>

IDENTIFIED WATER SOURCE TO BE USED			
() Spring No: <u> </u>		() Stream Name: <u> </u>	
() Stockpond Name/No: <u> </u>		() Lake/Reservoir Name: <u> </u>	
X Well No: <u>CUSA WW #17</u>		() Injection Well No: <u> </u>	
Amount of water requested: <u>1,000 acre-ft</u>			
() Other Description/Name: <u> </u>		Grazing District: <u>12</u>	
Chapter: <u>Aneth</u>		Chapter Code: <u>ANET</u>	
State:	() AZ/Arizona	() NM/New Mexico	(x) UT/Utah
County:	() AP/Apache	() MK/McKinley	(x) SJ/San Juan
	() NA/Navajo	() VL/Valencia	() KA/Kane
	() CO/Coconino	() BL/Bernalillo	
		() SD/Sandoval	
		() SO/Socorro	
		() RA/Rio Arriba	
		() SA/San Juan	
Quad. No: (7.5 min. Series) <u>4648</u>			
UTM COORDINATES: X (East) <u>648980</u>		Y (North) <u>4125255</u>	ZONE <u>12</u>
NE SE SW NW / NE SE SW NW / NE SE SW NW		<u>31</u>	<u>40S</u>
<u>10 Acre</u>		<u>40 Acre</u>	<u>160 Acre</u>
<u>Section</u>		<u>Township</u>	<u>Range</u>

LAND STATUS

☒ TRUST ☐ FEE ☐ LEASE ☐ ALLOTMENT ☐ OTHER
WATERSHED NAME: San Juan River USGS WATERSHED CODE NO. 14080201

CONSUMPTIVE WATER USE NEEDED FOR

PRIMARY:
☐ Domestic ☐ Recreational
☐ Municipal ☐ Industrial
☐ Livestock ☐ Mining
☐ Irrigation Agriculture ☐ Commercial
☐ Wildlife and Fish ☒ Other Oil and Gas Production

DOMESTIC/MUNICIPAL:
Number of People: Number of Homes: Others:

TYPE OF LIVESTOCK: ☐ Horses No: ☐ Goats No:
N/A ☐ Cattle No: ☐ Sheep No:
☐ Other: ☐ No:

TYPE OF CROPS: ☐ Row (ie., corn) Acres
N/A ☐ Forage-Hay-Pasture Acres
☐ Small Grains Acres
☐ Horticulture (ie., Fruits & Vegetables) Acres

TYPE OF WILDLIFE: ☐ Fish No: ☐ Small Game No:
N/A ☐ Large Game No: ☐ Birds No:
☐ Others No:

IF WATER IS USED FOR INDUSTRIAL OR MINING PURPOSES, ATTACH WATER SUPPLY PLAN
DESCRIBING SOURCE AND METHODS OF DIVERSION, CONVEYANCE AND USES.

SEASON OF MAXIMUM USE: ☒ Spring ☒ Summer ☒ Fall ☒ Winter
MAXIMUM RATE OF USE: 87.5 ☒ GPM ☐ CFS
EXPECTED DATE WATER USAGE TO BEGIN: 1/1/98 (renewed 1/1/03)
EXPECTED VOLUME OF WATER TO BE USED: 141 ac/ft (gallons)
METHOD OF WATER DIVERSION: ☐ Instream Pump ☐ Gate or Gravity Flow
☒ Other: pump located at well
METHOD OF WATER CONVEYANCE: ☐ Ditch ☐ Canal ☒ Pipeline ☐ Truck
☐ Other:

ATTACH AN 8 1/2" X 11" MAP SHOWING EXACT LOCATION OF IDENTIFIED WATER SOURCE AND
SCENARIO/LOCATION OF WHERE WATER IS TO BE USED.

RETURN FLOW OR DISCHARGE

AMOUNT OF WATER: N/A METHOD: ☐ Direct
☐ GPM ☐ CFS ☐ GPD ☐ Indirect
☐ Injection
IS DISCHARGE TREATED ☐ YES ☐ NO
IS QUALITY AFFECTED ☐ YES ☐ NO IS TEMPERATURE AFFECTED ☐ YES ☐ NO
FEDERAL/UC PERMIT: N/A NPDES PERMIT NUMBER: N/A

CONDITIONS

1. Purpose of definition "Department" means the Navajo Nation Department of Water Resources and "Permittee" means Resolute Natural Resources (Formerly Chevron U.S.A. Inc.) and its successors.
2. Permittee agrees to comply with the terms and conditions of the Water Use Permit and the Navajo Nation Water Code. Permittee understands and agrees that failure to comply with the permit shall result in forfeiture of this permit.
3. This permit may be revoked if:
 - A. Permittee is not in compliance with any conditions set forth in this permit.
 - B. Permittee is in violation of any provision of the Navajo Nation Water Code.
 - C. Insufficient water supplies are present for whatever reason or term.
 - D. For any other due cause as a result of negative findings from investigation that is performed by both Department and Permittee.
4. The total quantity of water withdrawn by the Permittee from all water supply wells in the alluvium of San Juan River for the secondary or tertiary recovery of oil shall not exceed 1,000 acre-feet in any year.
5. Permit is valid from January 1, 2006 through December 31, 2010 and shall expire on December 31, 2010 or at the completion of the proposed project or required water usage, whichever comes first. Permittee does not have authority to transfer, convey, or allocate the water subject to this permit to any third party or for any other to transfer, convey, or allocate the water subject to this permit to any third party or for any other project not specified herein. It is further agreed between the parties that this permit does not give the Permittee the right to haul water for hire on the Navajo Reservation, or on land subject to the jurisdiction of the Navajo Nation.
6. Permittee agrees to pay a water use fee of \$1,000.00 (one thousand dollars) per water supply well per year. A lump sum payment will be paid at the end of each year for anticipated water use for the coming year, beginning with 2006. Thereafter payment may be made in advance. The water use fee will increase by 100.00 (one hundred dollars) per water supply well per year in the event that the average posted price for West Texas Intermediate Crude Oil exceeds \$30.00 (thirty dollars) per barrel for more than 6 (six) months in any year. The Permittee will pay the additional amount to the Department with the next payment, if the said change in posted price occurred in the previous advance payment. A credit may be given to the Permittee for the amount paid in advance, if the water use fee for similar use is lowered by the Resources Committee. No amount of money will be refunded to the Permittee. The credited amount will be carried over to the next payment owed to the Navajo Nation. Permittee will pay the amount due in the beginning of each year to the Water Code Administration of the Department. Payment plans may be arranged between both parties in a written agreement.
7. Permittee agrees to provide water well development support to affected Chapters by paying directly to each Chapter \$250.00 (two hundred fifty dollars) per water well per year for wells located within each Chapter's boundaries. Permittee shall inform the Department of the payment as soon as the payment is made.
8. Permittee agrees to submit meter readings or other evidence showing the quantity of water withdrawn pursuant to this permit to the Water Code Administrator on a quarterly basis.
9. The Permittee shall monitor the effects of water use of the alluvial area by measuring static (non-pumping) water levels in at least three (3) of the water supply wells on a quarterly basis, and shall submit this water level data to the Department together with the information required in Condition 8. The Navajo Nation reserves the right to this permit due to adverse impacts on the water resources of the Navajo Nation resulting from the Permittee's activities, as determined by the Department.
10. The Navajo Nation may revoke this permit upon any breach by giving the Permittee notice of such revocation in writing no less than ten (10) days prior to the effective date of revocation, provided that if the Permittee remedies any such breach within said ten (10) day periods, the permit will remain in effect. Said notice shall state the grounds upon which the revocation is being made.

11. Permittee agrees to obtain a separate Water Use Permit for each point of withdrawal of water prior to making use of any additional water source.
12. Permittee agrees to hold harmless and indemnify the Navajo Nation against any and all losses, costs, damages, claims, expenses or other liability whatsoever, rising out of, or connected with Permittee's services under this permit including but not limited to, any accident or injury to person or property.
13. All disputes arising from the subject matter of this permit or the performance thereof will be settled in the Navajo Nation Courts and under the laws of the Navajo Nation. Nothing herein shall be construed as a waiver of the sovereign immunity of the Navajo Nation, pursuant to 1 N.T.C. §351 et seq.
14. Permittee agrees to maintain the immediate area in a safe and sanitary manner, free of unnecessary debris.
15. Authorization granted under this permit is only for the stated use of the indicated water source location. Permittee is responsible for obtaining any applicable permit from the appropriate department/agency that may be required for the proposed work.
16. If permittee hires sub-contractors to haul water covered by Water Use Permit, Permittee must notify the Navajo Water Code Administration of sub-contractors in writing.
17. It is agreed that the Department reserves the right to limit the quantity of water that can be taken under this permit to the above stated amount or less and will give the Permittee 30 day notice before such action is imposed. Such limitations will be imposed at the discretion of the Department.
18. Permittee agrees to allow reasonable entry upon their premises by Navajo Nation Employees engaged in the administration of this permit.
19. The Department will allow the Permittee to continue to make irrigation water available to the Whitehorse High School, Montezuma Creek, Utah, and to those local residents currently using the water for livestock usage.
20. In the event the Department or the Navajo Nation subsequently reduces the cost of water use permits to other oil and gas industry members, then the Department or Navajo Nation shall grant to the Permittee a credit for the amounts that it has previously paid and apply such credit to future financial obligations owed by Texaco to the Nation for water use.
21. The permit shall be renewable each year for the next 5 years under the same terms and conditions as set forth herein.

Permittee's Signature [Signature] Date JUN. 23-05

OFFICIAL USE ONLY	
Recommendation:	<input checked="" type="checkbox"/> Yes () No <u>[Signature]</u> Date <u>01-03-06</u> Water Code Administrator
	<input checked="" type="checkbox"/> Yes () No <u>[Signature]</u> Date <u>12-29-05</u> Technical Reviewer
Approved/Disapproved:	<u>[Signature]</u> Date <u>1-4-06</u> Director, Department of Water Resources
If Disapproved State Reasons:	

Sundry Number: 36692 API Well Number: 43037302420000

Navajo Department of Water Resources

Water Code Administration

P.O. Box 678

Fort Defiance, Arizona 86504

Ph. No. (928) 729-4132/Fax No. (928) 729-4421

APPROVED

WATER USE PERMIT

WUP NO: **06.0018**

VALID FROM **DEC 29 2005** to **DEC 29 2010**

NOTE: This permit is valid only upon signature of the Department of Water Resources Director. Please read Water Use Permit information sheet before completing this form.

APPLICANT: <u>Resolute Natural Resources</u>	
LAST NAME	FIRST; OR COMPANY NAME
MAILING ADDRESS: <u>Post Office Box 800</u>	
CITY: <u>Montezuma Creek</u>	STATE: <u>Utah</u> ZIP CODE: <u>84534</u>
CONTACT PERSON: <u>Roger Atcitty</u>	TELEPHONE NO: <u>435-651-3682 X-103</u>
***** Fax #: <u>435-651-3276</u> *****	
DATE RECEIVED: <u>NOV 23 2005</u>	DATE COMPLETED <u>JAN 04 2006</u>
\$25.00 Filing Fee Received	Receipt No. _____ Initial <u>JAN</u>

IDENTIFIED WATER SOURCE TO BE USED

() Spring No: _____	() Stream Name: _____
() Stockpond Name/No: _____	() Lake/Reservoir Name: _____
<input checked="" type="checkbox"/> Well No: <u>CUSA WW #18</u>	() Injection Well No: _____
Amount of water requested: <u>1,000 acre-ft</u>	
() Other Description/Name: _____	Grazing District: <u>12</u>
Chapter: <u>Aneth</u>	Chapter Code: <u>ANET</u>
State: () AZ/Arizona () NM/New Mexico <input checked="" type="checkbox"/> UT/Utah	
County: () AP/Apache () MK/McKinley <input checked="" type="checkbox"/> SJ/San Juan	
() NA/Navajo () VL/Valencia () KA/Kane	
() CO/Coconino () BL/Bernalillo	
() SD/Sandoval () SO/Socorro	
() RA/Rio Arriba () SA/San Juan	
Quad. No: (7.5 min. Series) <u>4648</u>	
UTM COORDINATES: X (East) <u>649045</u> Y (North) <u>4125190</u> ZONE <u>12</u>	
NE SE SW NW / NE SE SW NW / NE SE SW NW	31 40S 24E
10 Acre 40 Acre 160 Acre	Section Township Range

LAND STATUS

☒ TRUST ☐ FEE ☐ LEASE ☐ ALLOTMENT ☐ OTHER
WATERSHED NAME: San Juan River USGS WATERSHED CODE NO. 14080201

CONSUMPTIVE WATER USE NEEDED FOR

PRIMARY:

☐ Domestic ☐ Recreational
☐ Municipal ☐ Industrial
☐ Livestock ☐ Mining
☐ Irrigation Agriculture ☐ Commercial
☐ Wildlife and Fish ☒ Other Oil and Gas Production

DOMESTIC/MUNICIPAL:

Number of People: Number of Homes: Others:

TYPE OF LIVESTOCK:

N/A ☐ Horses No: ☐ Goats No:
☐ Cattle No: ☐ Sheep No:
☐ Other: ☐ No:

TYPE OF CROPS:

N/A ☐ Row (ie., corn) Acres
☐ Forage-Hay-Pasture Acres
☐ Small Grains Acres
☐ Horticulture (ie., Fruits & Vegetables) Acres

TYPE OF WILDLIFE:

N/A ☐ Fish No: ☐ Small Game No:
☐ Large Game No: ☐ Birds No:
☐ Others No:

IF WATER IS USED FOR INDUSTRIAL OR MINING PURPOSES, ATTACH WATER SUPPLY PLAN
DESCRIBING SOURCE AND METHODS OF DIVERSION, CONVEYANCE AND USES.

SEASON OF MAXIMUM USE: ☒ Spring ☒ Summer ☒ Fall ☒ Winter

MAXIMUM RATE OF USE: 87.5 ☒ GPM ☐ CFS

EXPECTED DATE WATER USAGE TO BEGIN: 1/1/98 (renewed 1/1/03)

EXPECTED VOLUME OF WATER TO BE USED: 141 ac/ft (gallons)

METHOD OF WATER DIVERSION:

☐ Instream Pump ☐ Gate or Gravity Flow
☒ Other: pump located at well

METHOD OF WATER CONVEYANCE:

☐ Ditch ☐ Canal ☒ Pipeline ☐ Truck
☐ Other:

ATTACH AN 8 1/2" X 11" MAP SHOWING EXACT LOCATION OF IDENTIFIED WATER SOURCE AND
SCENARIO/ LOCATION OF WHERE WATER IS TO BE USED.

RETURN FLOW OR DISCHARGE

AMOUNT OF WATER: N/A ☐ GPM ☐ CFS ☐ GPD METHOD: ☐ Direct
☐ Indirect
☐ Injection

IS DISCHARGE TREATED ☐ YES ☐ NO

IS QUALITY AFFECTED ☐ YES ☐ NO


FEDERAL/UIC PERMIT: N/A NPDES PERMIT NUMBER: N/A

CONDITIONS


1. Purpose of definition "Department" means the Navajo Nation Department of Water Resources and "Permittee" means Resolute Natural Resources (Formerly Chevron U.S.A. Inc.) and its successors.
2. Permittee agrees to comply with the terms and conditions of the Water Use Permit and the Navajo Nation Water Code. Permittee understands and agrees that failure to comply with the permit shall result in forfeiture of this permit.
3. This permit may be revoked if:
 - A. Permittee is not in compliance with any conditions set forth in this permit.
 - B. Permittee is in violation of any provision of the Navajo Nation Water Code.
 - C. Insufficient water supplies are present for whatever reason or term.
 - D. For any other due cause as a result of negative findings from investigation that is performed by both Department and Permittee.
4. The total quantity of water withdrawn by the Permittee from all water supply wells in the alluvium of San Juan River for the secondary or tertiary recovery of oil shall not exceed 1,000 acre-feet in any year.
5. Permit is valid from January 1, 2006 through December 31, 2010 and shall expire on December 31, 2010 or at the completion of the proposed project or required water usage, whichever comes first. Permittee does not have authority to transfer, convey, or allocate the water subject to this permit to any third party or for any other to transfer, convey, or allocate the water subject to this permit to any third party or for any other project not specified herein. It is further agreed between the parties that this permit does not give the Permittee the right to haul water for hire on the Navajo Reservation, or on land subject to the jurisdiction of the Navajo Nation.
6. Permittee agrees to pay a water use fee of \$1,000.00 (one thousand dollars) per water supply well per year. A lump sum payment will be paid at the end of each year for anticipated water use for the coining year, beginning with 2006. Thereafter payment may be made in advance. The water use fee will increase by 100.00 (one hundred dollars) per water supply well per year in the event that the average posted price for West Texas Intermediate Crude Oil exceeds \$30.00 (thirty dollars) per barrel for more than 6 (six) months in any year. The Permittee will pay the additional amount to the Department with the next payment, if the said change in posted price occurred in the previous advance payment. A credit may be given to the Permittee for the amount paid in advance, if the water use fee for similar use is lowered by the Resources Committee. No amount of money will be refunded to the Permittee. The credited amount will be carried over to the next payment owed to the Navajo Nation. Permittee will pay the amount due in the beginning of each year to the Water Code Administration of the Department. Payment plans may be arranged between both parties in a written agreement.
7. Permittee agrees to provide water well development support to affected Chapters by paying directly to each Chapter \$250.00 (two hundred fifty dollars) per water well per year for wells located within each Chapter's boundaries. Permittee shall inform the Department of the payment as soon as the payment is made.
8. Permittee agrees to submit meter readings or other evidence showing the quantity of water withdrawn pursuant to this permit to the Water Code Administrator on a quarterly basis.
9. The Permittee shall monitor the effects of water use of the alluvial aquifer by measuring static (non-pumping) water levels in at least three (3) of the water supply wells on a quarterly basis, and shall submit this water level data to the Department together with the information required in Condition 8. The Navajo Nation reserves the right to this permit due to adverse impacts on the water resources of the Navajo Nation resulting from the Permittee's activities, as determined by the Department.
10. The Navajo Nation may revoke this permit upon any breach by giving the Permittee notice of such revocation in writing no less than ten (10) days prior to the effective date of revocation, provided that if the Permittee remedies any such breach within said ten (10) day periods, the permit will remain in effect. Said notice shall state the grounds upon which the revocation is being made.

11. Permittee agrees to obtain a separate Water Use Permit for each point of withdrawal of water prior to making use of any additional water source.
12. Permittee agrees to hold harmless and indemnify the Navajo Nation against any and all losses, costs, damages, claims, expenses or other liability whatsoever, rising out of, or connected with Permittee's services under this permit including but not limited to, any accident or injury to person or property.
13. All disputes arising from the subject matter of this permit or the performance thereof will be settled in the Navajo Nation Courts and under the laws of the Navajo Nation. Nothing herein shall be construed as a waiver of the sovereign immunity of the Navajo Nation, pursuant to 1 N.T.C. §351 et seq.
14. Permittee agrees to maintain the immediate area in a safe and sanitary manner, free of unnecessary debris.
15. Authorization granted under this permit is only for the stated use of the indicated water source location. Permittee is responsible for obtaining any applicable permit from the appropriate department/agency that may be required for the proposed work.
16. If permittee hires sub-contractors to haul water covered by Water Use Permit, Permittee must notify the Navajo Water Code Administration of sub-contractors in writing.
17. It is agreed that the Department reserves the right to limit the quantity of water that can be taken under this permit to the above stated amount or less and will give the Permittee 30 day notice before such action is imposed. Such limitations will be imposed at the discretion of the Department.
18. Permittee agrees to allow reasonable entry upon their premises by Navajo Nation Employees engaged in the administration of this permit.
19. The Department will allow the Permittee to continue to make irrigation water available to the Whitehorse High School, Montezuma Creek, Utah, and to those local residents currently using the water for livestock usage.
20. In the event the Department or the Navajo Nation subsequently reduces the cost of water use permits to other oil and gas industry members, then the Department or Navajo Nation shall grant to the Permittee a credit for the amounts that it has previously paid and apply such credit to future financial obligations owed by Texaco to the Nation for water use.
21. The permit shall be renewable each year for the next 5 years under the same terms and conditions as set forth herein.

Permittee's Signature

Date Nov. 23-05

OFFICIAL USE ONLY

Recommendation: ☒ Yes ☐ No
Water Code AdministratorDate 01-03-06☒ Yes ☐ No
Technical ReviewerDate 12-29-05

Approved/Disapproved:


Director, Department of Water ResourcesDate 1-4-06

If Disapproved State Reasons:

Sundry Number: 36692 API Well Number: 43037302420000

Navajo Department of Water Resources
Water Code Administration
P.O. Box 678
Fort Defiance, Arizona 86504
Ph. No. (928) 729-4132/Fax No. (928) 729-4421

APPROVED

WATER USE PERMIT

06.0019

WUP NO: _____

VALID FROM DEC 29 2005 to DEC 29 2010

NOTE: This permit is valid only upon signature of the Department of Water Resources Director. Please read Water Use Permit information sheet before completing this form.

APPLICANT: <u>Resolute Natural Resources</u>	
LAST NAME	FIRST; OR COMPANY NAME
MAILING ADDRESS: <u>Post Office Box 800</u>	
CITY: <u>Montezuma Creek</u>	STATE: <u>Utah</u> ZIP CODE: <u>84534</u>
CONTACT PERSON: <u>Roger Atcitty</u>	TELEPHONE NO: <u>435-651-3682 X-103</u>
***** Fax #: <u>435-651-3276</u> *****	
DATE RECEIVED: <u>NOV 23 2005</u>	DATE COMPLETED <u>JAN 04 2006</u>
\$25.00 Filing Fee Received _____	Receipt No. _____ Initial <u>JA</u>

IDENTIFIED WATER SOURCE TO BE USED

() Spring No: _____ () Stream Name: _____

() Stockpond Name/No: _____ () Lake/Reservoir Name: _____

☒ Well No: CUSA WW #19 () Injection Well No: _____

Amount of water requested: 1,000 acre-ft

() Other Description/Name: _____ Grazing District: 12

Chapter: Aneth Chapter Code: ANET

State:	() AZ/Arizona	() NM/New Mexico	<input checked="" type="checkbox"/> UT/Utah
County:	() AP/Apache	() MK/McKinley	<input checked="" type="checkbox"/> SJ/San Juan
	() NA/Navajo	() VL/Valencia	() KA/Kane
	() CO/Coconino	() BL/Bernalillo	
		() SD/Sandoval	
		() SO/Socorro	
		() RA/Rio Arriba	
		() SA/San Juan	

Quad. No: (7.5 min. Series) 4648

UTM COORDINATES: X (East) 649102 Y (North) 4125125 ZONE 12

NE SE SW NW / NE SE SW NW / NE SE SW NW	<u>31</u>	<u>40S</u>	<u>24E</u>
10 Acre 40 Acre 160 Acre	Section	Township	Range

LAND STATUS

☒ TRUST ☐ FEE ☐ LEASE ☐ ALLOTMENT ☐ OTHER
 WATERSHED NAME: San Juan River USGS WATERSHED CODE NO. 14080201

CONSUMPTIVE WATER USE NEEDED FOR

PRIMARY:

☐ Domestic ☐ Recreational
☐ Municipal ☐ Industrial
☐ Livestock ☐ Mining
☐ Irrigation Agriculture ☐ Commercial
☐ Wildlife and Fish ☒ Other Oil and Gas Production

DOMESTIC/MUNICIPAL:

Number of People: _____ Number of Homes: _____ Others: _____

TYPE OF LIVESTOCK:

N/A ☐ Horses No: _____ ☐ Goats No: _____
☐ Cattle No: _____ ☐ Sheep No: _____
☐ Other: _____ ☐ No: _____

TYPE OF CROPS:

N/A ☐ Row (ie., corn) Acres _____
☐ Forage-Hay-Pasture Acres _____
☐ Small Grains Acres _____
☐ Horticulture (ie., Fruits & Vegetables) Acres _____

TYPE OF WILDLIFE:

N/A ☐ Fish No: _____ ☐ Small Game No: _____
☐ Large Game No: _____ ☐ Birds No: _____
☐ Others No: _____

IF WATER IS USED FOR INDUSTRIAL OR MINING PURPOSES, ATTACH WATER SUPPLY PLAN DESCRIBING SOURCE AND METHODS OF DIVERSION, CONVEYANCE AND USES.

SEASON OF MAXIMUM USE: ☒ Spring ☒ Summer ☒ Fall ☒ Winter

MAXIMUM RATE OF USE: 87.5 ☒ GPM ☐ CFS ☐ CFS

EXPECTED DATE WATER USAGE TO BEGIN: 1/1/98 (renewed 1/1/03)

EXPECTED VOLUME OF WATER TO BE USED: 141 ac/ft (_____ gallons)

METHOD OF WATER DIVERSION: ☐ Instream Pump ☐ Gate or Gravity Flow
☒ Other: pump located at well

METHOD OF WATER CONVEYANCE: ☐ Ditch ☐ Canal ☒ Pipeline ☐ Truck
☐ Other: _____

ATTACH AN 8 1/2" X 11" MAP SHOWING EXACT LOCATION OF IDENTIFIED WATER SOURCE AND SCENARIO/LOCATION OF WHERE WATER IS TO BE USED.

RETURN FLOW OR DISCHARGE

AMOUNT OF WATER: N/A ☐ GPM ☐ CFS ☐ GPD METHOD: ☐ Direct
☐ Indirect
☐ Injection


IS DISCHARGE TREATED ☐ YES ☐ NO
 IS QUALITY AFFECTED ☐ YES ☐ NO
 FEDERAL/UIC PERMIT: N/A IS TEMPERATURE AFFECTED ☐ YES ☐ NO
 NPDES PERMIT NUMBER: N/A

CONDITIONS

1. Purpose of definition "Department" means the Navajo Nation Department of Water Resources and "Permittee" means Resolute Natural Resources (Formerly Chevron U.S.A. Inc.) and its successors.
2. Permittee agrees to comply with the terms and conditions of the Water Use Permit and the Navajo Nation Water Code. Permittee understands and agrees that failure to comply with the permit shall result in forfeiture of this permit.
3. This permit may be revoked if:
 - A. Permittee is not in compliance with any conditions set forth in this permit.
 - B. Permittee is in violation of any provision of the Navajo Nation Water Code.
 - C. Insufficient water supplies are present for whatever reason or term.
 - D. For any other due cause as a result of negative findings from investigation that is performed by both Department and Permittee.
4. The total quantity of water withdrawn by the Permittee from all water supply wells in the alluvium of San Juan River for the secondary or tertiary recovery of oil shall not exceed 1,000 acre-feet in any year.
5. Permit is valid from January 1, 2006 through December 31, 2010 and shall expire on December 31, 2010 or at the completion of the proposed project or required water usage, whichever comes first. Permittee does not have authority to transfer, convey, or allocate the water subject to this permit to any third party or for any other to transfer, convey, or allocate the water subject to this permit to any third party or for any other project not specified herein. It is further agreed between the parties that this permit does not give the Permittee the right to haul water for hire on the Navajo Reservation, or on land subject to the jurisdiction of the Navajo Nation.
6. Permittee agrees to pay a water use fee of \$1,000.00 (one thousand dollars) per water supply well per year. A lump sum payment will be paid at the end of each year for anticipated water use for the coming year, beginning with 2006. Thereafter payment may be made in advance. The water use fee will increase by 100.00 (one hundred dollars) per water supply well per year in the event that the average posted price for West Texas Intermediate Crude Oil exceeds \$30.00 (thirty dollars) per barrel for more than 6 (six) months in any year. The Permittee will pay the additional amount to the Department with the next payment, if the said change in posted price occurred in the previous advance payment. A credit may be given to the Permittee for the amount paid in advance, if the water use fee for similar use is lowered by the Resources Committee. No amount of money will be refunded to the Permittee. The credited amount will be carried over to the next payment owed to the Navajo Nation. Permittee will pay the amount due in the beginning of each year to the Water Code Administration of the Department. Payment plans may be arranged between both parties in a written agreement.
7. Permittee agrees to provide water well development support to affected Chapters by paying directly to each Chapter \$250.00 (two hundred fifty dollars) per water well per year for wells located within each Chapter's boundaries. Permittee shall inform the Department of the payment as soon as the payment is made.
8. Permittee agrees to submit meter readings or other evidence showing the quantity of water withdrawn pursuant to this permit to the Water Code Administrator on a quarterly basis.
9. The Permittee shall monitor the effects of water use of the alluvial area by measuring static (non-pumping) water levels in at least three (3) of the water supply wells on a quarterly basis, and shall submit this water level data to the Department together with the information required in Condition 8. The Navajo Nation reserves the right to this permit due to adverse impacts on the water resources of the Navajo Nation resulting from the Permittee's activities, as determined by the Department.
10. The Navajo Nation may revoke this permit upon any breach by giving the Permittee notice of such revocation in writing no less than ten (10) days prior to the effective date of revocation, provided that if the Permittee remedies any such breach within said ten (10) day periods, the permit will remain in effect. Said notice shall state the grounds upon which the revocation is being made.

11. Permittee agrees to obtain a separate Water Use Permit for each point of withdrawal of water prior to making use of any additional water source.
12. Permittee agrees to hold harmless and indemnify the Navajo Nation against any and all losses, costs, damages, claims, expenses or other liability whatsoever, rising out of, or connected with Permittee's services under this permit including but not limited to, any accident or injury to person or property.
13. All disputes arising from the subject matter of this permit or the performance thereof will be settled in the Navajo Nation Courts and under the laws of the Navajo Nation. Nothing herein shall be construed as a waiver of the sovereign immunity of the Navajo Nation, pursuant to 1 N.T.C. §351 et seq.
14. Permittee agrees to maintain the immediate area in a safe and sanitary manner, free of unnecessary debris.
15. Authorization granted under this permit is only for the stated use of the indicated water source location. Permittee is responsible for obtaining any applicable permit from the appropriate department/agency that may be required for the proposed work.
16. If permittee hires sub-contractors to haul water covered by Water Use Permit, Permittee must notify the Navajo Water Code Administration of sub-contractors in writing.
17. It is agreed that the Department reserves the right to limit the quantity of water that can be taken under this permit to the above stated amount or less and will give the Permittee 30 day notice before such action is imposed. Such limitations will be imposed at the discretion of the Department.
18. Permittee agrees to allow reasonable entry upon their premises by Navajo Nation Employees engaged in the administration of this permit.
19. The Department will allow the Permittee to continue to make irrigation water available to the Whitehorse High School, Montezuma Creek, Utah, and to those local residents currently using the water for livestock usage.
20. In the event the Department or the Navajo Nation subsequently reduces the cost of water use permits to other oil and gas industry members, then the Department or Navajo Nation shall grant to the Permittee a credit for the amounts that it has previously paid and apply such credit to future financial obligations owed by Texaco to the Nation for water use.
21. The permit shall be renewable each year for the next 5 years under the same terms and conditions as set forth herein.

Permittee's Signature




Date

11-23-05

OFFICIAL USE ONLY

Recommendation:

☒ Yes ☐ No
Water Code Administrator

Date

01-03-06

☒ Yes ☐ No
Technical Reviewer

Date

12-29-05

Approved/Disapproved:


Director, Department of Water Resources

Date

1-4-06

If Disapproved State Reasons:

Sundry Number: 36692 API Well Number: 43037302420000

Navajo Department of Water Resources
Water Code Administration
P.O. Box 678
Fort Defiance, Arizona 86504
Ph. No. (928) 729-4132/Fax No. (928) 729-4421

APPROVED

WATER USE PERMIT

WUP NO: **06.0020**

VALID FROM **DEC 29 2005** to **DEC 29 2010**

NOTE: This permit is valid only upon signature of the Department of Water Resources Director. Please read Water Use Permit information sheet before completing this form.

APPLICANT: <u>Resolute Natural Resources</u>	
LAST NAME	FIRST; OR COMPANY NAME
MAILING ADDRESS: <u>Post Office Box 800</u>	
CITY: <u>Montezuma Creek</u>	STATE: <u>Utah</u> ZIP CODE: <u>84534</u>
CONTACT PERSON: <u>Roger Atcitty</u>	TELEPHONE NO: <u>435-651-3682 X-103</u>
Fax #: <u>435-651-3276</u>	
DATE RECEIVED: <u>NOV 23 2005</u>	DATE COMPLETED <u>JAN 04 2006</u>
\$25.00 Filing Fee Received	Receipt No. _____ Initial <u>MAN</u>

IDENTIFIED WATER SOURCE TO BE USED			
() Spring No: _____		() Stream Name: _____	
() Stockpond Name/No: _____		() Lake/Reservoir Name: _____	
X Well No: <u>CUSA WW #20</u>		() Injection Well No: _____	
Amount of water requested: <u>1,000 acre-ft</u>			
() Other Description/Name: _____		Grazing District: <u>12</u>	
Chapter: <u>Aneth</u>		Chapter Code: <u>ANET</u>	
State:	() AZ/Arizona	() NM/New Mexico	(x) UT/Utah
County:	() AP/Apache	() MK/McKinley	(x) SJ/San Juan
	() NA/Navajo	() VL/Valencia	() KA/Kane
	() CO/Coconino	() BL/Bernalillo	
		() SD/Sandoval	
		() SO/Socorro	
		() RA/Rio Arriba	
		() SA/San Juan	
Quad. No: (7.5 min. Series) <u>4648</u>			
UTM COORDINATES: X (East) <u>649170</u>		Y (North) <u>4125095</u>	ZONE <u>12</u>
NE SE SW NW / NE SE SW NW / NE SE SW NW		<u>31</u>	<u>40S</u> <u>24E</u>
<u>10 Acre</u> <u>40 Acre</u> <u>160 Acre</u>		<u>Section</u>	<u>Township</u> <u>Range</u>

This used to be called the CUSA Gallery Well.

LAND STATUS

☒ TRUST ☐ FEE ☐ LEASE ☐ ALLOTMENT ☐ OTHER
 WATERSHED NAME: San Juan River USGS WATERSHED CODE NO. 14080201

CONSUMPTIVE WATER USE NEEDED FOR

PRIMARY:

☐ Domestic ☐ Recreational
☐ Municipal ☐ Industrial
☐ Livestock ☐ Mining
☐ Irrigation Agriculture ☐ Commercial
☐ Wildlife and Fish ☒ Other Oil and Gas Production

DOMESTIC/MUNICIPAL:

Number of People: _____ Number of Homes: _____ Others: _____

TYPE OF LIVESTOCK: ☐ Horses No: _____ ☐ Goats No: _____
☐ Cattle No: _____ ☐ Sheep No: _____
☐ Other: _____ ☐ No: _____

TYPE OF CROPS: ☐ Row (ie., corn) Acres _____
☐ Forage-Hay-Pasture Acres _____
☐ Small Grains Acres _____
☐ Horticulture (ie., Fruits & Vegetables) Acres _____

TYPE OF WILDLIFE: ☐ Fish No: _____ ☐ Small Game No: _____
☐ Large Game No: _____ ☐ Birds No: _____
☐ Others No: _____

**IF WATER IS USED FOR INDUSTRIAL OR MINING PURPOSES, ATTACH WATER SUPPLY PLAN
 DESCRIBING SOURCE AND METHODS OF DIVERSION, CONVEYANCE AND USES.**

SEASON OF MAXIMUM USE: ☒ Spring ☒ Summer ☒ Fall ☒ Winter

MAXIMUM RATE OF USE: 87.5 ☒ GPM ☐ CFS

EXPECTED DATE WATER USAGE TO BEGIN: 1/1/98 (renewed 1/1/03)

EXPECTED VOLUME OF WATER TO BE USED: 141 ac/ft (_____ gallons)

METHOD OF WATER DIVERSION: ☐ Instream Pump ☐ Gate or Gravity Flow
☒ Other: pump located at well

METHOD OF WATER CONVEYANCE: ☐ Ditch ☐ Canal ☒ Pipeline ☐ Truck
☐ Other: _____

**ATTACH AN 8 1/2" X 11" MAP SHOWING EXACT LOCATION OF IDENTIFIED WATER SOURCE AND
 SCENARIO/LOCATION OF WHERE WATER IS TO BE USED.**

RETURN FLOW OR DISCHARGE

AMOUNT OF WATER: N/A ☐ GPM ☐ CFS ☐ GPD **METHOD:** ☐ Direct
☐ Indirect
☐ Injection

IS DISCHARGE TREATED ☐ YES ☐ NO
IS QUALITY AFFECTED ☐ YES ☐ NO **IS TEMPERATURE AFFECTED** ☐ YES ☐ NO
FEDERAL/UIC PERMIT: N/A **NPDES PERMIT NUMBER:** N/A


06.0015

CONDITIONS

1. Purpose of definition "Department" means the Navajo Nation Department of Water Resources and "Permittee" means Resolute Natural Resources (Formerly Chevron U.S.A. Inc.) and its successors.
2. Permittee agrees to comply with the terms and conditions of the Water Use Permit and the Navajo Nation Water Code. Permittee understands and agrees that failure to comply with the permit shall result in forfeiture of this permit.
3. This permit may be revoked if:
 - A. Permittee is not in compliance with any conditions set forth in this permit.
 - B. Permittee is in violation of any provision of the Navajo Nation Water Code.
 - C. Insufficient water supplies are present for whatever reason or term.
 - D. For any other due cause as a result of negative findings from investigation that is performed by both Department and Permittee.
4. The total quantity of water withdrawn by the Permittee from all water supply wells in the alluvium of San Juan River for the secondary or tertiary recovery of oil shall not exceed 1,000 acre-feet in any year.
5. Permit is valid from January 1, 2006 through December 31, 2010 and shall expire on December 31, 2010 or at the completion of the proposed project or required water usage, whichever comes first. Permittee does not have authority to transfer, convey, or allocate the water subject to this permit to any third party or for any other to transfer, convey, or allocate the water subject to this permit to any third party or for any other project not specified herein. It is further agreed between the parties that this permit does not give the Permittee the right to haul water for hire on the Navajo Reservation, or on land subject to the jurisdiction of the Navajo Nation.
6. Permittee agrees to pay a water use fee of \$1,000.00 (one thousand dollars) per water supply well per year. A lump sum payment will be paid at the end of each year for anticipated water use for the coming year, beginning with 2006. Thereafter payment may be made in advance. The water use fee will increase by 100.00 (one hundred dollars) per water supply well per year in the event that the average posted price for West Texas Intermediate Crude Oil exceeds \$30.00 (thirty dollars) per barrel for more than 6 (six) months in any year. The Permittee will pay the additional amount to the Department with the next payment, if the said change in posted price occurred in the previous advance payment. A credit may be given to the Permittee for the amount paid in advance, if the water use fee for similar use is lowered by the Resources Committee. No amount of money will be refunded to the Permittee. The credited amount will be carried over to the next payment owed to the Navajo Nation. Permittee will pay the amount due in the beginning of each year to the Water Code Administration of the Department. Payment plans may be arranged between both parties in a written agreement.
7. Permittee agrees to provide water well development support to affected Chapters by paying directly to each Chapter \$250.00 (two hundred fifty dollars) per water well per year for wells located within each Chapter's boundaries. Permittee shall inform the Department of the payment as soon as the payment is made.
8. Permittee agrees to submit meter readings or other evidence showing the quantity of water withdrawn pursuant to this permit to the Water Code Administrator on a quarterly basis.
9. The Permittee shall monitor the effects of water use of the alluvial area by measuring static (non-pumping) water levels in at least three (3) of the water supply wells on a quarterly basis, and shall submit this water level data to the Department together with the information required in Condition 8. The Navajo Nation reserves the right to this permit due to adverse impacts on the water resources of the Navajo Nation resulting from the Permittee's activities, as determined by the Department.
10. The Navajo Nation may revoke this permit upon any breach by giving the Permittee notice of such revocation in writing no less than ten (10) days prior to the effective date of revocation, provided that if the Permittee remedies any such breach within said ten (10) day periods, the permit will remain in effect. Said notice shall state the grounds upon which the revocation is being made.

11. Permittee agrees to obtain a separate Water Use Permit for each point of withdrawal of water prior to making use of any additional water source.
12. Permittee agrees to hold harmless and indemnify the Navajo Nation against any and all losses, costs, damages, claims, expenses or other liability whatsoever, rising out of, or connected with Permittee's services under this permit including but not limited to, any accident or injury to person or property.
13. All disputes arising from the subject matter of this permit or the performance thereof will be settled in the Navajo Nation Courts and under the laws of the Navajo Nation. Nothing herein shall be construed as a waiver of the sovereign immunity of the Navajo Nation, pursuant to 1 N.T.C. §351 et seq.
14. Permittee agrees to maintain the immediate area in a safe and sanitary manner, free of unnecessary debris.
15. Authorization granted under this permit is only for the stated use of the indicated water source location. Permittee is responsible for obtaining any applicable permit from the appropriate department/agency that may be required for the proposed work.
16. If permittee hires sub-contractors to haul water covered by Water Use Permit, Permittee must notify the Navajo Water Code Administration of sub-contractors in writing.
17. It is agreed that the Department reserves the right to limit the quantity of water that can be taken under this permit to the above stated amount or less and will give the Permittee 30 day notice before such action is imposed. Such limitations will be imposed at the discretion of the Department.
18. Permittee agrees to allow reasonable entry upon their premises by Navajo Nation Employees engaged in the administration of this permit.
19. The Department will allow the Permittee to continue to make irrigation water available to the Whitehorse High School, Montezuma Creek, Utah, and to those local residents currently using the water for livestock usage.
20. In the event the Department or the Navajo Nation subsequently reduces the cost of water use permits to other oil and gas industry members, then the Department or Navajo Nation shall grant to the Permittee a credit for the amounts that it has previously paid and apply such credit to future financial obligations owed by Texaco to the Nation for water use.
21. The permit shall be renewable each year for the next 5 years under the same terms and conditions as set forth herein.

Permittee's Signature

Date Jan. 23-05

OFFICIAL USE ONLY

Recommendation: ☒ Yes () No
Water Code AdministratorDate 01-03-06☒ Yes () No
Technical ReviewerDate 12-29-05

Approved/Disapproved:


Director, Department of Water ResourcesDate 1-4-06

If Disapproved State Reasons:

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 04/12/2013

API NO. ASSIGNED: 43-037-30242

WELL NAME: ANETH H-222

OPERATOR: RESOLUTE NATURAL (N2700)

CONTACT: SHERRY GLASS

PHONE NUMBER: 303-573-4886

PROPOSED LOCATION:

SENE 22 400S 240E

SURFACE: 2103 FNL 0783 FEL

BOTTOM: 1036 FNL 1606 FEL

COUNTY: SAN JUAN

LATITUDE: 37.29630 LONGITUDE: -109.26146

UTM SURF EASTINGS: 654093 NORTHINGS: 4129159

FIELD NAME: GREATER ANETH (365)

INSPECT LOCATN BY: / /

Tech Review

Initials

Date

Engineering

Geology

Surface

LEASE TYPE: 2 - Indian

LEASE NUMBER: I-149-IND-8836

SURFACE OWNER: 2 - Indian

PROPOSED FORMATION: ISMY

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[2] Sta[] Fee[]
(No. B001264)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 06.0019)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

___ R649-2-3.
Unit: ANETH *OK*
___ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
___ R649-3-3. Exception
☒ Drilling Unit
Board Cause No: 152-7
Eff Date: 4-22-1998
Siting: *Case Not Suspended General Siting*
___ R649-3-11. Directional Drill

COMMENTS:

STIPULATIONS:

1- Fecund Approval
2- Directional



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

April 17, 2013

Resolute Natural Resources
1675 Broadway, Ste 1950
Denver, CO 80202


Subject: Aneth H-222 Well, 2103' FNL, 783' FEL, SE NE, Sec. 22, T. 40 South, R. 24 East,
Bottom Location 1036' FNL, 1606' FEL, NW NE, Sec. 22, T. 40 South, R. 24 East,
San Juan County, Utah

Ladies and Gentlemen:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause: 152-7. The expected producing formation or pool is the ISMAY Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-037-30242.

Sincerely,



John Rogers
Associate Director

JR/js
Enclosures

cc: San Juan County Assessor
Bureau of Land Management, Monticello Office

Operator: Resolute Natural Resources
Well Name & Number Aneth H-222
API Number: 43-037-30242
Lease: I-149-IND-8836

Location: SE NE **Sec.** 22 **T.** 40 South **R.** 24 East
Bottom Location: NW NE **Sec.** 22 **T.** 40 South **R.** 24 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please let a voicemail message if not available)

OR

Submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office
(801) 733-0983 after office hours

3. Reporting Requirements

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. In accordance with Utah Admin. R.649-3-21, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: I-149-IND-8836
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: ANETH
3. ADDRESS OF OPERATOR: 1675 Boradway Ste 1950 , Denver, CO, 80202		8. WELL NAME and NUMBER: ANETH H-222
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2103 FNL 0783 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 22 Township: 40.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037302420000
9. FIELD and POOL or WILDCAT: GREATER ANETH		COUNTY: SAN JUAN
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/11/2013	<input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF			
<input type="checkbox"/> SPUD REPORT Date of Spud:				
<input type="checkbox"/> DRILLING REPORT Report Date:				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

 Resolute completed deepening the subject well on 5-6-13; well was completed via sidetrack on whipstock set at 5513', drilled out an OH lateral from 5613' to 7034' MD. Well put back to injection 5-11-13.

Accepted by the
Utah Division of
Oil, Gas and Mining

FOR RECORD ONLY

June 11, 2013

NAME (PLEASE PRINT) Sherry Glass	PHONE NUMBER 303 573-4886	TITLE Sr Regulatory Technician
SIGNATURE N/A	DATE 6/10/2013	

Sidetrack
Aneth Unit H-222
2096' FNL & 776' FEL
Sec 22, T40S, R24E
San Juan County, Utah
API 43-037-30242

Formation Tops (KB 4,945)

Navajo	928'
Chinle	1,694'
DeChelley	2,832'
Organ Rock	2,930' (Est)
Hermosa	4,696'
Ismay	5,588'

Sidetrack Procedure (Proposed)

1. MIRU (04-09-2013)
2. Mock MIT.
3. Pull injection equipment.
4. Set CIBP (5590').
5. Run CBL & Csg Inspection Logs (5590' to Surface).
6. Set whipstock on CIBP (5554').
7. Mill window (5545'-5551').
Note: *Lost window – mechanical failure.*
8. Set whipstock on CIBP (5522').
9. Mill window (5513'-5518).
10. Drill 4-3/4" OH lateral from 5518' to 7034' (MD), (TVD = 5910'),
BHL: 1001' FNL & 1631' FEL of Sec. 22, T40S, R24E.
Note: Sfc Location: 2096' FNL & 776' FEL of Sec. 22, T40S, R24E

11. Acidize OH lateral w/ 5,000 gals of 20% HCL.

12. Run injection equipment.

13. Circulate packer fluid.

14. RDMOL (05-07-2013)

15. MIT (05-08-2013)

16. RWTI (05-11-2013)

AU H-222 (Sidetrack/Short Lateral)

GREATER ANETH FIELD

2096' FNL & 776' FEL

SEC 22-T40S-R24E

SAN JUAN COUNTY, UTAH


API 43-037-30242

Injector

Formation Tops

Navajo	928'
Chinle	1694'
DeChelly	2832'
Organ Rock	2930' (Est)
Hermosa	4696' (Est)
Ismay	5588'

Current





Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Job Category Drilling	Primary Job Type Drilling - re-entry	Secondary Job Type
Start Date 4/8/2013	End Date	AFE Number 10013701
Objective Job scope includes: sidetrack wellbore, drill OH lateral, acid stimulation, install injection equipment, MIT & RWTL.		
Contractor Key	Rig Number #27	Rig Type
Report Start Date 2/22/2013	Report End Date 2/22/2013	Operations Summary Survey Loc.
Report Start Date 4/8/2013	Report End Date 4/8/2013	Operations Summary Report on H-222 Capital Injector Had Lansing extent location for 24 hour rig also had Key energy test all anchors
Report Start Date 4/9/2013	Report End Date 4/10/2013	Operations Summary Move service unit to location.. This location is clean and open,the anchors were tested 4/13 and marked.The cathodic system is hook-up and on.There is also a CO2 sub station on the north west side of location and injecting. The well head is a 3000# well head with 2 7/8 tree,Tubing pressure was at 2400 psi and 0 psi on backside. Spot in lay down tanks, rig ramp and with the assist of Dawn trucking winch unit onto ramp.Finish spotting in close loop system, gas buster., pipe trailers, BOP skid, also living quarters Rig up.service unit. Crew change at 18:00 hours tail gate safety meeting with everyone on location topic was job task, using the right tool for the job, wind directions., Rig up hard lines to rig pump and lines to frac tanks. pressure test casing to 1000 psi for 30 mins.(Good Test). Open well through choke to bleed off pressure to frac tanks.well making good amount of CO2 with readings of H2S at 70 PPM. Pump 10# to establish kill weight fluid.monitor pressure for 1 hour. Rig-up Tefteller and make up 1.901 gauge ring, pressure test lubricator to 1000 psi. Run on down and tag at 5469 wire line depth. Come out and pick up 1.81 plug run on in and set. Pressure test to 1000 psi (Good Test). Release pressure come and rig down wireline and move off. Nipple down well head. Pick up sub with TIW valve and strip BOP stack over and nipple up.Rig up rig floor and tongs, hand rails, ladders. Crew change at 6:00 am safety meeting with contractors on location topic was hand placement, laying down tubing, tong operations, suspended loads. Had Weatherford on location to release off packer.

Dur (hrs)		Comment
		2.50 secure all loads for rig move 1.00 move unit to location 6.00 move all equipennt with the help of Dawn trucking winch unit on to ramp finish spotting in equipment 2.50 rig up service unit 0.50 crew change at 18:00 hours safety meeting with everyone on location topic was job task, using the ight tool for the job, wind diruptions 2.00 rig up hard lines from pump to well also lines to manifold to frac tank.put on safety cables 0.50 pressure test casing to 1000 psi for 30 mis (good test) 2.00 open well through choke manifold and bleed off pressure 1.50 pump kill weight fluid and shut in well for 1 hour monitor pressure 2.00 rig up Tefteller and rig up pick up 1.901 gauge ring pressure test lubricator to 1000 psi. run on in to 5469 wireline depth. come out and pick up 1.81 plug and set come out and rig down wireline and release 2.00 nipple down well head and pick up sub with TIW valve strip over BOP stack and nipple up 1.50 rig up rig floor tongs hand rails and safety equipment 0.50 crew change at 6:00 am safety meeting with contractors on location topic was hand placement, laying down tubing, tong operations, suspended loads 0.50 start to release off packer
Report Start Date 4/10/2013	Report End Date 4/11/2013	Operations Summary Waited on Weatherford mechanic and electrician to work on accumulator.While waiting on starter to be replace on unit,set up catwalk with pipe racks. .The tubing pressure up to 600 psi, bleed off pressure and monitor. Pressure test BOP to 1000 high and 300 low. Release off packer and lay down landing jt 2 pup jt 8,6 ft. plus 167 jt Tally and transfer to empty trailer. Change equipment over and move DP from trailer to pipe racks. Crew change at 18:00 hours tail gate safety meeting with contractors on location topic was job task, hand placement, communication, picking up DP. Tally work string and make up BHA with on and off tool with 4 ft perf sub X-over back to AOH. Start picking up work string.and tag at 5448. Lay down jt 175 and install TIW valve with kelley hose. Circulate well around with 16# mud. Pull up and release packer. Start out of hole but shut down due to swabbing fluids back. Worked tubing up and down to try and relax rubbers on packer. Call out Tefteller to recover 1.81 plug. Crew change at 6:00 am safety meeting with with everyone on location topic was keeping on eye on fluids, job task, team work. Contline to wait on slickline
Dur (hrs)		Comment
		3.00 wain on Weatherford service hand 2.00 set pipe rack and cat walk. bleed off pressure on tubing and monitor tubing 1.00 pressure test BOP stack 1000 high and 300 low 0.50 release off packer and monitors pressure 4.50 lay down production tubing and tally and transfer to trailer 1.00 change over equipment . transfer AOH work string to pipe racks



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
0.50	crew change at 18:00 hours safety meeting with contractors on location topic was hand placement, job task, communication, picking up DP
1.00	tally working and make up BHA with on and off tool with 4 ft perf sub,x-over back to AOH
5.00	pick up workstring tally and transfer to pipe racks.
2.50	hook up hoses on top of TIW valve and circulate well around with 16# mud
1.50	release packer and start out. shut down because we were swabbing back fluids work tubing up and down
1.00	call out slickline hand to recovery 1.81 plug
0.50	crew change at 6:00 am safety meeting with contractors on location topic was

Report Start Date 4/11/2013	Report End Date 4/12/2013	Operations Summary Jsa Safety Mtg. Crew waited for WL for 1.5 hr, WL arrived spotted/ RU WL to Tbg Rih down to 5442' shear blank plug/ Retrieve blank plug, RD WL MOL. Continue tooh w/ aoh & packer pumping 3 bbls every row when tooh, LD packer/ on off tool. PU B/S Rih w/174 aoh out of derrick, pu 7 jts off pipe rack down to 5724' total 181 jts, LD 7 jts back down pump 5 bbls 16# mud. SI Dash hot shot unloaded 2 mornells, 3 mud motors. LD 6 more aoh dp tooh with 102 jts SB in derrick. Crew change 18:00. Unloaded 15 2 7/8" aoh dp, 6- 2 7/8" H-90 spiral dp off hot shot trailer. Continue tooh w aoh dp total standing back 168 jts ld bit/ scraper. Spotted/ RU Blue Jet WL rih w/ CIBP notified Craig Wright suggest to set CIBP @ 5590', Set CIBP @ 5590' rooh w/ WL RD. Rih w/ aoh open end down 176 jts 5587' tag up CIBP pull lad down #176 ru tiw valve kelly hose up, made back up #176 set eot 10' above CIBP 5577'. Pump Cir. 16# mud out of hole to rig pit, Lansing haul mud back to mud plant. Lot of Co2 on return had to choke back pump slowly pump 180 bbl to make sure mud clear up, Pressure tested CIBP 580 psi good, RD lines off tbg lay down 5 jts tooh 172 jts in derrick. RU WL rih to 5590' logging to surface. Crew change 6:00.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
0.50	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg.
1.50	Crew waited for WL for 1.5 hr,
1.50	WL arrived spotted/ RU WL to Tbg Rih down to 5442' shear blank plug/ Retrieve blank plug, RD WL MOL
3.00	Continue tooh w/ aoh & packer pumping 3 bbls every row when tooh, LD packer/ on off tool.
2.50	PU B/S Rih w/174 aoh out of derrick, pu 7 jts off pipe rack down to 5724' total 181 jts, LD 7 jts back down pump 5 bbls 16# mud.
1.00	SI Dash hot shot unloaded 2 mornells, 3 mud motors.
1.50	LD 6 more aoh dp tooh with 102 jts SB in derrick.
0.50	Crew change 18:00.
0.50	Unloaded 15 2 7/8" aoh dp, 6- 2 7/8" H-90 spiral dp off hot shot trailer.
1.00	Continue tooh w aoh dp total standing back 168 jts ld bit/ scraper.
1.50	Spotted/ RU Blue Jet WL rih w/ CIBP notified Craig Wright suggest to set CIBP @ 5590', Set CIBP @ 5590' rooh w/ WL RD
2.50	Rih w/ aoh open end down 176 jts 5587' tag up CIBP pull lad down #176 ru tiw valve kelly hose up, made back up #176 set eot 10' above CIBP 5577'.
3.50	Pump Cir. 16# mud out of hole to rig pit, Lansing haul mud back to mud plant. Lot of Co2 on return had to choke back pump slowly pump 180 bbl to make sure mud clear up, Pressure tested CIBP 580 psi good,
2.00	RD lines off tbg lay down 5 jts tooh 172 jts in derrick.
1.00	RU WL rih to 5590' logging to surface. Crew change 6:00.

Report Start Date 4/12/2013	Report End Date 4/13/2013	Operations Summary Jsa Safety Mtg. WL rih w/ CIL down 5590' WL depth Log up to surface, RD CIL, RU CBL rih 5590' log up to surface got to together w/ Craig Wright, Mesa West, Select w WS Agree on setting 2nd CIBP @ 5545' 13' below Csg collar, Set CIBP 5545' rooh w/ WL RD MOL. Crew change out rotating head, Re adjusted rig floor. SI Select oil tools with Whipstock/ mills, Pu Achor 2.83' WS 6.24' WM 1.45' F/M 4.75' XO 1.15' 1-dp 32.22' UBHO 1.99' XO 1.66' 10- hwdp 305.72' XO 1.26, Total BHA 358.27' Lansing dig out/ line earth pit while crew ate lunch. After tih w/ Aoh out of derrick 152 jts out of derrick w/ min/ half a stand, Crew change 18:00 Jsa safety Mtg. Crew finished tih 12 jts total 164 out of derrick an Total 174 jts w/ 10- hwdp WS @ 5537.40. PU # 165 w/ WL & Gyro tool. Rih with WL/ Gyro tool down to OBHO, Then went down w #165 tag 14.40' in @ 5551.80' an oriented few times got it to 322.41 called it good, Sat down 9k shear anchor re check 320.5, pull up/ down gyro final 321.98 called it good an pull gyro up to 5000', pull up on WS 1' string not pulling over, went back down tag @ same depth 5551.80 pull up again no luck, not pulling over string weight. anchor not set or bad casing. Rooh w WL/ gyro tool RD WL. Notified Craig W. Wilson D. about WS not setting. Select order fishing tools/ another Whipstock. Crew tooh w 10 jts hwdp + 164 aoh dp standing back in derrick lay down mills. SI Double S hot shot w/ fishing tools, Pu fish tools w/ hook. Rih w aoh 164 + 10 hwdp, jar, hook pu 165 an tag WS, Work the hook up/ down to get in slot an rotated ed tbg work it for 45 min no sign of toque tooh w 128 jts no sign of drag or weight change. Crew change at 6:00.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
5.50	Jsa Safety Mtg. WL rih w/ CIL down 5590' WL depth Log up to surface, RD CIT, RU CBL rih 5590' log up to surface got to together w/ Craig Wright, Mesa West, Select w WS Agree on setting 2nd CIBP @ 5545' 13' below Csg collar, Set CIBP 5545' rooh w/ WL RD MOL.
1.50	Crew change out rotating head, Re adjusted rig floor.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
1.50	Pu Achor 2.83' WS 6.24' WM 1.45' FM 4.75' XO 1.15' 1-dp 32.22' UBHO 1.99' XO 1.66' 10- hwdp 305.72' XO 1.26, Total BHA 358.27
1.00	Lansing dig out/ line earth pit while crew ate lunch.
2.50	After tih w/ Aoh out of derrick 152 jts out of derrick w/ min/ half a stand,
0.50	Crew change Jsa safety Mtg. Crew finished tih 12 jts total 164 out of derrick an Total 174 jts w/ 10- hwdp WS @ 5537.40.
1.00	PU # 165 w/ WL & Gyro tool.
1.00	Rih with WL/ Gyro tool down to OBHO,
1.00	Then went down w #165 tag 14.40' in @ 5551.80' an oriented few times got it to 322.41 called it good, Sat down 9k shear anchor re check 320.5, pull up/ down gyro final 321.98 called it good an pull gyro up to 5000', pull up on WS 1' string not pulling over, went back down tag @ same depth 5551.80 pull up again no luck, not pulling over string weight. anchor not set or bad casing.
1.00	Rooh w WL/ gyro tool RD WL. Notified Craig W. Wilson D. about WS not setting. Select order fishing tools/ another Whipstock.
2.00	Crew tooh w 164 jts w/ 10 hwdp aoh dp standing back in derrick lay down mills.
1.00	SI Double S hot shot w/ fishing tools, Pu fish tools w/ hook.
4.50	Rih w aoh 164 + 10 hwdp, jar, hook pu 165 an tag WS. Work the hook up/ down to get in slot an rotated ed tbg work it for 45 min no sign of toque tooh w 128 jts no sign of drag or weight change. Crew change at 6:00.

Report Start Date	Report End Date	Operations Summary
4/13/2013	4/14/2013	Jsa Safety Mtg. Crew finished tooh with aoh 36 jts got hook to surface w/ no whipstock. MU box tap, jar, xo 1 dp, ox 10- hwdp 164 jts out of derrick tih pu #165 9.5' in 5551.80' tag up WS, Rotated over WS/ Work box tap up/ down pulling string weight over 10k. Tooh slowly dragging out of hole 450' lost drag, Pull out 41 stands out pull over again 25k then release an continue tooh w/ aoh pull whipstock to surface. Look at WS anchor look like never set against casing, set WS on rig floor an anchor set an measure out 5 1/8", 5 1/2" Csg ID 5.012. RD Select WS/ Mills fish tools mol. Notified Craig Wright fish out of hole, Suggest to Rih w baker set at same depth 5554'. Spotted in Baker w/ WS MU WS/ Mills. Tih with WS, 10- HWDP 164 jts dp @ 5537' w/ baker WS tools, MU #165 w/ WL & Gyro tool, Rih an set ubho started w/ gyro tool face 33.50 made 5 attempts got TF to 320, went down tag CIBP TF 319, Called Craig Wright ok to set 319 check TF one time 319 pu on wire line, Sat down 8k on achor & shear anchor check TF 317, Pull Gyro up to 5000' work string/ Whipstock up/ down 55k to 60k then sat down 30k shear bolt set whipstock, Notified Craig W. about setting @ 317. Rooh w/ WL & Gyro tool RD WL. Crew rig up 3" flex hose to gas buster, RD swivel up w/ # 165, Break Cir. Went down tag up start milling on cutting window 5543.99/ 1000 lbs. down on mill 1200 lbs torque, 1000 lbs Circulation pressure. @ 4 am finished milling whipstock slide from 5543.99 thru 5549.86' / Continue milling rat hole. finished milling rat hole from 5549. 86' thru 5555. 99' total of 6.13' of rat hole. Crew change 6:00 am.

Dur (hrs)	Comment
1.00	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg. Crew finished tooh with aoh 36 jts got hook to surface w/ no whipstock.
6.50	MU box tap, jar, xo 1 dp, ox 10- hwdp 164 jts out of derrick tih pu #165 9.5' in 5551.80' tag up WS, Rotated over WS/ Work box tap up/ down pulling string weight over 10k. Tooh slowly dragging out of hole 450' lost drag, Pull out 41 stands out pull over again 25k then release an continue tooh w/ aoh pull whipstock to surface.
1.50	Look at WS anchor look like never set against casing, set WS on rig floor an anchor set an measure out 5 1/8", 5 1/2" Csg ID 5.012. RD Select WS/ Mills fish tools mol. Notified Craig Wright fish out of hole, Suggest to Rih w baker set at same depth 5554'. Spotted in Baker w/ WS MU WS/ Mills.
2.00	Tih with WS, 10- HWDP 164 jts dp @ 5537' w/ baker WS tools,
0.50	MU #165 w/ WL & Gyro tool,
3.00	Rih an set ubho started w/ gyro tool face 33.50 made 5 attempts got TF to 320, went down tag CIBP TF 319, Called Craig Wright ok to set 319 check TF one time 319 pu on wire line, Sat down 8k on achor & shear anchor check TF 317, Pull Gyro up to 5000' work string/ Whipstock up/ down 55k to 60k then sat down 30k shear bolt set whipstock, Notified Craig W. about setting @ 317. Rooh w/ WL & Gyro tool RD WL.
2.00	Crew rig up 3" flex hose to gas buster, RD swivel up w/ # 165
7.50	Break Cir. Went down tag up start milling on cutting window 5543.99/ 1000 lbs. down on mill 1200 lbs torque, 1000 lbs Circulation pressure. @ 4 am finished milling whipstock slide from 5543.99 thru 5549.86' / Continue milling rat hole. finished milling rat hole from 5549. 86' thru 5555. 99' total of 6.13' of rat hole. Crew change 6:00 am.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Report Start Date 4/14/2013	Report End Date 4/15/2013	Operations Summary Jsa Safety Mtg. Jsa safety Mtg. Crew started whipstock slide assure good slide, Swivel quit working/ Acts like break is lock on swivel, RD all hose's off 3.5 swivel stiff arm's an break joint w/ Tbg tongs LD swivel w/ # 165. Down time 2 hrs, Pu 2.5 swivel xo hose's from 3.5 to 2.5. PU 2.5 swivel w/ # 165 break cir. worked whipstock slide everything looks good. Cir. well for 1 hr. RD Swivel w/ #165. lay down 25 jts on rack tooh w/ 140 jts in derrick + 10 jts Hwdp, LD mills an gauge mill 1/16 under gauge discuss with Doug w/ baker, Good to go LD tools mol. Moved 10 more hwdp to pr tally revised tally/ jt count with Mesa West 199 aoh dp + 20 hwdp total 219 jts on location, Safety Mtg w/ MW & Rig Crew about pu tools/ dp. Western Diverter arrived w new rotating head/ change out. MU 4 3/4 bit/ 3 3/4 , 5L, 3.0 motor an subscribe 2.57/ 31 degree dog leg, 1.23 float sub ,Subscribe w/ 2.87 UBHO set face tool, 1.20, Xo, 31.01 monel, 30.94 monel, UBHO, 8- jts aoh dp 252.69', 1.66" Xo, 15- hwdp. Crew change 18:00, Jsa safety Mtg. Crew finished pu 5 more hwdp total 19- hwdp @ 582.04, 1.26 Xo. Rih w/ 60 jts tested motor (good) continue rih 80 jts out of derrick total 140 jts, Pu 6 jts off float w/ swivel an caliber depth logger, PU # 147 w/ wire line/ gyro tool rih tag 5453' set in face tool 135.04, inclination 0.77 Azmth 336.97. break cir. slide from 5553' to 5564' inclination 1.80 azmth 332.81, Gyro connection slide 5564' to 5570' inclination 1.80 azmth 331.52 return fine sand/ water, losing 12 bbl an getting it back 12 bbl. Crew change at 6:00.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
1.00	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg, Jsa safety Mtg. Crew started whipstock slide assure good slide, Swivel quit working/ Acts like break is lock on swivel, RD all hose's off 3.5 swivel stiff arm's an break joint w/ Tbg tongs LD swivel w/ # 165.
2.00	Down time 2 hrs
1.50	Pu 2.5 swivel xo hose's from 3.5 to 2.5. PU 2.5 swivel w/ # 165 break cir. worked whipstock slide everything looks good. Cir. well for 1 hr
2.50	RD Swivel w/ #165. lay down 25 jts on rack tooh w/ 140 jts in derrick + 10 jts Hwdp, LD mills an gauge mill 1/16 under gauge discuss with Doug w/ baker, Good to go LD tools mol
1.00	Moved 10 more hwdp to pr tally revised tally/ jt count with Mesa West 199 aoh dp + 20 hwdp total 219 jts on location,
0.50	Safety Mtg w/ MW & Rig Crew about pu tools/ dp.
1.50	Western Diverter arrived w new rotating head/ change out.
2.00	MU 4 3/4 bit/ 3 3/4 , 5L, 3.0 motor an subscribe 2.57/ 31 degree dog leg, 1.23 float sub ,Subscribe w/ 2.87 UBHO set face tool, 1.20, Xo, 31.01 monel, 30.94 monel, UBHO, 8- jts aoh dp 252.69', 1.66" Xo, 15- hwdp.
3.00	Crew change 18:00, Jsa safety Mtg. Crew finished pu 5 more hwdp total 19- hwdp @ 582.04, 1.26 Xo. Rih w/ 60 jts tested motor (good) continue rih 80 jts out of derrick total 140 jts, Pu 6 jts off float w/ swivel an caliber depth logger,
3.50	PU # 147 w/ wire line/ gyro tool rih tag 5453' set in face tool 135.04, inclination 0.77 Azmth 336.97.
2.50	break cir. slide from 5553' to 5564' inclination 1.80 azmth 332.81,
3.00	Gyro connection slide 5564' to 5570' inclination 1.80 azmth 331.52 return fine sand/ water, losing 12 bbl an getting it back 12 bbl. Crew change at 6:00.

Report Start Date 4/15/2013	Report End Date 4/16/2013	Operations Summary Jsa Safety Mtg. Continue Sliding from 5570' to 5583', Mesa West suggest don't need Gyro any more. Kick put pump rooh w/ WL, Gyro tool lay down gyro, RD WL MOL. Continue slide from 5582' to 5590' after motor unable to slide/ making no hole, Cir. well, Lay down 2 jts, RD swivel hang back in derrick. Tooh w/ aoh 146 jts, Xo 19 jts hwdp xo 8 aoh dp 2- monels, Ox, ubho, float sub, motor, bit. LD down motor/ Pu new motor re adjust motor from 2.57 to 2.83 @ 34 degree, Re orient mule shoe to high side, string float, ubho, MU 2- monel's 8jts dp, ox, 19 hwdp ox 66 jts aoh out of derrick. Crew change 18:00, Jsa safety Mtg. Finished rih w/ 80 out of derrick total 146 on top of bha. Ru swivel/ pu 147- 148 / swivel tag 5590' break cir. 1100 psi on Tbg. Continue sliding 9k on bit from 5589' to 5594' survey @ 5561' Inc.- 2.6, slide from 5594' to 5625' survey @ 5592' Inc. 9.4, Azm 48', slide from 5625' to 5635' check shots @ 5602' Inc.-13.4, Azm 42, slide from 5635' to 5644' trying to get better reading but check shots @ 5602' Inc. 17.1, Azm 43' at that point sliding wrong way. Notified Craig W. Jason B. about direction Azm of 43'. Suggested to pull back in 5 1/2 wait for orders. Cir. well, pooh lay down 5 jts back to 146 an back in csg. Shut down wait for orders. Crew change at 6:00. wait on orders.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
2.50	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg. Continue Slidding from 5570' to 5583', Mesa West suggest don't need Gyro any more.
1.00	Kick put pump rooh w/ WL, Gyro tool lay down gyro, RD WL MOL.
2.00	Continue slide from 5582' to 5590' after motor unable to slide/ making no hole, Cir. well
1.50	Lay down 2 jts, RD swivel hang back in derrick
2.50	Tooh w/ aoh 146 jts, Xo 19 jts hwdp xo 8 aoh dp 2- monels, Ox, ubho, float sub, motor, bit. LD down motor
1.00	Pu new motor re adjust motor from 2.57 to 2.83 @ 34 degree
1.50	Re orient mule shoe to high side, string float, ubho, MU 2- monel's 8jts dp, ox, 19 hwdp ox 66 jts aoh out of derrick.
1.00	Crew change 18:00, Jsa safety Mtg. Finished rih w/ 80 out of derrick total 146 on top of bha.
1.00	Ru swivel/ pu 147- 148 / swivel tag 5590' break cir. 1100 psi on Tbg.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
7.00	Ru swivel/ pu 147- 148 / swivel tag 5590' break cir. 1100 psi on Tbg. Continue sliding 9k on bit from 5589' to 5594' survey @ 5561' Inc.- 2.6, slide from 5594' to 5625' survey @ 5592' Inc. 9.4, Azm 48', slide from 5625' to 5635' check shots @ 5602' Inc.-13.4, Azm 42, slide from 5635' to 5644' trying to get better reading but check shots @ 5602' Inc. 17.1, Azm 43' at that point sliding wrong way. Notified Craig W. Jason B. about direction Azm of 43'. Suggested to pull back in 5 1/2 wait for orders.
1.50	Cir. well, pooh lay down 5 jts back to 146 an back in csg.
1.00	Shut down wait for orders.
0.50	Crew change at 6:00. wait on orders.

Report Start Date 4/16/2013	Report End Date 4/17/2013	Operations Summary Waited on orders. Orders were to TOH with Mesa West tools.. Hang swivel back and start out with tools. shut down operations due to high winds in the area. After winds die down finish TOH with tools. Check tools motor was still adjusted at 2.83. Break down tools. crew change at 18:00 tail gate safety meeting with all contractors on location topic was hand placement, job task, suspended loads, wireline operations. Make up BHA with 4 3/4 bit, bit sub and TIH with 171 jts to 5387.. Picked up 4 jts and tag top of window at 5543. Slide on through with out no drag. Tag bottom with jt 180 at 5642. Rig up wireline and picked up Gyrodata tools . Run on in and survey from surface to bottom with 200 ft Incl to top of window at 5543 to 5556. with Azimuth of 347.52. 9 ft later with a 45% turn putting Azimuth at 43.32 from 5556 to 5565. Survey show all tools were working properly. Discuss next operations with Craig Wright. Circulate well clean and lay down 8 jt to get above the window. TOH out with BHA.. Crew change at 6:00 am safety meeting with contractors on location topic was team work, tripping DP, wireline operations., Spot in wireline and rig up
--------------------------------	------------------------------	---

Dur (hrs)	Comment
3.00	wait on orders
0.50	rig down power swivel and hand back
1.00	start TOH with BHA
5.00	waited on wind to die down
1.50	finish TOH with BHA
1.00	check all Mesa West tools and break down
0.50	crew change safety meeting topic was hand placement, job task, suspended loads, wireline operations
0.50	make up BHA with bit and bit sub
2.50	TIH with 171 jt to 5383.
1.00	pick up 2 jt an go through window run on down to 5642 and tag.
1.00	rig up wireline and pick up gyrodata tools
2.00	run tools and survey hole
1.00	circulate well clean
2.50	lay down 8 jt and TOH with BHA
0.50	crew change at 6:00 am saety meeting with contractors on location topic was tripping DP, tong operations, team work
0.50	rig up wireline

Report Start Date 4/17/2013	Report End Date 4/18/2013	Operations Summary This is the report on Aneth Unit H-222 Capital Injector Key rig # 27 Finish rigging up wireline and pick up CIBP run on in and set at 5522 top of plug. Come out and rig down wireline Wait on Baker to bring out 5 1/2 whipstock. Make up BOH with 5 1/2 Anchor, 5 1/2 whipstock, 4 3/4 window mill, 4 3/4 watermelon mill that were check for gauge, 3 1/8 OD flex pup jt, 2 7/8 AOH x 2 7/8 Pac, UBHO sub, H-90 x 2 7/8 AOH, 19 jts of heavy weight spiral DP, 2 7/8 H-90 x AOH DP and 150 jt of DP to the depth of 5347. Pick-up 5 jt and rig up BlueJet wireline on the 6 jt with Gyrodata tools. Run on in and survey every 1000 ft. Crew change at 18:00 hour safety meeting with contractors on location topic was wireline operations, high pressure lines, keeping up with fluids, communication, Orient whipstock with gyro tool face at 322.02. Have wireline pull up 1000 ft. Shear-off whipstock. Rig down BlueJet and Gyrodata and release. Rig up power swivel and establish circulation. Tag and start milling out casing with pump pressure at 900 psi with 4-K down with good returns of metal, cement, formation shale, Milled out to 5524. Pull-up and circulate well clean. Crew change at 6:00 tail gate safety meeting with contractors on location topic was job task, tripping DP, hand placement. Hang back swivel and TOH with tools
--------------------------------	------------------------------	--

Dur (hrs)	Comment
2.00	spot and rig up wireline to set cibp at 5522
3.00	wait on baker tool hand to deliver whipstock
2.00	pick up 5 1/2 whipstock with anchor and make up
3.50	TIH with tools tally in
1.50	pick-up 5 jts and rig up wireline on the 6 jt pick-up gyro tools and run on in and survey every 1000 ft on the way in
0.50	crew change at 18:00 hours safety meeting with contractors on location topic was wireline operations, high pressure lines, keeping up with fluids, communication
2.00	set and orient whipstock at 322.02 come out and release wireline and gyrodata
1.00	rig up power swivel
6.50	tag and establish circulation and start milling on casing
1.00	circulate well clean
0.50	crew change at 6:00 safety meeting with crew topic was tripping DP, hand placement, job task



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)		Comment
0.50		hang back swivel and start TOH with tools
Report Start Date 4/18/2013	Report End Date 4/19/2013	<p>Operations Summary</p> <p>This is the report on H-222 Capital Injector Key rig #27 Finish TOH with tools. Rig up Mesa west tools with 4 3/4 bit, 3 3/4 3 stage motor, float sub, UBHO sub, x-over, 2 flex Monels, Gyrodata UBHO sub, Rig up to test motors (Good Test) TIH with 8 joints of AOH DP, x-over and 18 jts of spiral heavy weight DP x-over and 146 jts of AOH. Test motors half way in (Good Test). TIH to the depth of 5481 Change out to longer bails. Rig up swivel on jt 173 and BlueJets lubricator to the top of swivel. Pick-up jt and make up gyro tools. Run on in and survey every 1000 ft. Seat for proper tool face. Bring pump on line with 1000 psi at 2 bbl a min. Had no readings in gyro tool. Pull tool to check cable head and gyro tools. Replace gyro tools, computer, and re-head wireline cable. Pick up tools, run on in seat to get tool face. Put pump on line with 1300 psi on pressure Slide from 5522 to 5530. Gyro up date Azimuth at 339.43 Inclination at .6 Tool Face at 326.3. Slide from 5530 to 5536. Gyro connection. Slide from 5536 to 5545 Gyro up date Azimuth at 336.3 Inclination at .74 Tool Face 10.51. Slide from 5545 to 5558 drift up date Azimuth at 333.86 Inclination at .77 Tool Face 9.35. Slide from 5558 to 5568 Gyro up date Azimuth at 332.32 Inclination at .80 Tool Face 18.56. Gyro connection. Crew change at 6:00 safety meeting with contractors on location topic was wireline operations, job task, teamwork Continue to slide drill.</p>

Dur (hrs)		Comment
1.00		hang back swivel and lay down 5 jts
2.50		TOH with BHA
2.00		break down Baker tools and load. Pick up Mesa West tools make up BHA with bit, motor, float sub, UBHO , 2 flex monels, gyro data UBHO sub, 8 jts, xover, 18 HWDP, xover. ttest motors
2.50		TIH with Directionals tools test motor half way in
1.50		change out bails and rig up power swivel on jt 173 rig up wireline lubricator
1.50		run on in and survey every 1000 ft
1.00		set tool face bring pump on line and lost signal and pull tools
3.00		check tools and cable head cre change safety meeting with contractors on location topic was wireline operations, high pressure lines, communication.
3.50		run in with wireline seat and get tool face kick on pump tp 1000 psi at 2 bbl a min tag and start drilling ahead
1.00		pull tools for gyro connection test tools for high side
4.00		slide drill from 5536 to 5568
0.50		crew change at 6:00 am safety meeting with contractors on location topic was wireline operationss, job task, teamwork
Report Start Date 4/19/2013	Report End Date 4/20/2013	<p>Operations Summary</p> <p>This is the repot on H-222 Capital Injector Key rig #27 Slide drill from 5568 to 5583 Gyro up date Azimuth at 325.25, Inclination 16.10 Slide from 5583 to 5599. gyro up date Azimuth at 326.40 Inclination 16.10. Circulate well clean and pull up wireline for gyro connection. Slide from 5599 to 5631 gyro up date Azimuth 325.10 Inclination 24.70. Circulate well clean pull up and release wireline truck and gyro data. Make connection and slide from 5631 to 5644 Shut down to work on rig pump. Crew change at 18:00 hours safety meeting with contractors on location topic was high pressure lines, job task, keeping and eye on fluids, communication. Reestablish circulation and slide from 5644 to 5663. Survey at 5630. Inclinations at 34.1 azimuth of 323.3 323.3. Slide from 5663 to 5672. when close loop hand notices an pit gain. notified rig operator. Pull up and monitor well through choke. Well unloaded with 100% LEL. good amount of CO2. Pressure climbing up to 1400 psi. Shut in well due to wind direction. Call in for kill weight fluids. Wait on trucks to haul out 15# mud. Run mud across shakers. Open well through choke and bleed of pressure down to 600 psi. Start to pump kill weight fluid kept an eye on pressure. Crew change at 6:00 tail gate safety meeting with crew topic was keeping and eye on fluids, pump pressure, job task. Continue to pump kill weight fluids.</p>

Dur (hrs)		Comment
3.00		continue to slide drill from 5568 to 5583
9.00		circulate well clean pull wireline and lay down tool and test for high side slide drill from 5583 to 5644 with 10 K down and pump pressure at 1350 psi with good returns of formation drill out 61 feet with the help og gyrodata
0.50		crew change safety meting with contractors on location topic was high pressure lines, job task, communication
1.00		work on rig pump
2.00		continue to drill from 5644 5672. with good returns. a total of 28 ft with pump pressure of 1350 psi
1.00		had a pit gain well started to comr around monitor pressure through choke shut in well due to wind direction
3.00		wait on trucks to haul mud from mud plant
2.00		open well through choke and monitors pressure starting at 1400 psi down to 600 psi welll making CO-2
1.00		mud arrived run mud across shakers
1.00		started pump 15# mud keep and eye on pressure
0.50		crew change at 6:00 safety meeting with crew topic was keeping and eye on fluids, pump pressure, job task



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Report Start Date 4/20/2013	Report End Date 4/21/2013	Operations Summary This is the report on AU H-222 Capital Injector. Key Rig # 27 Finish pumping 15.# mud. the well was starting to take fluids. the hole is full and no pressure. pulled up 1 jt with swivel and lay it down. Swivel up on next jt pulled up 15 ft and was stuck. The weight indicator pads was not working properly. Call Craig and discuss next operations.. Decided to circulate well around with P/W to try and get back into window. Waited on water truck to arrive. Start filling up 400 bbl tank. Pumped 40 bbls down tubing it started to pressure up Release pressure and had pumper start wagging G-122 with water. Called out Select Tool hand while waiting replace weight indicator pads and monitor well. Started pull 15 to 20 over and working tubing up and down when it started to move. Crew change at 18:00 safety meeting with contractors on location topic was stay off floor when pulling on DP, tong operations, suspended loads. Work tubing up 30 ft with swivel and lay down jt and continue to work tubing free. Work BHA back in top of window. Waited on kill weight fluids for displacement when TOH with BHA. Start out of hole with BHA. Lay down Mesa West tools. Make up BHA with 4 3/4 bit, bit sub, 8 jts of AOH, 18 jts of HWD, and tally back in.. Crew change at 6:00 am safety meeting with crew topic was tripping DP, communication, teamwork. Continue to TIH
Dur (hrs)		Comment

2.00 finish killing well with 15 # mud through choke manifold
 2.00 lay down jt 151 with swivel pull up on jt 150 about 15 ft up when tubing became stuck.
 3.00 call out water truck to haul in PW
 2.00 had pumper wag well G-1222 and replace weight indicator pads
 3.50 start working tubing up and down and rotate with swivel pull up 30 ft and lay down jt with swivel
 0.50 crew change at 18:00 safety meeting with rig crew topic was staying of rig floor when pulling on DP, tong operations, suspended loads
 3.00 continue to work on pulling DP and BHA back to the top of window
 2.50 had water truck haul in 13# mud and run across shakers for displacement
 3.50 TOH with BHA and pump displacement
 1.50 brake down Mesa West tools and make up BHA with 4 3/4 bit and bit sub tally back in
 0.50 crew change at 6:00 am safety meeting with crew topic was tripping DP, communication, teamwork

Report Start Date 4/21/2013	Report End Date 4/22/2013	Operations Summary Jsa safety Mtg. Crew finished pu last 8 jts w/ swivel tag with 180 5670' work pipe up/ down. Lansing finished load up right w/ 280 bbls 10# brine. Break Cir. to flow back tank, Circulated 13 & 14# mud out of well w/ 10# brine 145 bbls, pump another 5 bbls total 150 bbl 10# brine. SWI well pressure 550 psi, SIW for 30 min pressure up to 850 psi. Went SI H122/ G122 injection wells Notified the pumper/ Lynn Begay/ Craig Wright. Open well flow back 10# back to FB tank lot of Co2, H2S, Fluid. Bled well down to 150 psi, pump another 200 bbl of 10# Down Tbg out Csg fluid did not come back to FB tank, blowing gas down to 0psi well dead. Crew change at 18:00, Crew lay down 7 jts back on cat walk. Waited on order/ monitor well for hour an well started to flow. Craig W. called roll hole w/ pw, wait for mud engineer to mix LCM w/ mud. Roll the hole w/ pw 480 bbl to fb tank w/ some gas pockets, kick out pump pressure drop down to 20 psi an pick up pressure up to 950 psi shut in 30 min. Lansing haul fb to A1/ D6. Open well to fb tank flow well back unloaded p/w, Lot of gas blowing to fb tank 30 to 50 h2s, LEL 4. blow down 250 psi mostly gas/ very little fluid coming back. Lansing haul 545 bbl to D6/ A1. Crew change @ 6:00 AM.
Dur (hrs)		Comment

2.50 Jsa safety Mtg. Crew finished pu last 8 jts w/ swivel tag with 180 5670' work pipe up/ down.
 3.00 Lansing finished load up right w/ 280 bbls 10# brine. Break Cir. to flow back tank, Circulated 13 & 14# mud out of well w/ 10# brine 145 bbls, pump another 5 bbls total 150 bbl 10# brine. SWI well pressure 550 psi, SIW for 30 min pressure up to 850 psi. Went SI H122/ G122 injection wells Notified the pumper/ Lynn Begay/ Craig Wright
 6.50 Open well flow back 10# back to FB tank lot of Co2, H2S, Fluid. Bled well down to 150 psi, pump another 200 bbl of 10# Down Tbg out Csg fluid did not come back to FB tank, blowing gas down to 0psi well dead.
 1.00 Crew change at 18:00, Crew lay down 7 jts back on cat walk.
 1.00 Waited on order/ monitor well for hour an well started to flow. Craig W. called roll hole w/ pw, wait for mud engineer to mix LCM w/ mud.
 3.50 Roll the hole w/ pw 480 bbl to fb tank w/ some gas pockets, kick out pump pressure drop down to 20 psi an pick up pressure up to 950 psi shut in 30 min. Lansing haul fb to A1/ D6.
 6.50 Open well to fb tank flow well back unloaded p/w, Lot of gas blowing to fb tank 30 to 50 h2s, LEL 4. blow down 250 psi mostly gas/ very little fluid coming back. Lansing haul 545 bbl to D6/ A1. Crew change @ 6:00 AM.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Report Start Date 4/22/2013	Report End Date 4/23/2013	Operations Summary Jsa safety Mtg. Crew continue flowing back well to FB tank 500 psi gas/ fluid, H2S 30 & 50 psi SWI due to wind direction to CO2 plant, SIP 450 psi. Waited for Halliburton Mud Engineer to arrive, Engineer arrive @ 13:00. Got sample of MW 13.25# & tested. Mtg with Craig W. about mixing/ pumping mud. Got back to rig, Lansing fill up 400 bbl FW up right tank. Continue to roll out 87 bbls mud to reserve tank, started to mix mud w/ 99 bbl in loop tank an added 100 bbls of FW to bring down 10.2# mud. Safety mtg 9 people about pumping mud/ pressure. Started pumping mud down tbg out csg, Csg 800 psi, Tbg 500 psi pumped pressure an Co2 on return. Blow down csg to 0 psi after pumping 100 bbl 10.2 # mud. Pumped 150 bbls, finally got return back at loop system. Circ. 20 min, lost 30 bbls, SD pump. Unloaded/ materials of dash truck. Started adding FW to mud/ bring down 10#. Added 10 sks zeogel, 6 sks stop hit, 3 sks cedar fiber, 2 sks N seal, total 8% LCM to start with. Swivel up/ PU 3 jts down to #176, 5546' and break circ. w/ 500 pump psi 3 bpm. Circ. well for hr, got back 9.8# mud return w/ no gas or CO2. Made 2 jts down 5609' #178, continue adding very little of zeogel, stop hit, N seal working slide up/ down. PU #179 & 180 working slide with no drag or any sign of CO2/ H2S. Work slide down to 5670' w/ MW 9.8#, circ. well, fluid staying @ 176 bbl in loop system, no loss or gain. Notified Craig W., OK to move on. TOOH w/ DP & bit. Slug 20 bbl with 13# mud down tbg on vac for dry trip. Started RD swivel.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
3.00	This is the report on AU H-222 Capital Injector. Key Rig # 27, Jsa safety Mtg. Crew continue flowing back well to fb tank 500 psi gas/ fluid, H2S 30 & 50 psi SWI do to wind direction to Co2 plant, SIP 450 psi
4.00	Waited for Halliburton Mud Engineer to arrive,
1.50	Engineer arrive @ 13:00, Got sample of mud/ weigh 13.25# & tested
1.00	Mtg with Craig W. about mixing/ pumping mud.
3.00	Lansing fill up 400 bbl fw in up right tanl, Continue to roll out 87 bbls mud to reserve tank, started to mix mud w/ 99 bbl in loop tank added 100 bbls of fw to bring down 10.2# mud.
0.50	Safety mtg 9 people about pumping mud/ pressure.
1.00	Started pumping mud down tbg out csg, Csg 800 psi, Tbg 500 psi pumped pressure an Co2 on return. Blow down csg to 0 psi after pumping 100 bbl 10.2 # mud. Pumped 150 bbls finally got return back at loop system, cir. about 20 min lost 30 bbl SD pump
1.50	unloaded/ materials of dash truck.
1.00	.Started adding fw to mud/ bring down 10#,
7.00	Added 10 sks zeogel, 6 sks- stop hit, 3 sks- ceder fiber, 2 sks- N seal total 8% LCM to start with. Swivel up/ pu 3 jts down to # 176 5546' an break cir. w/ 500 pump psi 3 bpm, Cir. well for hr got back 9.8# mud return w/ no gas or co2. made 2 jts down 5609' #178 continue adding very little of zeogel, stop hit, N seal working slide up/ down, Pu #179 & 180 working slide with no drag or any sign of co2/ h2s, work slide down to 5670' w/ MW 9.8# cir. well fluid staying @ 176 bbl in loop system no lost/ or gain. Notified Craig W. ok to move on tooh w/ dp & bit.
0.50	Slug 20 bbl with 13# mud down tbg on vac for dry trip, Started rd swivel Crew change at 6:00.

Report Start Date 4/23/2013	Report End Date 4/24/2013	Operations Summary Crew finished RD swivel and LD 8 jts on pipe rack. TOOH pumping 6 bbls 9.8# mud every row. TOOH w/146 jts when well start flowing. SD SWI CP @ 600 psi. Tbg dead, installed TIW valve, 9.8# mud in loop system and build up to 10.1 to top kill tbg. Started pumping down tbg 500 psi, Csg 600 psi, open to FB tank. Pump 30 bbls 10.1 mud, csg 0, tbg 0, well dead for sec. Installed string float, RIH w/1 jt, had kick, casing side 500 psi. Choke back 50%, continue RIH w/DP 172 jts 5419'. Csg flowing @ 200 psi to FB tank. SWI wait for orders from Engineers. New contact person Jeremy Ray, Engineer- Denver. Dicussed and agree w/ 10.2 MW to pump, csg 600 psi and open to FB tank. Pumped 10.2 mud down tbg, 500 psi pump pressure, csg 0 psi after pumping 80 bbls 10.2 mud. Pump another 70 bbls, total mud return to shaker MW 9.8. Pump another 10 bbls, MW 10.1, total 160 mud pumped. Kick out pump well 0 psi. RD hoses off tbg, open pipe ram. TOOH w/DP standing back in derrick, PO 48 jts. Continue TOOH w/DP, pumping 10.1 mud every row, keep casing full. TOOH LD bit/ sub. Well still dead, PU 4 3/4 bit, motor, ubho, XO, flex monels. Tested motor (good). RIH 60 jts DP, XO, 18 jts hwdp + 17 jts on hwdp, total 95 jts. Tested MWD tool/ motor, pump pressure kept comming up 1700 psi to test motor, acting like plugged hole. TOOH w DP/ hwdp, monels, MWD tool, LD. Test motor at surface (good), MWD checked out good. BO ubho, found little pieces of trash, found that didn't put screen on when testing. Put BHA back together, test motor (good). RIH w/10 jts, test motor (good) but MWD not reading right. Pit hand went to mud plant to get de-former to put in mud. Crew RIH with 95 jts. Pit man came back, dumped de-former in pit and circ. 10 min. MWD tool reading good, continue RIH with DP.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
3.00	This is the report on AU H-222 Capital Injector. Key Rig # 27, Jsa safety Mtg. Crew finished rd swivel an lay down 8 jts on pipe rack. Tooh pumping 6 bbls 9.8# mud every row tooh w/ 146 when well start flowing
3.00	SD SWI CP @ 600 psi, Tbg dead installed Tiw valve, 9.8# mud in loop system an build up to 10.1 to top kill tbg. Started pumping down tbg 500 psi, Csg 600 psi open to fb tank pump 30 bbls 10.1 mud csg 0, tbg 0. well dead for sec
1.00	Installed string float rih w/ 1-jt had kick casing side 500 psi choke back 50%, Continue rih w/ dp 172 jts 5419' csg flowing @ 200 psi to fb tank.
3.00	SWI wait for orders from Engineer's.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)		Comment
		<p>1.00 New contact person Jeremy Rae- Engineer- Denver, Dicussed an agree w/ 10.2 MW to pump. Csg 600 psi an open to fb tank, Pumped 10.2 mud down tbg 500 psi pump pressure, Csg 0 psi after pumping 80 bbls 10.2 mud pump another 70 total mud return to shaker MW 9.8 pump another 10 bbls MW 10.1 total 160 mud pump, kick out pump well 0 psi.</p> <p>1.00 RD hose's off Tbg open pipe ram tooh w/ dp standing back in derrick PO 48 jts. Crew change 18:00</p> <p>2.00 Continue tooh w/ dp pumping 10.1 mud every row keep casing full. TooH lay down bit/ sub.</p> <p>1.50 Pu 4 3/4 bit, motor, ubho, ox, flex monel's. Tested motor (good)</p> <p>1.50 Rih 60 jts dp, ox, 18 jts hwdp + 17 jts on hwdp total 95 jts tested mwd tool/ motor pump pressure kept comming up 1700 psi to test motor acting like plug hole.</p> <p>2.50 TooH w dp/ hwdp monel's mwd tool ld</p> <p>2.00 Test motor at surface (good) mwd check out good. BO ubho found little peace's of trash, found that didn't put screen when testing. Put back bha together test motor (good).</p> <p>2.50 Rih w/ 10 jts test motor (good) but mwd not reading right, Pit hand went to mud plant to get de former to put in mud, crew rih with 95 jts pit man came back dump de former in pit an cir. 10 min, Mwd tool reading good, continue rih with dp. Crew change 6:00.</p>
Report Start Date 4/24/2013	Report End Date 4/25/2013	<p>Operations Summary</p> <p>Finished RIH with DP/ BHA down to 5440'm check MWD tool, motor (good). Put screen in surface jt to circ. but plugged up - trash in screen. Pressure up 1500 psi, went thru routine for about hour, finally plug up down hole. Notified Jeremy Ray, agree to POOH w/tbg. KO pump RD hoses off tbg. TOO H w/DP, BHA, wet pull. LD BHA w/motor. PU bit/sub, RIH w/DP, hwdp down to 5611', 180 jts tbg depth only. Csg started blowing gas to FB tank. Flow back well for 30 min, SWI, wind towards CO2 plant. Kick pump in, circ down tbg out csg. Csg blowing gas to FB tank 500 psi. Pump 120 bbls, csg 0 psi. Switch return to loop system and clean out well. Return a lot of LCM, made 3 poly sweeps, LCM cleared up. Mesa West agreed on mud clean, kick out pump well dead. LD 8 jts on catwalk, TOO H w/DP, hwdp. LD bit/sub, PU motor, MU bit and threads on bit twisted off when making up. LD motor, didn't have another 4 3/4 bit - CH34MRS on location. Notified Donnie T, Jeremy R. agreed on using 4 3/4" bit CH24MRS. PU another motor & 4 3/4 bit CH24MRS, ubho, XO, flex monels, tested motor- mwd tool (good). RIH w/ 60 jts DP, 18- hwdp. RIH w/rest of tbg out of derrick. PU 5 jts off rack to #177, 5599' swivel up.</p>
Dur (hrs)		Comment
		<p>1.00 This is the report on AU H-222 Capital Injector. Key Rig # 27, Jsa safety Mtg. Finished rih with dp/ bha down to 5440' check mwd tool, motor (good).</p> <p>2.50 Put screen in surface jt to cir. but plug up/ trash in screen pressure up 1500 psi went thru routine for about hour finally plug up down hole.</p> <p>4.50 Notified Jeremy Rae agree to pooh w/ tbg. KO pump rd hose's off tbg tooh w/ dp,bha. wet pull. ld bha w/ motor.</p> <p>4.00 pu bit/ sub rih w/ dp, hwdp down to 5611' 180 jts tbg depth only. csg started blowing gas to fb tank flow back well for 30 min swi wind towards co2 plant. Kick pump in cir down tbg out csg, Csg blowing gas to fb tank 500 psi pump 120 bbls csg 0 psi.</p> <p>4.00 Crew change 18:00, Jsa safety Mtg Switch return to loop system an clean out well. return a lot of lcm made 3 poly sweeps lcm clear up, Mesa West agree on mud clean, kick out pump well dead.</p> <p>3.00 LD 8 jts on cat walk tooh w/ dp, hwdp, ld bit/ sub. Pu motor mu bit an threads on bit twisted off when making up. ld motor, didn't have another 4 3/4 bit-CH34MRS on location. Notified Donnie T, Jeremy R. agree on using 4 3/4" bit CH24MRS.</p> <p>2.00 Pu another motor & 4 3/4 bit CH24MRS, ubho, xo, flex monels, tested motor- mwd tool (good).</p> <p>3.00 Rih w/ 60 jts aoh dp, 18- hwdp rih w/ rest of tbg out of derrick. pu 5 jts off rack to #177 5599' swivel up. Crew change 6:00</p>
Report Start Date 4/25/2013	Report End Date 4/26/2013	<p>Operations Summary</p> <p>Crew finished RU swivel, calibrate depth tracker (good). Break Circ, slide from 5672' to 5678'. Mule shoe packed off, had to work DP. Slide from 5678' to 5693', survey @ 5660' Inc 43.2 Az 323.1. Slide from 5693' to 5725', survey @ 5692' Inc 50.4 Az 322.4. Slide from 5725' to 5749', rotate from 5749' to 5756', survey @ 5723' Inc 56.4 AZ 321.9. Slide 5756' to 5771', slide from 5771' 5776'. Rotate from 5776' 5788', survey @ 5755' Inc 61.5 AZ 322.4. As of this morning, sliding from 5788' to 5812' w/ MW 9.9#, Vis 48, ph 7.3, temp 100, pump rate 60 SPM, soils 6.2%, sand 0.50 %, LCM 0%.</p>
Dur (hrs)		Comment
		<p>3.50 Jsa safety mtg, crew finished ru swivel, break cir. tag up at 5672' w #178. slide from 5672' to 5678' mule shoe packed off so work pipe up/ down got cir. back.</p> <p>1.75 good cir. to loop system 9.9# mud vis 47 ph 8 130 bbl no lost or gain slide from 5678' to 5693'.</p> <p>3.75 slide from 5693' to 5725' survey @ 5692' Inc 50.4 AZ 322.4 return shall/ sand. good cir.</p> <p>3.00 mud at 9.9# siding w/ good cir.</p> <p>2.25 Dash hot shot deliver 2 aoh dp, torque gage for aoh. haul back 2 aoh that were bad, 1- mud motor.</p> <p>3.75 slow drilling</p> <p>6.00 slow drilling with good return of fine sand/ shell no h2s or co2. no kick yet. no fluid lost or gain in the last 6 hrs. Crew change @ 6 am.</p>
Report Start Date 4/26/2013	Report End Date 4/27/2013	<p>Operations Summary</p> <p>Continue to slide and rotate from 5788 to 5883</p>



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)		Comment
		4.00 slide and rotate from 5788 to 5808
		6.00 connection pick up jt 183 and continue to slide from 5808 to 5820 ROP at 5 ft an hour slide from 5820 to 5881
		0.50 pick up jt 183 and establish circulation.5818 to 5851
		0.50 hold safety meeting with all contractors on location topic was keeping and eye on all fluids and report all pit gains and loss we are 11 ft away from DC2C1A had ABS safety check all monitors
		1.00 continue to slide from 5851
		0.50 crew change at 1800 tail gate safety meeting with contractors on location topic was high pressure lines,communication, team work, keeping an eye on fluids.
		3.50 continue to slide to 5860
		1.50 drilled into DC2C had an pit gain of 40 bbls pull up and shut in pipe rams and monitor pressure, pressure climbing up to 250 psi open well through choke and vent off gas to flare stack. up mud weight to 9.9 start pumping and re-condition well bore and work out gas bubble.
		4.00 continue to slide and rotate from 5860 to 5878. circulate well clean make an connection on jt 185 start slide drilling from 5883.
		2.50 continue to slide from 5883 to 5895 crew change at 6:00
Report Start Date 4/27/2013	Report End Date 4/28/2013	Operations Summary Slide and rotate ahead to target Depth of 7376 (TMD)
Dur (hrs)		Comment
		0.50 safety meeting with all contractors on location topic was watch all fluids, high pressure lines, job task
		5.00 slide from 5883 to 5914 run a survey Inc at 78.5 Az 321.5 start rotating from 5914 to 5946. run a survey
		0.50 make a connection with jt 187
		3.00 rotate from 5946 to 5956 slide 5956 to 5968 rotate from 5968 to 5977 with 12 K down Survey at 5944 Inc at 84.4 az at 323.5
		0.50 make an connection and pick up jt 188
		1.00 rotate from 5968 to 5983 survey at
		0.50 connection pick up jt 189 mud weight still at 10. vist at 46.
		1.00 continue to rotate from 6009 to 6024 survey at
		0.50 crew change at 18:00 safety meeting with contractors on location topic was high pressure lines, job task, teamwork
		2.50 rotate from 5977 to 6009 survey at 5976 inc at 82.6 Az at 321.0
		4.00 continue to rotate from 6041 to 6072 survey at 6039 Inc at 83.0 Az at 321.5 rotate from 6072 to 6094
		2.00 shut down due to swivel pull up and lay down jt 191 while working on swivel the well started to flow pressure running up to 400 psi open well through choke and release gas to flare stack and monitors pressure circulate gas around with 10# mud. pull up on jt 190 to make sure we are no stuck work pipe up and down
		1.00 pick up jt 192 and continue to rotate on down to 6104. make connection.
		2.00 continue to rotate from 6104 to 6135. survey at 6039 Inc at 83.3 Az 321.6 crew change at 6:00
Report Start Date 4/28/2013	Report End Date 4/29/2013	Operations Summary Rotate to 6167 Trip for bit and motor
Dur (hrs)		Comment
		0.50 safety meeting with all contractors on location topic was watch all fluids, high pressure lines, job task
		5.00 rotate and slide from 6135 to 6167 survey at 6134 Inc at 83.3 Az at 321.9
		1.50 bring up mud weight to 10.2# circulate well bore
		0.50 safety meeting with contractors topic was keeping hole full, hand placement, laying down DP, communication, job task
		2.00 lay down 22 jts with power swivel to get above window at 5512
		1.50 rig down power swivel and circulate well around with 9 bbls unload hotshot truck of drilling material with forklift
		1.00 TOH with bit and keep hole full
		0.50 safety meeting with contractors on location topic was tripping DP, keeping hole full, hand placement, teamwork
		1.50 continue to TOH with tools
		1.50 break down monels and break down Mesa West Directional tools. make up new (4 3/4 bit # 1333195-CH34) with new 1.75 stage motor and monels. scribe UBHO to motor
		2.00 TIH with monels, and 60 jt of AOH DP, 18 jts of HWDP TIH half way to test motor
		1.00 circulate well around with 10.2# mud.
		1.50 finish tallying in o the top of window at 5512
		1.50 rig up power swivel and circulate well around to recondition well bore
		2.00 start picking up DP and go through window out lateral to 5883. circulate well
		0.50 continue to pick up DP rotate from 6135 to 6167 to clean up lateral. crew change at 6:00
Report Start Date 4/29/2013	Report End Date 4/30/2013	Operations Summary (Continue to rotate ahead to target depth of 7051 TMD) 600 total ft.
Dur (hrs)		Comment
		0.50 safety meeting with contractors on location topic was communication, high pressure lines, job task
		2.50 calibrate depth tracker make connection and break circulation start rotating from 6167 to 6198 survey at 6165 inc 82.5 az 322.0 with rop at 14 ft an hour with good returns.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
2.50	make connection on jt 195 rotate from 6198 to 6230. survey at 6197 inc at 82.3 az 321.9 with 12 k down rop at 12 to 10 ft an hour
3.00	make connection jt 196 rotate from 6230 to 6262 loss 9 bbls circulate well clean mud weight at 10.2# vist of 46.
0.50	safety meeting with contractors on location topic was keeping an eye on fluids, communication, job task, getting ready to rotate through DC-1A formation
2.50	make connection on jt 197 rotate from 6262 to 6293 survey at 6260 inc 82.8 az 322.4 had no pit gain or loss mud weight at 10.2
0.50	make connetion on jt 198 rotate from 6293 to 6298
0.50	crew change at 18:00 hours safety topic was watch all fluids, communication, teamwork
3.00	continue to rotate from 6298 to 6325 with mud weight of 10.2 coming out and going in with vist of 45. rop at 8 to 10 ft an hour.
3.00	make connction on jt 199 rotate from 6325 to 6356. survey at 6323 inc 82.1 az 322.4
2.50	make connection on jt 200 rotate from 6356 to 6388 had rop of 25 ft an hour from 6356 to 6374 pressure decrease torq increase pull up and shut down pups well started to flow start up pup and circulate gas pocket aroud with 10.2 mud around.survey at 6323 inc 81.7 az 321.4
2.50	make connection on jt 201 rotate fom 6388 to 6419 survey at 6386 inc 82.1 az 322.4
0.50	make connection on jt 202 start roating from 6419 to 6424 crew change

Report Start Date 4/30/2013	Report End Date 5/1/2013	Operations Summary Rotate to DC-2C and continue to rotate out to Target depth of TMD of 7047. TVD of 5912. 1400 ft of Vertical Section (593 ft to TD)
--------------------------------	-----------------------------	--

Dur (hrs)	Comment
0.50	hold safety meeting with contractors on location topic was high pressure lines, team work, job task
3.00	rotate from 6419 to 6451 with 11 k down with mud weight of 10.1 coming out and going in. pump pressure at 1750. ROP at 13 ft an hour with return of white shell formation.
2.50	circulate well clean went over to office to discuss pulling tools to put string in place
3.00	lay down 18 jt with swivel when well started to flow shut down and monitor pressure and circulate gas bubble around through choke
2.00	finish laying down DP to get back above window.circulate well around to get gas around
1.00	start out with tools
0.50	crew change at 18:00 safety meeting with contractors on location topic was keeping hole full, hand placement, tripping DP
2.50	Finish TOH to 1983 install string float New BHA Directional tool, 30 jts AOH, string float, 30 jts of AOH 18 jts of HWDP. xover and AOH
2.00	TIH to 3417 and circulate well around with 10.1# mud to re-condition well bore and circulate gas around
2.00	finish TIH to top of window at 5512. rig up swivel and circulate well around.
1.00	shut down pump to change out swab that were leaking
2.00	Staet picking up DP with swivel to 6054 circulate gas around
2.00	finish picking up DP to 6454 break circulation and calibrate depth tracker continue to circulate crew change

Report Start Date 5/1/2013	Report End Date 5/2/2013	Operations Summary Continue to rotate out to target depth of TMD of 7047', TVD of 5912', 1400' of vertical section (309' to TD).
-------------------------------	-----------------------------	---

Dur (hrs)	Comment
0.50	Crew change @ 6:00 am, Jsa safety Mtg with crew
4.00	Contiue Cir. well to get air out, MWD no reading. Kick pump out and break down pump valves. Found rocks/ pieces of vis cup in the pump. Aggitator was on in suction pit causing solids to pick up off bottom of suction pit and were sucked into pump.
1.00	Slide from 6454' to 6458' made connection.
2.00	Made connection, rotate from 6458'- 6485', survey @ 6452' Inc 81.7 Az 322.
2.00	Rotate 6485'- 6517', survey @ 6484' Inc 82 Az 321.9.
2.50	Rotate 6517'- 6548', survey @ 6515' Inc 81.9 Az 322, lost 9 bbls.
0.50	Crew Change 18:00, Jsa Safety Mtg.
1.50	Rotate 6548'- 6580', Survey @ 6547' Inc 81.7 Az 321.7.
2.00	Rotate from 6580'- 6611', Survey @ 6578', Inc 81.5 Az 321.9
2.00	Rotate 6611'- 6616', slide from 6616'- 6619', rotate 6619'- 6643', survey @ 6610' Inc 81.5 Az 321.9.
6.00	Rotate 6643'- 6675', survey @ 6642', Inc 81.7 Az 321.4. Rotate 6675'- 6706', survey 6673' Inc 81.9 Az 322.0. Rotate 6706'- 6738', survey @ 6705' Inc 81.9 Az 322.0. Lost 3 bbls last 6 hrs, pump pressure 1600 psi. Mud 10.3, 48 vis. No sign of H2S/ pressure, return of white shell formation. Rotating now from 6738'- 6770' Crew change 6:00.

Report Start Date 5/2/2013	Report End Date 5/3/2013	Operations Summary Continue to rotate/slide and reach TMD 7022' + 12' rat hole, total 7034', TVD 5909.80', Vertical Section 1387.49.
-------------------------------	-----------------------------	---

Dur (hrs)	Comment
0.50	Crew change 6:00 am, Jsa safety mtg.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)		Comment
		6.00 Rotate from 6738'- 6741', slide 6741'- 6744' rotate 6744- 6770 survey @ 6737' Inc 81.5 Az 321.1, Rotate 6770'- 6774' lost 9 bbl of mud, Cir. well drop MW 10.2#. Continue rotate 6774'- 6801' Survey @ 6768' Inc 81.9 Az 321.3, slide 6801'- 6805' rotate 6805'- 6833' survey @ 6800' Inc 81.7 Az 322.1
		5.50 Rotate 6833'- 6864' survey @ 6831' 81.5 Az 322.1, Rotate 6864'- 6896' survey @ 6863' Inc 80.9 Az 321.6
		0.50 Crew change @ 18:00, Jsa safety Mtg.
		1.00 Rotate 6896'- 6927', Pull up 30' Cir. well for 30 min. CNJ tried to fix 1 Agitator in rig pit but no luck.
		5.50 Survey @ 6894'- Inc 81.3 Az 322.2, Rotate 6927'- 6942. Slide 6942- 6945' rotate 6945'- 6959' Cir. well, Survey @ 6926' Inc 81.6 Az 321.9, Rotate 6959'- 6975'
		3.75 Rotate 6975'- 6991' Survey @ 6958 Inc 80.5 Az 321.5, Rotate 6991'- 6999' slide 6999'- 7001' rotate 7001'- 7022 Survey @ 6989' Inc 80.6 Az 321.6, Rotate 7022'- 7034' TD Survey @ 7001' Inc 80.9 Az 321.9. MDT 7022' + 12' rat hole Total Depth 7034'
		1.25 Work hole for 30 min, Cir. well, Grey color shell return, sand Crew change @ 6:00.
Report Start Date 5/3/2013	Report End Date 5/4/2013	Operations Summary TOOH with 51 jts, lay down on cat walk. TOOH AOH HWDP BHA. RIH w/ Ph6 tail jts, packer, AOH, set packer 5490'.
Dur (hrs)		Comment
		0.50 Crew change 6:00, Jsa safety Mtg
		2.50 Kick out pump, lay down 7 jts pipe dragging up hole w/ swivel rotating
		1.50 Well kick with 350 psi at surface, bled off gas bubble. build mud 10.8# Cir. well dead.
		2.50 Continue to pull, Pipe stuck, Worked pipe for 2.50 hrs, Notified Jeremy Rae/ Craig Wright. Pump 40 bbls F/W an Continue working pipe,
		5.00 Got free an rotating swivel up the hole slowly. lay down 11 jts total.
		0.50 Crew change Jsa safety Mtg.
		0.50 Continue pulling pipe, no luck pipe stuck again worked pipe/ pump 40 bbls f/w still won't get free. pump some quick stop but no luck.
		4.00 Notified Jeremy Rae finally agree on pumping F/W an roll out mud. pump 130 bbl F/W well came flowing out to fb tank. kept pumping f/w work pipe, pipe came free.
		2.75 Continue tooh w/ pipe laying down w/ swivel rotating out, pipe dragging for 20 jts after pipe free up, pull 5 more jts. 196 jts in hole @ 6264', casing flowing to fb tank oil/ gas.
		1.25 Pump 140 bbls 10.1# mud kill well.
		3.00 Continue tooh w/ dp ld total 51 jts on cat walk. Cir. well w/ 11.0# mud crew change @ 6:00 am
Report Start Date 5/4/2013	Report End Date 5/5/2013	Operations Summary Contiue TOOH w/AOH, LD BHA. RIH w/ 5.5 packer, set 5490' w/ 362' tail pipe, Ph6.
Dur (hrs)		Comment
		0.50 Crew change @ 6:00 am. Jsa safety Mtg
		6.50 Hang back swivel, Tooh w/ aoh dp lay down hwdp, lay down motors, monel's
		4.50 PU 1- Mule shoe, 12- ph6 362' 5 1/2" packer/ on off tool. rih w/ aoh re tally 151 jts, Pu 22 more off rack, 22' subs, Set packer 5490' j-off packer.
		2.00 Roll mud out to rig pit w/ fw.
		0.50 Pressure test casing/ packer 1000 psi 30- min. (good).
		1.50 Latch on packer/ RU WL retrieve blank plug. Tbg pressure 500 psi
		8.50 open to fb tank 500 psi drop to 0 psi. FB 35 bbl by 4am, Went to H122/ G122 open back to injection. Flow back rate started to pick up. Crew change 6:00 am.
Report Start Date 5/5/2013	Report End Date 5/6/2013	Operations Summary Flow back well to LD tanks, pump 80 bbls of FW injection rate well taking fluid. FB well, acidize well w/20% acid.
Dur (hrs)		Comment
		0.50 Crew change @ 6:00 am, Jsa safety Mtg,
		11.50 Flow back well Mud/ Gas to FB Tank. Lansing haul fluid to A1. Flow back 480 bbl, pump 80 bbls f/w to get rate. pump 45 bbl well 0 psi, pump another 10 bbl pressure came up to 600 psi pump another 20 bbl pressure stay same 600 psi, total 80 bbl pump. Open back to fb tank,
		0.50 Crew change 18:00, Jsa safety Mtg
		1.50 Wait on baker w/ acid 1.5 hr
		4.00 Baker arrived with acid, Well still dead spot/ ru baker safety mtg. pump 5 bbl ahead pump 5000 gal 20% acid 2.5 bpm flush 60 bbl F/W. pump 42 bbl acid 1455 psi, 119 bbl 1210 psi, Flush F/W 60 bbl, ISIP 705 psi, 5-min 614 psi, 10-min 545 psi, 15-500 psi, SWI 500 psi. RD Baker Acid trucks
		2.00 2 hr SI,
		4.00 200 psi on Tbg, Flow well back 450 psi, Flare gas. flow back 210 bbl Crew change 6:00 am.
Report Start Date 5/6/2013	Report End Date 5/7/2013	Operations Summary Finish picking up new 2 7/8" KC TK FL injection tubing. Latch on to 5 1/2" packer, set at 5490'. Land out and schedule MIT. Rig down all equipment.
Dur (hrs)		Comment
		0.50 safety meeting with contractors on location topic was communication, high pressure lines, job task
		2.50 flow well back through choke and monitor pressure recovered a total of 100 bbls oil cut was about 50/50



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
3.00	spot in and rig up Tefteller test lubricator to 1000 psi (good test) run on in and set 1.81 plug at 5470 pull up and blees off pressure through choke waited on trucks to haul out packer fluid
0.50	pressure test 1.81 plug to make sure it is seat properly for 30 mins
2.50	j-off packer and re-condition well bore with 130 bbls of packer and pressure test packer to 1000 psi (Good Test) release pressure
3.00	start laying down AOH work string and transfer to empty trailer
0.50	crew change safety meeting with contractors on location topic was hand placement, teamwork, suspended loads,
3.00	continue to lay down AOH work string and transfer to empty trailer
1.50	transfer production tubing on to pipe racks and prep. make up on and off tool to nickel coated seat nipple.started setting toque on system by slowly increase the hydraulic pressure it would reach minimum torque when it would fall off by 200 psi. tried with out no success
1.50	went through hydrilic system and add more fluid
4.50	start picking up production tubing pick up 95 jts transfer tubing from trailer to pipe racks and prep.
1.00	satert picking up tubing crew change at 6:00

Report Start Date 5/7/2013	Report End Date 5/8/2013	Operations Summary This well is landed with tubing hanger, stainless steal nipple, 1 jt of new 2 7/8" KC Fiber-lined tubing, 3 pup jts 10,8,4, 167 jts, 5 1/2" nickel-coated Arrowset 1-X packer set at 5490', 1 78 R nipple 2 3/8" x 2 7/8" crossover, 2 7/8" nickel-coated downhole swivel, 13 jts of 2 7/8" PH-6 drill pipe. This well also passed NNEPA MIT, witnessed by Jean Bia.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
0.50	Safety meeting with contractors on location topic was slip trip and falls. job task, communication
2.50	finish picking up tubing. land well with 167 jt pony subs 4,6,10,and landing jt with SS nipple and dunot set down with 20 K on compression
0.50	pressure test packer to 1000 psi (good test) for 30 mins
2.50	rig down rig floor and nipple down BOP stack put away. nipple up upper tree
1.50	rig up tefteller and pressure test lubricator to 1000 psi run on in and spear disk come out and pick up tool to recover 1.81 plug come out and rig down and move off
1.00	start rigging down equipment
1.00	had Wilson srvice on location to perform MIT with NNEPA Jean Bia rig down truck and move off
2.50	rig down service unit
1.00	finish rigging down alll equipment
11.00	have one hand watch all equipment

Report Start Date 5/8/2013	Report End Date 5/9/2013	Operations Summary Have location cleaned up and turn back over to Production.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
4.00	take pressure readings and open well to frac tanks for 4 hours shut in well.
7.00	Key hands out to work on unit and rig pump, Riley out to clean close loop system had Dawn hand watch equipment.
13.00	had one Dawn hand watch all equipment



Resolute Natural Resources

Aneth Unit (Nad 27)

Aneth Unit H222

H222 Sidetrack

Sidetrack

UWI:

WL:

Survey: Final

Standard Survey Report

06 May, 2013





Site: Aneth Unit H222
Well: H222 Sidetrack
Wellbore: Sidetrack
Plan: Final

Reference Details - WELL CENTRE

Geodetic System: US State Plane 1927 (Exact solution)
Ellipsoid: Clarke 1866
Zone: Utah Central 4302
Northing: -369691.10
Easting: 2651861.48
Latitude: 37° 17' 46.428 N
Longitude: 109° 15' 39.172 W
Grid Convergence: 1.43° West
Ground Elevation: 4933.0
KB Elevation: KB @ 4945.0usft




PLAN DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
5520.0	0.00	0.00	5520.0	0.0	0.0	0.00	0.00	0.0	
5847.3	82.65	322.00	5745.0	155.9	-121.8	25.25	322.00	197.9	
6667.7	82.65	322.00	5850.0	797.1	-622.8	0.00	0.00	1011.5	
7121.1	82.65	322.00	5908.0	1151.4	-899.6	0.00	0.00	1461.2	
7376.9	77.53	322.00	5952.0	1349.9	-1054.7	2.00	180.00	1713.1	D4_TD (H222)

ANNOTATIONS

TVD	MD	Annotation
5512.7	5512.7	Top of Window at 5512.7' MD
5518.0	5518.0	Bottom of Window at 5518' MD
5904.6	7001.0	Last MWD Svy;7001' MD
5909.8	7034.0	Extrap to Bit;7034' MD



Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Project	Aneth Unit (Nad 27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		Using geodetic scale factor

Site	Aneth Unit H222		
Site Position:		Northing:	-369,691.10 usft
From:	Lat/Long	Easting:	2,651,861.48 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	37° 17' 46.428 N
		Longitude:	109° 15' 39.172 W
		Grid Convergence:	1.43 °

Well	H222 Sidetrack		
Well Position	+N/-S	0.0 usft	Northing:
	+E/-W	0.0 usft	Easting:
Position Uncertainty	0.0 usft	Wellhead Elevation:	usft
		Latitude:	37° 17' 46.428 N
		Longitude:	109° 15' 39.172 W
		Ground Level:	4,933.0 usft

Wellbore	Sidetrack		
Magnetics	Model Name	Sample Date	Declination
			(°)
	IGRF2010	2/8/2013	10.39
			Dip Angle
			(°)
			63.61
			Field Strength
			(nT)
			50,694

Design	Final		
Audit Notes:			
Version:	1.0	Phase:	ACTUAL
		Tie On Depth:	0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.0	0.0	0.0
			Direction
			(°)
			322.00

Survey Program	Date	5/6/2013		
From	To	Survey (Wellbore)	Tool Name	Description
(usft)	(usft)			
5,512.7	7,034.0	Final (Sidetrack)	MWD	MWD - Standard

Survey										
Measured	Inclination	Azimuth	Vertical	Subsea	+N/-S	+E/-W	Vertical	Dogleg	Build	Turn
Depth	(°)	(°)	Depth	(usft)	(usft)	(usft)	Section	Rate	Rate	Rate
(usft)			(usft)				(usft)	(°/100usft)	(°/100usft)	(°/100usft)
0.0	0.00	0.00	0.0	-4,945.0	0.0	0.0	0.0	0.00	0.00	0.00
Top of Window at 5512.7' MD										
5,512.7	0.00	0.00	5,512.7	567.7	0.0	0.0	0.0	0.00	0.00	0.00
Bottom of Window at 5518' MD										
5,518.0	3.10	322.00	5,518.0	573.0	0.1	-0.1	0.1	58.49	58.49	0.00
5,535.0	6.60	325.25	5,534.9	589.9	1.3	-0.9	1.6	20.64	20.59	19.12
5,566.0	16.10	326.40	5,565.3	620.3	6.3	-4.3	7.7	30.65	30.65	3.71
Ismay										
5,590.1	22.57	325.33	5,588.0	643.0	12.9	-8.8	15.6	26.91	26.87	-4.43
5,598.0	24.70	325.10	5,595.3	650.3	15.5	-10.6	18.8	26.91	26.88	-2.95

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,630.0	34.10	323.30	5,623.1	678.1	28.2	-19.8	34.5	29.50	29.38	-5.63
5,660.0	43.20	323.10	5,646.5	701.5	43.2	-31.0	53.2	30.34	30.33	-0.67
LISA										
5,674.8	46.53	322.76	5,657.0	712.0	51.6	-37.3	63.6	22.56	22.50	-2.33
5,692.0	50.40	322.40	5,668.4	723.4	61.8	-45.2	76.5	22.56	22.50	-2.07
5,723.0	56.40	321.90	5,686.9	741.9	81.4	-60.4	101.4	19.40	19.35	-1.61
LISB										
5,750.1	60.72	322.33	5,701.0	756.0	99.6	-74.6	124.5	15.99	15.94	1.57
5,755.0	61.50	322.40	5,703.4	758.4	103.1	-77.2	128.8	15.99	15.94	1.49
LISC										
5,782.8	64.45	322.75	5,716.0	771.0	122.7	-92.3	153.5	10.68	10.62	1.25
5,787.0	64.90	322.80	5,717.8	772.8	125.7	-94.6	157.3	10.68	10.63	1.22
5,818.0	68.20	322.30	5,730.1	785.1	148.3	-111.9	185.8	10.75	10.65	-1.61
5,850.0	73.70	321.70	5,740.6	795.6	172.1	-130.5	216.0	17.28	17.19	-1.88
DC 1A										
5,863.0	75.71	321.62	5,744.0	799.0	182.0	-138.3	228.5	15.50	15.48	-0.65
5,881.0	78.50	321.50	5,748.0	803.0	195.7	-149.2	246.1	15.50	15.48	-0.64
5,913.0	83.90	323.10	5,752.9	807.9	220.7	-168.5	277.7	17.58	16.88	5.00
5,944.0	84.40	323.50	5,756.1	811.1	245.5	-186.9	308.5	2.06	1.61	1.29
5,976.0	82.60	321.40	5,759.7	814.7	270.7	-206.3	340.3	8.61	-5.63	-6.56
6,008.0	82.80	321.00	5,763.8	818.8	295.4	-226.2	372.0	1.39	0.63	-1.25
DC 1B										
6,034.1	82.97	321.42	5,767.0	822.0	315.6	-242.4	398.0	1.73	0.65	1.61
6,039.0	83.00	321.50	5,767.6	822.6	319.4	-245.5	402.8	1.73	0.65	1.61
6,071.0	83.10	321.50	5,771.5	826.5	344.2	-265.2	434.6	0.31	0.31	0.00
6,102.0	83.30	321.60	5,775.1	830.1	368.4	-284.4	465.3	0.72	0.65	0.32
6,134.0	83.00	321.90	5,779.0	834.0	393.3	-304.0	497.1	1.32	-0.94	0.94
DC 1C										
6,134.4	83.00	321.90	5,779.0	834.0	393.6	-304.3	497.5	0.00	0.00	0.00
6,165.0	82.50	322.00	5,782.9	837.9	417.5	-323.0	527.9	1.66	-1.63	0.33
6,197.0	82.30	321.90	5,787.1	842.1	442.5	-342.5	559.6	0.70	-0.63	-0.31
6,229.0	82.50	322.30	5,791.3	846.3	467.5	-362.0	591.3	1.39	0.63	1.25
6,260.0	82.80	322.40	5,795.3	850.3	491.9	-380.8	622.1	1.02	0.97	0.32
DC 2A										
6,288.3	82.18	322.40	5,799.0	854.0	514.1	-397.9	650.1	2.19	-2.19	0.00
6,292.0	82.10	322.40	5,799.5	854.5	517.0	-400.2	653.8	2.19	-2.19	0.00
6,323.0	81.30	321.40	5,804.0	859.0	541.1	-419.1	684.4	4.10	-2.58	-3.23
6,355.0	81.70	321.40	5,808.7	863.7	565.9	-438.8	716.1	1.25	1.25	0.00
6,386.0	81.50	321.50	5,813.2	868.2	589.9	-458.0	746.8	0.72	-0.65	0.32
6,418.0	81.40	321.40	5,818.0	873.0	614.6	-477.7	778.4	0.44	-0.31	-0.31
6,452.0	81.70	322.00	5,823.0	878.0	641.0	-498.5	812.0	1.96	0.88	1.76
6,484.0	82.00	321.90	5,827.5	882.5	665.9	-518.0	843.7	0.99	0.94	-0.31
DC 2B										
6,487.4	81.99	321.91	5,828.0	883.0	668.6	-520.1	847.1	0.45	-0.32	0.32
6,515.0	81.90	322.00	5,831.9	886.9	690.1	-537.0	874.4	0.45	-0.32	0.32

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
6,547.0	81.70	321.70	5,836.4	891.4	715.0	-556.5	906.1	1.12	-0.63	-0.94
6,578.0	81.50	321.90	5,841.0	896.0	739.1	-575.5	936.7	0.91	-0.65	0.65
6,610.0	81.70	321.30	5,845.6	900.6	763.9	-595.2	968.4	1.96	0.63	-1.88
DC 2C										
6,640.2	81.70	321.39	5,850.0	905.0	787.3	-613.8	998.3	0.31	0.00	0.31
6,642.0	81.70	321.40	5,850.3	905.3	788.7	-614.9	1,000.1	0.31	0.00	0.31
6,673.0	81.90	322.00	5,854.7	909.7	812.7	-633.9	1,030.7	2.02	0.65	1.94
6,705.0	81.50	321.10	5,859.3	914.3	837.5	-653.6	1,062.4	3.05	-1.25	-2.81
6,737.0	81.50	321.10	5,864.0	919.0	862.2	-673.5	1,094.1	0.00	0.00	0.00
6,768.0	81.90	321.30	5,868.5	923.5	886.1	-692.7	1,124.7	1.44	1.29	0.65
6,800.0	81.70	322.10	5,873.1	928.1	910.9	-712.4	1,156.4	2.55	-0.63	2.50
6,831.0	80.50	322.00	5,877.9	932.9	935.1	-731.2	1,187.0	3.88	-3.87	-0.32
6,863.0	80.90	321.60	5,883.0	938.0	959.9	-750.7	1,218.6	1.76	1.25	-1.25
6,894.0	81.30	322.20	5,887.8	942.8	984.0	-769.6	1,249.2	2.31	1.29	1.94
6,926.0	81.60	321.90	5,892.6	947.6	1,009.0	-789.1	1,280.9	1.32	0.94	-0.94
6,958.0	80.50	321.50	5,897.6	952.6	1,033.8	-808.7	1,312.5	3.65	-3.44	-1.25
6,989.0	80.60	321.60	5,902.7	957.7	1,057.7	-827.7	1,343.1	0.45	0.32	0.32
Last MWD Svy;7001' MD										
7,001.0	80.90	321.90	5,904.6	959.6	1,067.0	-835.0	1,354.9	3.51	2.50	2.50
DC III										
7,022.6	80.90	321.90	5,908.0	963.0	1,083.8	-848.2	1,376.2	0.00	0.00	0.00
Extrap to Bit;7034' MD										
7,034.0	80.90	321.90	5,909.8	964.8	1,092.7	-855.1	1,387.5	0.00	0.00	0.00

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting		
- Shape	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)	Latitude	Longitude
D4_TD (H222)	0.00	0.00	5,952.0	1,349.9	-1,054.7	-368,340.03	2,650,805.87	37° 18' 0.031 N	109° 15' 51.803 W
- survey misses target center by 328.3usft at 7034.0usft MD (5909.8 TVD, 1092.7 N, -855.1 E)									
- Point									



Mesa West Directional

Survey Report



Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
5,590.1	5,588.0	Ismay		0.00		
5,674.8	5,657.0	LISA		0.00		
5,750.1	5,701.0	LISB		0.00		
5,782.8	5,716.0	LISC		0.00		
5,863.0	5,744.0	DC 1A		0.00		
6,034.1	5,767.0	DC 1B		0.00		
6,134.4	5,779.0	DC 1C		0.00		
6,288.3	5,799.0	DC 2A		0.00		
6,487.4	5,828.0	DC 2B		0.00		
6,640.2	5,850.0	DC 2C		0.00		
7,022.6	5,908.0	DC III		0.00		

Survey Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
5,512.7	5,512.7	0.0	0.0	Top of Window at 5512.7' MD	
5,518.0	5,518.0	0.1	-0.1	Bottom of Window at 5518' MD	
7,001.0	5,904.6	1,067.0	-835.0	Last MWD Svy;7001' MD	
7,034.0	5,909.8	1,092.7	-855.1	Extrap to Bit;7034' MD	

Checked By: _____	Approved By: _____	Date: _____
-------------------	--------------------	-------------

END OF WELL REPORT



Client: Resolute Natural Resources
Well Name: Aneth Unit H222
Location: Sec.22, T40S, R24E
Job Number: 1305
Start Date: 12-Apr-13 **End Date:** 5-May-13

PERSONAL

Operator Personnel
Company Man:
 Myron Dee, James Yellowman
Geologist:

Directional Personnel
 David Westbrook
 Shane Sligar

Survey Personnel
 Ron Alexis
 Greg Vlaming

WELL SUMMARY

BHA 1 - Drilled F/ 5556' - 5590' , 34 ft in 7.75 hrs - 4.4 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with no jets . Motor is a CAVO 3.75", 5/6 lobe, 3.0 stage, 1.4 rev/gal, set at 2.57°.

While sliding motor lost all reactive torque and drilling differential pressure. Tripped BHA 1 out to inspect motor. Motor drained on surface but was making grinding noises and would lock up and let free while draining on surface.

BHA 2 - Drilled F/ 5590' - 5644' , 54 ft in 5.5 hrs - 9.82 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a CAVO 3.75", 5/6 lobe, 3.0 stage, 1.4 rev/gal, set at 2.83°.

Tripped out due to coming off of whipstock @ 48° azimuth instead of 322°. On surface high side of motor was scribed to top of UBHO to insure mule shoe didn't move from original point. Motor drained and sounded good on surface and had no visual signs of wear. Motor delivered 41°/100'.

Ran in wireline to check inc and azimuth of existing well in 200' increments to top of window. From window to end of mill depth azimuth went from 322 at top to 338 azimuth at bottom of milled depth. At the point which gyro was used to slide azimuth trended from 338 - 48 azimuth from 5556' to 5583' the point which gyro was released.

BHA 3 - Drilled F/ 5522' - 5672' , 150 ft in 11.25 hrs - 12.8 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a CAVO 3.75", 5/6 lobe, 3.0 stage, 1.4 rev/gal, set at 2.29°.

Motor delivered 26°/100' during the build section. Motor drained well and no visible signs of wear at surface. TOOH due to gas kick.

BHA 4 - Drilled F/ 5672' - 5672'

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 2.00°.

At shallow test pressure spiked out at 2500#. Recycled pumps and brought throttle to operating range pressure was 2500# and circulating full returns. MWD was sending bad pulses. TOOH to inspect BHA.

BHA 5 - Drilled F/ 5672' - 5672'

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 2.00°.

Tested motor halfway in hole and had bad pulses due to air in mud. Conditioned mud with defoamer and tool tested fine. Continued to trip in hole to top of window and proceeded to break circulation. Pressure went to normal operating pressure but began to rise. Once pump was kicked out pressure stayed at 1600# multiple times and was bled off through pump.

BHA 6 - Drilled F/ 5672' - 6167' , 495ft in 68.25 hrs - 7.25 ft/hr

Bit - 4 3/4" Varel insert CH24MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 1.75°.

Motor averaged 18°/100' throughout the bottom half of the build section except for the Gothic Shale where it delivered 15°/100'.

POOH due to slow ROP and bit hours - motor had numerous stalls while rotating. All three cones were locked up on this bit.

BHA 7 - Drilled F/ 6167' - 7034' , 867ft in 57.75 hrs - 15 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 1.75°.

REPORT PREPARED BY:

David Westbrook

RECEIVED: Jun. 10, 2013

END OF WELL REPORT 2



Client: Resolute Natural Resources
Well Name: Aneth Unit H222
Location: Sec.22, T40S, R24E
Job Number: 1305
Start Date: 12-Apr-13 **End Date:** 5-May-13

PERSONAL

Operator Personnel
Company Man:
 Myron Dee, James Yellowman
Geologist:

Directional Personnel
 David Westbrook
 Shane Sligar

Survey Personnel
 Ron Alexis
 Greg Vlaming

WELL SUMMARY

KOP: 5525	TD: 7034	FEET DRLG.: 1600	TOTAL DRLG. HRS.: 146	AVG. ROP:
# DAYS: 22	# BITS: 3	# BHA'S: 7	NO. OF MOTORS: 6	11.0

Well Parameters

RE-ENTRY	TOTAL DEPTH	
	Leg 1	LEG 2
HOLE SIZE: 4 3/4 WHIPSTOCK SETTING: 322.18° Coordinates: MD: TVD: INC: DIRECTION: VERTICAL SECTION: N / S: E / W:	HOLE SIZE: 4 3/4 Coordinates: MD: 5644 TVD: 5640.64 INC: 28.65 DIRECTION: 32 VERTICAL SECTION: 5.47 N / S: 16.62 E / W: 12.39	HOLE SIZE: 4 3/4 Coordinates: MD: 7034 TVD: 5909.8 INC: 80.9 DIRECTION: 321.9 VERTICAL SECTION: 1387.49 N / S: 1092.65 E / W: -855.13

RE-ENTRY DATA:

TOP OF WINDOW: 5512.67 DIRECTION: 322.18
 BOTTOM OF WINDOW: 5518.49 RAT HOLE: 7

DIRECTIONAL COMMENTS

1. Slide with gyro until the azimuths match with the MWD tool.
2. Install an auto-driller to maximize weight-on-bit and penetration rate.
3. Install a stroke counter to maximize motor performance, hole cleaning and penetration rate.
4. A PDC bit might drill faster - especially in the Desert Creek formations.

REPORT PREPARED BY:

David Westbrook

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MININGAMENDED REPORT ☐ FORM 8
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:

9. API NUMBER:

10 FIELD AND POOL, OR WILDCAT

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,
MERIDIAN:

12. COUNTY

13. STATE

UTAH

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☐ DRY ☐ OTHER _____b. TYPE OF WORK: NEW WELL ☐ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER _____

2. NAME OF OPERATOR:

3. ADDRESS OF OPERATOR:

CITY

STATE

ZIP

PHONE NUMBER:

4. LOCATION OF WELL (FOOTAGES)

AT SURFACE:

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH:

14. DATE SPUDDED:

15. DATE T.D. REACHED:

16. DATE COMPLETED:

ABANDONED ☐READY TO PRODUCE ☐

17. ELEVATIONS (DF, RKB, RT, GL):

18. TOTAL DEPTH: MD

TVD

19. PLUG BACK T.D.: MD

TVD

20. IF MULTIPLE COMPLETIONS, HOW MANY? *

21. DEPTH BRIDGE MD

PLUG SET:

TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

23.

WAS WELL CORED?

NO ☐YES ☐

(Submit analysis)

WAS DST RUN?

NO ☐YES ☐

(Submit report)

DIRECTIONAL SURVEY?

NO ☐YES ☐

(Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)
(A)				
(B)				
(C)				
(D)				

27. PERFORATION RECORD

INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS☐ GEOLOGIC REPORT☐ DST REPORT☐ DIRECTIONAL SURVEY☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION☐ CORE ANALYSIS☐ OTHER: _____

30. WELL STATUS:

FINAL/survey/procedure details

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) _____ TITLE _____

SIGNATURE _____ DATE _____

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

Sidetrack
Aneth Unit H-222
2096' FNL & 776' FEL
Sec 22, T40S, R24E
San Juan County, Utah
API 43-037-30242

Formation Tops (KB 4,945)

Navajo	928'
Chinle	1,694'
DeChelley	2,832'
Organ Rock	2,930' (Est)
Hermosa	4,696'
Ismay	5,588'

Sidetrack Procedure (Proposed)

1. MIRU (04-09-2013)
2. Mock MIT.
3. Pull injection equipment.
4. Set CIBP (5590').
5. Run CBL & Csg Inspection Logs (5590' to Surface).
6. Set whipstock on CIBP (5554').
7. Mill window (5545'-5551').
Note: *Lost window – mechanical failure.*
8. Set whipstock on CIBP (5522').
9. Mill window (5513'-5518).
10. Drill 4-3/4" OH lateral from 5518' to 7034' (MD), (TVD = 5910'),
BHL: 1001' FNL & 1631' FEL of Sec. 22, T40S, R24E.
Note: Sfc Location: 2096' FNL & 776' FEL of Sec. 22, T40S, R24E

11. Acidize OH lateral w/ 5,000 gals of 20% HCL.

12. Run injection equipment.

13. Circulate packer fluid.

14. RDMOL (05-07-2013)

15. MIT (05-08-2013)

16. RWTI (05-11-2013)

AU H-222 (Sidetrack/Short Lateral)

GREATER ANETH FIELD

2096' FNL & 776' FEL


SEC 22-T40S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30242

Injector**Formation Tops**

Navajo	928'
Chinle	1694'
DeChelly	2832'
Organ Rock	2930' (Est)
Hermosa	4696' (Est)
Ismay	5588'

Current



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Job Category Drilling	Primary Job Type Drilling - re-entry	Secondary Job Type
Start Date 4/8/2013	End Date	AFE Number 10013701
Objective Job scope includes: sidetrack wellbore, drill OH lateral, acid stimulation, install injection equipment, MIT & RWTL.		
Contractor Key	Rig Number #27	Rig Type
Report Start Date 2/22/2013	Report End Date 2/22/2013	Operations Summary Survey Loc.
Report Start Date 4/8/2013	Report End Date 4/8/2013	Operations Summary Report on H-222 Capital Injector Had Lansing extent location for 24 hour rig also had Key energy test all anchors
Report Start Date 4/9/2013	Report End Date 4/10/2013	Operations Summary Move service unit to location.. This location is clean and open,the anchors were tested 4/13 and marked.The cathodic system is hook-up and on.There is also a CO2 sub station on the north west side of location and injecting. The well head is a 3000# well head with 2 7/8 tree,Tubing pressure was at 2400 psi and 0 psi on backside. Spot in lay down tanks, rig ramp and with the assist of Dawn trucking winch unit onto ramp.Finish spotting in close loop system, gas buster., pipe trailers, BOP skid, also living quarters Rig up.service unit. Crew change at 18:00 hours tail gate safety meeting with everyone on location topic was job task, using the right tool for the job, wind directions., Rig up hard lines to rig pump and lines to frac tanks. pressure test casing to 1000 psi for 30 mins.(Good Test). Open well through choke to bleed off pressure to frac tanks.well making good amount of CO2 with readings of H2S at 70 PPM. Pump 10# to establish kill weight fluid.monitor pressure for 1 hour. Rig-up Tefteller and make up 1.901 gauge ring, pressure test lubricator to 1000 psi. Run on down and tag at 5469 wire line depth. Come out and pick up 1.81 plug run on in and set. Pressure test to 1000 psi (Good Test). Release pressure come and rig down wireline and move off. Nipple down well head. Pick up sub with TIW valve and strip BOP stack over and nipple up.Rig up rig floor and tongs, hand rails, ladders. Crew change at 6:00 am safety meeting with contractors on location topic was hand placement, laying down tubing, tong operations, suspended loads. Had Weatherford on location to release off packer.

Dur (hrs)		Comment
		2.50 secure all loads for rig move 1.00 move unit to location 6.00 move all equipennt with the help of Dawn trucking winch unit on to ramp finish spotting in equipment 2.50 rig up service unit 0.50 crew change at 18:00 hours safety meeting with everyone on location topic was job task, using the ight tool for the job, wind diruptions 2.00 rig up hard lines from pump to well also lines to manifold to frac tank.put on safety cables 0.50 pressure test casing to 1000 psi for 30 mis (good test) 2.00 open well through choke manifold and bleed off pressure 1.50 pump kill weight fluid and shut in well for 1 hour monitor pressure 2.00 rig up Tefteller and rig up pick up 1.901 gauge ring pressure test lubricator to 1000 psi. run on in to 5469 wireline depth. come out and pick up 1.81 plug and set come out and rig down wireline and release 2.00 nipple down well head and pick up sub with TIW valve strip over BOP stack and nipple up 1.50 rig up rig floor tongs hand rails and safety equipment 0.50 crew change at 6:00 am safety meeting with contractors on location topic was hand placement, laying down tubing, tong operations, suspended loads 0.50 start to release off packer
Report Start Date 4/10/2013	Report End Date 4/11/2013	Operations Summary Waited on Weatherford mechanic and electrician to work on accumulator.While waiting on starter to be replace on unit,set up catwalk with pipe racks. .The tubing pressure up to 600 psi, bleed off pressure and monitor. Pressure test BOP to 1000 high and 300 low. Release off packer and lay down landing jt 2 pup jt 8,6 ft. plus 167 jt Tally and transfer to empty trailer. Change equipment over and move DP from trailer to pipe racks. Crew change at 18:00 hours tail gate safety meeting with contractors on location topic was job task, hand placement, communication, picking up DP. Tally work string and make up BHA with on and off tool with 4 ft perf sub X-over back to AOH. Start picking up work string.and tag at 5448. Lay down jt 175 and install TIW valve with kelley hose. Circulate well around with 16# mud. Pull up and release packer. Start out of hole but shut down due to swabbing fluids back. Worked tubing up and down to try and relax rubbers on packer. Call out Tefteller to recover 1.81 plug. Crew change at 6:00 am safety meeting with with everyone on location topic was keeping on eye on fluids, job task, team work. Contline to wait on slickline
Dur (hrs)		Comment
		3.00 wain on Weatherford service hand 2.00 set pipe rack and cat walk. bleed off pressure on tubing and monitor tubing 1.00 pressure test BOP stack 1000 high and 300 low 0.50 release off packer and monitors pressure 4.50 lay down production tubing and tally and transfer to trailer 1.00 change over equipment . transfer AOH work string to pipe racks



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
0.50	crew change at 18:00 hours safety meeting with contractors on location topic was hand placement, job task, communication, picking up DP
1.00	tally working and make up BHA with on and off tool with 4 ft perf sub,x-over back to AOH
5.00	pick up workstring tally and transfer to pipe racks.
2.50	hook up hoses on top of TIW valve and circulate well around with 16# mud
1.50	release packer and start out. shut down because we were swabbing back fluids work tubing up and down
1.00	call out slickline hand to recovery 1.81 plug
0.50	crew change at 6:00 am safety meeting with contractors on location topic was

Report Start Date 4/11/2013	Report End Date 4/12/2013	Operations Summary Jsa Safety Mtg. Crew waited for WL for 1.5 hr, WL arrived spotted/ RU WL to Tbg Rih down to 5442' shear blank plug/ Retrieve blank plug, RD WL MOL. Continue tooh w/ aoh & packer pumping 3 bbls every row when tooh, LD packer/ on off tool. PU B/S Rih w/174 aoh out of derrick, pu 7 jts off pipe rack down to 5724' total 181 jts, LD 7 jts back down pump 5 bbls 16# mud. SI Dash hot shot unloaded 2 mornells, 3 mud motors. LD 6 more aoh dp tooh with 102 jts SB in derrick. Crew change 18:00. Unloaded 15 2 7/8" aoh dp, 6- 2 7/8" H-90 spiral dp off hot shot trailer. Continue tooh w aoh dp total standing back 168 jts ld bit/ scraper. Spotted/ RU Blue Jet WL rih w/ CIBP notified Craig Wright suggest to set CIBP @ 5590', Set CIBP @ 5590' rooh w/ WL RD. Rih w/ aoh open end down 176 jts 5587' tag up CIBP pull lad down #176 ru tiw valve kelly hose up, made back up #176 set eot 10' above CIBP 5577'. Pump Cir. 16# mud out of hole to rig pit, Lansing haul mud back to mud plant. Lot of Co2 on return had to choke back pump slowly pump 180 bbl to make sure mud clear up, Pressure tested CIBP 580 psi good, RD lines off tbg lay down 5 jts tooh 172 jts in derrick. RU WL rih to 5590' logging to surface. Crew change 6:00.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
0.50	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg.
1.50	Crew waited for WL for 1.5 hr,
1.50	WL arrived spotted/ RU WL to Tbg Rih down to 5442' shear blank plug/ Retrieve blank plug, RD WL MOL
3.00	Continue tooh w/ aoh & packer pumping 3 bbls every row when tooh, LD packer/ on off tool.
2.50	PU B/S Rih w/174 aoh out of derrick, pu 7 jts off pipe rack down to 5724' total 181 jts, LD 7 jts back down pump 5 bbls 16# mud.
1.00	SI Dash hot shot unloaded 2 mornells, 3 mud motors.
1.50	LD 6 more aoh dp tooh with 102 jts SB in derrick.
0.50	Crew change 18:00.
0.50	Unloaded 15 2 7/8" aoh dp, 6- 2 7/8" H-90 spiral dp off hot shot trailer.
1.00	Continue tooh w aoh dp total standing back 168 jts ld bit/ scraper.
1.50	Spotted/ RU Blue Jet WL rih w/ CIBP notified Craig Wright suggest to set CIBP @ 5590', Set CIBP @ 5590' rooh w/ WL RD
2.50	Rih w/ aoh open end down 176 jts 5587' tag up CIBP pull lad down #176 ru tiw valve kelly hose up, made back up #176 set eot 10' above CIBP 5577'.
3.50	Pump Cir. 16# mud out of hole to rig pit, Lansing haul mud back to mud plant. Lot of Co2 on return had to choke back pump slowly pump 180 bbl to make sure mud clear up, Pressure tested CIBP 580 psi good,
2.00	RD lines off tbg lay down 5 jts tooh 172 jts in derrick.
1.00	RU WL rih to 5590' logging to surface. Crew change 6:00.

Report Start Date 4/12/2013	Report End Date 4/13/2013	Operations Summary Jsa Safety Mtg. WL rih w/ CIL down 5590' WL depth Log up to surface, RD CIL, RU CBL rih 5590' log up to surface got to together w/ Craig Wright, Mesa West, Select w WS Agree on setting 2nd CIBP @ 5545' 13' below Csg collar, Set CIBP 5545' rooh w/ WL RD MOL. Crew change out rotating head, Re adjusted rig floor. SI Select oil tools with Whipstock/ mills, Pu Achor 2.83' WS 6.24' WM 1.45' F/M 4.75' XO 1.15' 1-dp 32.22' UBHO 1.99' XO 1.66' 10- hwdp 305.72' XO 1.26, Total BHA 358.27' Lansing dig out/ line earth pit while crew ate lunch. After tih w/ Aoh out of derrick 152 jts out of derrick w/ min/ half a stand, Crew change 18:00 Jsa safety Mtg. Crew finished tih 12 jts total 164 out of derrick an Total 174 jts w/ 10- hwdp WS @ 5537.40. PU # 165 w/ WL & Gyro tool. Rih with WL/ Gyro tool down to OBHO, Then went down w #165 tag 14.40' in @ 5551.80' an oriented few times got it to 322.41 called it good, Sat down 9k shear anchor re check 320.5, pull up/ down gyro final 321.98 called it good an pull gyro up to 5000', pull up on WS 1' string not pulling over, went back down tag @ same depth 5551.80 pull up again no luck, not pulling over string weight. anchor not set or bad casing. Rooh w WL/ gyro tool RD WL. Notified Craig W. Wilson D. about WS not setting. Select order fishing tools/ another Whipstock. Crew tooh w 10 jts hwdp + 164 aoh dp standing back in derrick lay down mills. SI Double S hot shot w/ fishing tools, Pu fish tools w/ hook. Rih w aoh 164 + 10 hwdp, jar, hook pu 165 an tag WS, Work the hook up/ down to get in slot an rotated ed tbg work it for 45 min no sign of toque tooh w 128 jts no sign of drag or weight change. Crew change at 6:00.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
5.50	Jsa Safety Mtg. WL rih w/ CIL down 5590' WL depth Log up to surface, RD CIT, RU CBL rih 5590' log up to surface got to together w/ Craig Wright, Mesa West, Select w WS Agree on setting 2nd CIBP @ 5545' 13' below Csg collar, Set CIBP 5545' rooh w/ WL RD MOL.
1.50	Crew change out rotating head, Re adjusted rig floor.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
1.50	Pu Achor 2.83' WS 6.24' WM 1.45' FM 4.75' XO 1.15' 1-dp 32.22' UBHO 1.99' XO 1.66' 10- hwdp 305.72' XO 1.26, Total BHA 358.27
1.00	Lansing dig out/ line earth pit while crew ate lunch.
2.50	After tih w/ Aoh out of derrick 152 jts out of derrick w/ min/ half a stand,
0.50	Crew change Jsa safety Mtg. Crew finished tih 12 jts total 164 out of derrick an Total 174 jts w/ 10- hwdp WS @ 5537.40.
1.00	PU # 165 w/ WL & Gyro tool.
1.00	Rih with WL/ Gyro tool down to OBHO,
1.00	Then went down w #165 tag 14.40' in @ 5551.80' an oriented few times got it to 322.41 called it good, Sat down 9k shear anchor re check 320.5, pull up/ down gyro final 321.98 called it good an pull gyro up to 5000', pull up on WS 1' string not pulling over, went back down tag @ same depth 5551.80 pull up again no luck, not pulling over string weight. anchor not set or bad casing.
1.00	Rooh w WL/ gyro tool RD WL. Notified Craig W. Wilson D. about WS not setting. Select order fishing tools/ another Whipstock.
2.00	Crew tooh w 164 jts w/ 10 hwdp aoh dp standing back in derrick lay down mills.
1.00	SI Double S hot shot w/ fishing tools, Pu fish tools w/ hook.
4.50	Rih w aoh 164 + 10 hwdp, jar, hook pu 165 an tag WS. Work the hook up/ down to get in slot an rotated ed tbg work it for 45 min no sign of toque tooh w 128 jts no sign of drag or weight change. Crew change at 6:00.

Report Start Date	Report End Date	Operations Summary
4/13/2013	4/14/2013	Jsa Safety Mtg. Crew finished tooh with aoh 36 jts got hook to surface w/ no whipstock. MU box tap, jar, xo 1 dp, ox 10- hwdp 164 jts out of derrick tih pu #165 9.5' in 5551.80' tag up WS, Rotated over WS/ Work box tap up/ down pulling string weight over 10k. Tooh slowly dragging out of hole 450' lost drag, Pull out 41 stands out pull over again 25k then release an continue tooh w/ aoh pull whipstock to surface. Look at WS anchor look like never set against casing, set WS on rig floor an anchor set an measure out 5 1/8", 5 1/2" Csg ID 5.012. RD Select WS/ Mills fish tools mol. Notified Craig Wright fish out of hole, Suggest to Rih w baker set at same depth 5554'. Spotted in Baker w/ WS MU WS/ Mills. Tih with WS, 10- HWDP 164 jts dp @ 5537' w/ baker WS tools, MU #165 w/ WL & Gyro tool, Rih an set ubho started w/ gyro tool face 33.50 made 5 attempts got TF to 320, went down tag CIBP TF 319, Called Craig Wright ok to set 319 check TF one time 319 pu on wire line, Sat down 8k on achor & shear anchor check TF 317, Pull Gyro up to 5000' work string/ Whipstock up/ down 55k to 60k then sat down 30k shear bolt set whipstock, Notified Craig W. about setting @ 317. Rooh w/ WL & Gyro tool RD WL. Crew rig up 3" flex hose to gas buster, RD swivel up w/ # 165, Break Cir. Went down tag up start milling on cutting window 5543.99/ 1000 lbs. down on mill 1200 lbs torque, 1000 lbs Circulation pressure. @ 4 am finished milling whipstock slide from 5543.99 thru 5549.86' / Continue milling rat hole. finished milling rat hole from 5549. 86' thru 5555. 99' total of 6.13' of rat hole. Crew change 6:00 am.

Dur (hrs)	Comment
1.00	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg. Crew finished tooh with aoh 36 jts got hook to surface w/ no whipstock.
6.50	MU box tap, jar, xo 1 dp, ox 10- hwdp 164 jts out of derrick tih pu #165 9.5' in 5551.80' tag up WS, Rotated over WS/ Work box tap up/ down pulling string weight over 10k. Tooh slowly dragging out of hole 450' lost drag, Pull out 41 stands out pull over again 25k then release an continue tooh w/ aoh pull whipstock to surface.
1.50	Look at WS anchor look like never set against casing, set WS on rig floor an anchor set an measure out 5 1/8", 5 1/2" Csg ID 5.012. RD Select WS/ Mills fish tools mol. Notified Craig Wright fish out of hole, Suggest to Rih w baker set at same depth 5554'. Spotted in Baker w/ WS MU WS/ Mills.
2.00	Tih with WS, 10- HWDP 164 jts dp @ 5537' w/ baker WS tools,
0.50	MU #165 w/ WL & Gyro tool,
3.00	Rih an set ubho started w/ gyro tool face 33.50 made 5 attempts got TF to 320, went down tag CIBP TF 319, Called Craig Wright ok to set 319 check TF one time 319 pu on wire line, Sat down 8k on achor & shear anchor check TF 317, Pull Gyro up to 5000' work string/ Whipstock up/ down 55k to 60k then sat down 30k shear bolt set whipstock, Notified Craig W. about setting @ 317. Rooh w/ WL & Gyro tool RD WL.
2.00	Crew rig up 3" flex hose to gas buster, RD swivel up w/ # 165
7.50	Break Cir. Went down tag up start milling on cutting window 5543.99/ 1000 lbs. down on mill 1200 lbs torque, 1000 lbs Circulation pressure. @ 4 am finished milling whipstock slide from 5543.99 thru 5549.86' / Continue milling rat hole. finished milling rat hole from 5549. 86' thru 5555. 99' total of 6.13' of rat hole. Crew change 6:00 am.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Report Start Date 4/14/2013	Report End Date 4/15/2013	Operations Summary Jsa Safety Mtg. Jsa safety Mtg. Crew started whipstock slide assure good slide, Swivel quit working/ Acts like break is lock on swivel, RD all hose's off 3.5 swivel stiff arm's an break joint w/ Tbg tongs LD swivel w/ # 165. Down time 2 hrs, Pu 2.5 swivel xo hose's from 3.5 to 2.5. PU 2.5 swivel w/ # 165 break cir. worked whipstock slide everything looks good. Cir. well for 1 hr. RD Swivel w/ #165. lay down 25 jts on rack tooh w/ 140 jts in derrick + 10 jts Hwdp, LD mills an gauge mill 1/16 under gauge discuss with Doug w/ baker, Good to go LD tools mol. Moved 10 more hwdp to pr tally revised tally/ jt count with Mesa West 199 aoh dp + 20 hwdp total 219 jts on location, Safety Mtg w/ MW & Rig Crew about pu tools/ dp. Western Diverter arrived w new rotating head/ change out. MU 4 3/4 bit/ 3 3/4 , 5L, 3.0 motor an subscribe 2.57/ 31 degree dog leg, 1.23 float sub ,Subscribe w/ 2.87 UBHO set face tool, 1.20, Xo, 31.01 monel, 30.94 monel, UBHO, 8- jts aoh dp 252.69', 1.66" Xo, 15- hwdp. Crew change 18:00, Jsa safety Mtg. Crew finished pu 5 more hwdp total 19- hwdp @ 582.04, 1.26 Xo. Rih w/ 60 jts tested motor (good) continue rih 80 jts out of derrick total 140 jts, Pu 6 jts off float w/ swivel an caliber depth logger, PU # 147 w/ wire line/ gyro tool rih tag 5453' set in face tool 135.04, inclination 0.77 Azmth 336.97. break cir. slide from 5553' to 5564' inclination 1.80 azmth 332.81, Gyro connection slide 5564' to 5570' inclination 1.80 azmth 331.52 return fine sand/ water, losing 12 bbl an getting it back 12 bbl. Crew change at 6:00.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
1.00	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg, Jsa safety Mtg. Crew started whipstock slide assure good slide, Swivel quit working/ Acts like break is lock on swivel, RD all hose's off 3.5 swivel stiff arm's an break joint w/ Tbg tongs LD swivel w/ # 165.
2.00	Down time 2 hrs
1.50	Pu 2.5 swivel xo hose's from 3.5 to 2.5. PU 2.5 swivel w/ # 165 break cir. worked whipstock slide everything looks good. Cir. well for 1 hr
2.50	RD Swivel w/ #165. lay down 25 jts on rack tooh w/ 140 jts in derrick + 10 jts Hwdp, LD mills an gauge mill 1/16 under gauge discuss with Doug w/ baker, Good to go LD tools mol
1.00	Moved 10 more hwdp to pr tally revised tally/ jt count with Mesa West 199 aoh dp + 20 hwdp total 219 jts on location,
0.50	Safety Mtg w/ MW & Rig Crew about pu tools/ dp.
1.50	Western Diverter arrived w new rotating head/ change out.
2.00	MU 4 3/4 bit/ 3 3/4 , 5L, 3.0 motor an subscribe 2.57/ 31 degree dog leg, 1.23 float sub ,Subscribe w/ 2.87 UBHO set face tool, 1.20, Xo, 31.01 monel, 30.94 monel, UBHO, 8- jts aoh dp 252.69', 1.66" Xo, 15- hwdp.
3.00	Crew change 18:00, Jsa safety Mtg. Crew finished pu 5 more hwdp total 19- hwdp @ 582.04, 1.26 Xo. Rih w/ 60 jts tested motor (good) continue rih 80 jts out of derrick total 140 jts, Pu 6 jts off float w/ swivel an caliber depth logger,
3.50	PU # 147 w/ wire line/ gyro tool rih tag 5453' set in face tool 135.04, inclination 0.77 Azmth 336.97.
2.50	break cir. slide from 5553' to 5564' inclination 1.80 azmth 332.81,
3.00	Gyro connection slide 5564' to 5570' inclination 1.80 azmth 331.52 return fine sand/ water, losing 12 bbl an getting it back 12 bbl. Crew change at 6:00.

Report Start Date 4/15/2013	Report End Date 4/16/2013	Operations Summary Jsa Safety Mtg. Continue Sliding from 5570' to 5583', Mesa West suggest don't need Gyro any more. Kick put pump rooh w/ WL, Gyro tool lay down gyro, RD WL MOL. Continue slide from 5582' to 5590' after motor unable to slide/ making no hole, Cir. well, Lay down 2 jts, RD swivel hang back in derrick. Tooh w/ aoh 146 jts, Xo 19 jts hwdp xo 8 aoh dp 2- monels, Ox, ubho, float sub, motor, bit. LD down motor/ Pu new motor re adjust motor from 2.57 to 2.83 @ 34 degree, Re orient mule shoe to high side, string float, ubho, MU 2- monel's 8jts dp, ox, 19 hwdp ox 66 jts aoh out of derrick. Crew change 18:00, Jsa safety Mtg. Finished rih w/ 80 out of derrick total 146 on top of bha. Ru swivel/ pu 147- 148 / swivel tag 5590' break cir. 1100 psi on Tbg. Continue sliding 9k on bit from 5589' to 5594' survey @ 5561' Inc.- 2.6, slide from 5594' to 5625' survey @ 5592' Inc. 9.4, Azm 48', slide from 5625' to 5635' check shots @ 5602' Inc.-13.4, Azm 42, slide from 5635' to 5644' trying to get better reading but check shots @ 5602' Inc. 17.1, Azm 43' at that point sliding wrong way. Notified Craig W. Jason B. about direction Azm of 43'. Suggested to pull back in 5 1/2 wait for orders. Cir. well, pooh lay down 5 jts back to 146 an back in csg. Shut down wait for orders. Crew change at 6:00. wait on orders.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
2.50	This report is on H-222 Capital Injector Key rig #27. Jsa Safety Mtg. Continue Slidding from 5570' to 5583', Mesa West suggest don't need Gyro any more.
1.00	Kick put pump rooh w/ WL, Gyro tool lay down gyro, RD WL MOL.
2.00	Continue slide from 5582' to 5590' after motor unable to slide/ making no hole, Cir. well
1.50	Lay down 2 jts, RD swivel hang back in derrick
2.50	Tooh w/ aoh 146 jts, Xo 19 jts hwdp xo 8 aoh dp 2- monels, Ox, ubho, float sub, motor, bit. LD down motor
1.00	Pu new motor re adjust motor from 2.57 to 2.83 @ 34 degree
1.50	Re orient mule shoe to high side, string float, ubho, MU 2- monel's 8jts dp, ox, 19 hwdp ox 66 jts aoh out of derrick.
1.00	Crew change 18:00, Jsa safety Mtg. Finished rih w/ 80 out of derrick total 146 on top of bha.
1.00	Ru swivel/ pu 147- 148 / swivel tag 5590' break cir. 1100 psi on Tbg.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
7.00	Ru swivel/ pu 147- 148 / swivel tag 5590' break cir. 1100 psi on Tbg. Continue sliding 9k on bit from 5589' to 5594' survey @ 5561' Inc.- 2.6, slide from 5594' to 5625' survey @ 5592' Inc. 9.4, Azm 48', slide from 5625' to 5635' check shots @ 5602' Inc.-13.4, Azm 42, slide from 5635' to 5644' trying to get better reading but check shots @ 5602' Inc. 17.1, Azm 43' at that point sliding wrong way. Notified Craig W. Jason B. about direction Azm of 43'. Suggested to pull back in 5 1/2 wait for orders.
1.50	Cir. well, pooh lay down 5 jts back to 146 an back in csg.
1.00	Shut down wait for orders.
0.50	Crew change at 6:00. wait on orders.

Report Start Date	Report End Date	Operations Summary
4/16/2013	4/17/2013	Waited on orders. Orders were to TOH with Mesa West tools.. Hang swivel back and start out with tools. shut down operations due to high winds in the area. After winds die down finish TOH with tools. Check tools motor was still adjusted at 2.83. Break down tools. crew change at 18:00 tail gate safety meeting with all contractors on location topic was hand placement, job task, suspended loads, wireline operations. Make up BHA with 4 3/4 bit, bit sub and TIH with 171 jts to 5387.. Picked up 4 jts and tag top of window at 5543. Slide on through with out no drag. Tag bottom with jt 180 at 5642. Rig up wireline and picked up Gyrodata tools . Run on in and survey from surface to bottom with 200 ft Incl to top of window at 5543 to 5556. with Azimuth of 347.52. 9 ft later with a 45% turn putting Azimuth at 43.32 from 5556 to 5565. Survey show all tools were working properly. Discuss next operations with Craig Wright. Circulate well clean and lay down 8 jt to get above the window. TOH out with BHA.. Crew change at 6:00 am safety meeting with contractors on location topic was team work, tripping DP, wireline operations., Spot in wireline and rig up

Dur (hrs)	Comment
3.00	wait on orders
0.50	rig down power swivel and hand back
1.00	start TOH with BHA
5.00	waited on wind to die down
1.50	finish TOH with BHA
1.00	check all Mesa West tools and break down
0.50	crew change safety meeting topic was hand placement, job task, suspended loads, wireline operations
0.50	make up BHA with bit and bit sub
2.50	TIH with 171 jt to 5383.
1.00	pick up 2 jt an go through window run on down to 5642 and tag.
1.00	rig up wireline and pick up gyrodata tools
2.00	run tools and survey hole
1.00	circulate well clean
2.50	lay down 8 jt and TOH with BHA
0.50	crew change at 6:00 am saety meeting with contractors on location topic was tripping DP, tong operations, team work
0.50	rig up wireline

Report Start Date	Report End Date	Operations Summary
4/17/2013	4/18/2013	This is the report on Aneth Unit H-222 Capital Injector Key rig # 27 Finish rigging up wireline and pick up CIBP run on in and set at 5522 top of plug. Come out and rig down wireline Wait on Baker to bring out 5 1/2 whipstock. Make up BOH with 5 1/2 Anchor, 5 1/2 whipstock, 4 3/4 window mill, 4 3/4 watermelon mill that were check for gauge, 3 1/8 OD flex pup jt, 2 7/8 AOH x 2 7/8 Pac, UBHO sub, H-90 x 2 7/8 AOH, 19 jts of heavy weight spiral DP, 2 7/8 H-90 x AOH DP and 150 jt of DP to the depth of 5347. Pick-up 5 jt and rig up BlueJet wireline on the 6 jt with Gyrodata tools. Run on in and survey every 1000 ft. Crew change at 18:00 hour safety meeting with contractors on location topic was wireline operations, high pressure lines, keeping up with fluids, communication, Orient whipstock with gyro tool face at 322.02. Have wireline pull up 1000 ft. Shear-off whipstock. Rig down BlueJet and Gyrodata and release. Rig up power swivel and establish circulation. Tag and start milling out casing with pump pressure at 900 psi with 4-K down with good returns of metal, cement, formation shale, Milled out to 5524. Pull-up and circulate well clean. Crew change at 6:00 tail gate safety meeting with contractors on location topic was job task, tripping DP, hand placement. Hang back swivel and TOH with tools

Dur (hrs)	Comment
2.00	spot and rig up wireline to set cibp at 5522
3.00	wait on baker tool hand to deliver whipstock
2.00	pick up 5 1/2 whipstock with anchor and make up
3.50	TIH with tools tally in
1.50	pick-up 5 jts and rig up wireline on the 6 jt pick-up gyro tools and run on in and survey every 1000 ft on the way in
0.50	crew change at 18:00 hours safety meeting with contractors on location topic was wireline operations, high pressure lines, keeping up with fluids, communication
2.00	set and orient whipstock at 322.02 come out and release wireline and gyrodata
1.00	rig up power swivel
6.50	tag and establish circulation and start milling on casing
1.00	circulate well clean
0.50	crew change at 6:00 safety meeting with crew topic was tripping DP, hand placement, job task



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)		Comment
0.50		hang back swivel and start TOH with tools
Report Start Date 4/18/2013	Report End Date 4/19/2013	<p>Operations Summary</p> <p>This is the report on H-222 Capital Injector Key rig #27 Finish TOH with tools. Rig up Mesa west tools with 4 3/4 bit, 3 3/4 3 stage motor, float sub, UBHO sub, x-over, 2 flex Monels, Gyrodata UBHO sub, Rig up to test motors (Good Test) TIH with 8 joints of AOH DP, x-over and 18 jts of spiral heavy weight DP x-over and 146 jts of AOH. Test motors half way in (Good Test). TIH to the depth of 5481 Change out to longer bails. Rig up swivel on jt 173 and BlueJets lubricator to the top of swivel. Pick-up jt and make up gyro tools. Run on in and survey every 1000 ft. Seat for proper tool face. Bring pump on line with 1000 psi at 2 bbl a min. Had no readings in gyro tool. Pull tool to check cable head and gyro tools. Replace gyro tools, computer, and re-head wireline cable. Pick up tools, run on in seat to get tool face. Put pump on line with 1300 psi on pressure Slide from 5522 to 5530. Gyro up date Azimuth at 339.43 Inclination at .6 Tool Face at 326.3. Slide from 5530 to 5536. Gyro connection. Slide from 5536 to 5545 Gyro up date Azimuth at 336.3 Inclination at .74 Tool Face 10.51. Slide from 5545 to 5558 drift up date Azimuth at 333.86 Inclination at .77 Tool Face 9.35. Slide from 5558 to 5568 Gyro up date Azimuth at 332.32 Inclination at .80 Tool Face 18.56. Gyro connection. Crew change at 6:00 safety meeting with contractors on location topic was wireline operations, job task, teamwork Continue to slide drill.</p>
Dur (hrs)		Comment
1.00		hang back swivel and lay down 5 jts
2.50		TOH with BHA
2.00		break down Baker tools and load. Pick up Mesa West tools make up BHA with bit, motor, float sub, UBHO , 2 flex monels, gyro data UBHO sub, 8 jts, xover, 18 HWDP, xover. ttest motors
2.50		TIH with Directionals tools test motor half way in
1.50		change out bails and rig up power swivel on jt 173 rig up wireline lubricator
1.50		run on in and survey every 1000 ft
1.00		set tool face bring pump on line and lost signal and pull tools
3.00		check tools and cable head cre change safety meeting with contractors on location topic was wireline operations, high pressure lines, communication.
3.50		run in with wireline seat and get tool face kick on pump tp 1000 psi at 2 bbl a min tag and start drilling ahead
1.00		pull tools for gyro connection test tools for high side
4.00		slide drill from 5536 to 5568
0.50		crew change at 6:00 am safety meeting with contractors on location topic was wireline operations, job task, teamwork
Report Start Date 4/19/2013	Report End Date 4/20/2013	<p>Operations Summary</p> <p>This is the report on H-222 Capital Injector Key rig #27 Slide drill from 5568 to 5583 Gyro up date Azimuth at 325.25, Inclination 16.10 Slide from 5583 to 5599. gyro up date Azimuth at 326.40 Inclination 16.10. Circulate well clean and pull up wireline for gyro connection. Slide from 5599 to 5631 gyro up date Azimuth 325.10 Inclination 24.70. Circulate well clean pull up and release wireline truck and gyro data. Make connection and slide from 5631 to 5644 Shut down to work on rig pump. Crew change at 18:00 hours safety meeting with contractors on location topic was high pressure lines, job task, keeping and eye on fluids, communication. Reestablish circulation and slide from 5644 to 5663. Survey at 5630. Inclinations at 34.1 azimuth of 323.3 323.3. Slide from 5663 to 5672. when close loop hand notices an pit gain. notified rig operator. Pull up and monitor well through choke. Well unloaded with 100% LEL. good amount of CO2. Pressure climbing up to 1400 psi. Shut in well due to wind direction. Call in for kill weight fluids. Wait on trucks to haul out 15# mud. Run mud across shakers. Open well through choke and bleed of pressure down to 600 psi. Start to pump kill weight fluid kept an eye on pressure. Crew change at 6:00 tail gate safety meeting with crew topic was keeping and eye on fluids, pump pressure, job task. Continue to pump kill weight fluids.</p>
Dur (hrs)		Comment
3.00		continue to slide drill from 5568 to 5583
9.00		circulate well clean pull wireline and lay down tool and test for high side slide drill from 5583 to 5644 with 10 K down and pump pressure at 1350 psi with good returns of formation drill out 61 feet with the help og gyrodata
0.50		crew change safety meting with contractors on location topic was high pressure lines, job task, communication
1.00		work on rig pump
2.00		continue to drill from 5644 5672. with good returns. a total of 28 ft with pump pressure of 1350 psi
1.00		had a pit gain well started to comr around monitor pressure through choke shut in well due to wind direction
3.00		wait on trucks to haul mud from mud plant
2.00		open well through choke and monitors pressure starting at 1400 psi down to 600 psi welll making CO-2
1.00		mud arrived run mud across shakers
1.00		started pump 15# mud keep and eye on pressure
0.50		crew change at 6:00 safety meeting with crew topic was keeping and eye on fluids, pump pressure, job task



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Report Start Date 4/20/2013	Report End Date 4/21/2013	Operations Summary This is the report on AU H-222 Capital Injector. Key Rig # 27 Finish pumping 15.# mud. the well was starting to take fluids. the hole is full and no pressure. pulled up 1 jt with swivel and lay it down. Swivel up on next jt pulled up 15 ft and was stuck. The weight indicator pads was not working properly. Call Craig and discuss next operations.. Decided to circulate well around with P/W to try and get back into window. Waited on water truck to arrive. Start filling up 400 bbl tank. Pumped 40 bbls down tubing it started to pressure up Release pressure and had pumper start wagging G-122 with water. Called out Select Tool hand while waiting replace weight indicator pads and monitor well. Started pull 15 to 20 over and working tubing up and down when it started to move. Crew change at 18:00 safety meeting with contractors on location topic was stay off floor when pulling on DP, tong operations, suspended loads. Work tubing up 30 ft with swivel and lay down jt and continue to work tubing free. Work BHA back in top of window. Waited on kill weight fluids for displacement when TOH with BHA. Start out of hole with BHA. Lay down Mesa West tools. Make up BHA with 4 3/4 bit, bit sub, 8 jts of AOH, 18 jts of HWD, and tally back in.. Crew change at 6:00 am safety meeting with crew topic was tripping DP, communication, teamwork. Continue to TIH
Dur (hrs)		Comment

2.00 finish killing well with 15 # mud through choke manifold
 2.00 lay down jt 151 with swivel pull up on jt 150 about 15 ft up when tubing became stuck.
 3.00 call out water truck to haul in PW
 2.00 had pumper wag well G-1222 and replace weight indicator pads
 3.50 start working tubing up and down and rotate with swivel pull up 30 ft and lay down jt with swivel
 0.50 crew change at 18:00 safety meeting with rig crew topic was staying of rig floor when pulling on DP, tong operations, suspended loads
 3.00 continue to work on pulling DP and BHA back to the top of window
 2.50 had water truck haul in 13# mud and run across shakers for displacement
 3.50 TOH with BHA and pump displacement
 1.50 brake down Mesa West tools and make up BHA with 4 3/4 bit and bit sub tally back in
 0.50 crew change at 6:00 am safety meeting with crew topic was tripping DP, communication, teamwork

Report Start Date 4/21/2013	Report End Date 4/22/2013	Operations Summary Jsa safety Mtg. Crew finished pu last 8 jts w/ swivel tag with 180 5670' work pipe up/ down. Lansing finished load up right w/ 280 bbls 10# brine. Break Cir. to flow back tank, Circulated 13 & 14# mud out of well w/ 10# brine 145 bbls, pump another 5 bbls total 150 bbl 10# brine. SWI well pressure 550 psi, SIW for 30 min pressure up to 850 psi. Went SI H122/ G122 injection wells Notified the pumper/ Lynn Begay/ Craig Wright. Open well flow back 10# back to FB tank lot of Co2, H2S, Fluid. Bled well down to 150 psi, pump another 200 bbl of 10# Down Tbg out Csg fluid did not come back to FB tank, blowing gas down to 0psi well dead. Crew change at 18:00, Crew lay down 7 jts back on cat walk. Waited on order/ monitor well for hour an well started to flow. Craig W. called roll hole w/ pw, wait for mud engineer to mix LCM w/ mud. Roll the hole w/ pw 480 bbl to fb tank w/ some gas pockets, kick out pump pressure drop down to 20 psi an pick up pressure up to 950 psi shut in 30 min. Lansing haul fb to A1/ D6. Open well to fb tank flow well back unloaded p/w, Lot of gas blowing to fb tank 30 to 50 h2s, LEL 4. blow down 250 psi mostly gas/ very little fluid coming back. Lansing haul 545 bbl to D6/ A1. Crew change @ 6:00 AM.
Dur (hrs)		Comment

2.50 Jsa safety Mtg. Crew finished pu last 8 jts w/ swivel tag with 180 5670' work pipe up/ down.
 3.00 Lansing finished load up right w/ 280 bbls 10# brine. Break Cir. to flow back tank, Circulated 13 & 14# mud out of well w/ 10# brine 145 bbls, pump another 5 bbls total 150 bbl 10# brine. SWI well pressure 550 psi, SIW for 30 min pressure up to 850 psi. Went SI H122/ G122 injection wells Notified the pumper/ Lynn Begay/ Craig Wright
 6.50 Open well flow back 10# back to FB tank lot of Co2, H2S, Fluid. Bled well down to 150 psi, pump another 200 bbl of 10# Down Tbg out Csg fluid did not come back to FB tank, blowing gas down to 0psi well dead.
 1.00 Crew change at 18:00, Crew lay down 7 jts back on cat walk.
 1.00 Waited on order/ monitor well for hour an well started to flow. Craig W. called roll hole w/ pw, wait for mud engineer to mix LCM w/ mud.
 3.50 Roll the hole w/ pw 480 bbl to fb tank w/ some gas pockets, kick out pump pressure drop down to 20 psi an pick up pressure up to 950 psi shut in 30 min. Lansing haul fb to A1/ D6.
 6.50 Open well to fb tank flow well back unloaded p/w, Lot of gas blowing to fb tank 30 to 50 h2s, LEL 4. blow down 250 psi mostly gas/ very little fluid coming back. Lansing haul 545 bbl to D6/ A1. Crew change @ 6:00 AM.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Report Start Date 4/22/2013	Report End Date 4/23/2013	Operations Summary Jsa safety Mtg. Crew continue flowing back well to FB tank 500 psi gas/ fluid, H2S 30 & 50 psi SWI due to wind direction to CO2 plant, SIP 450 psi. Waited for Halliburton Mud Engineer to arrive, Engineer arrive @ 13:00. Got sample of MW 13.25# & tested. Mtg with Craig W. about mixing/ pumping mud. Got back to rig, Lansing fill up 400 bbl FW up right tank. Continue to roll out 87 bbls mud to reserve tank, started to mix mud w/ 99 bbl in loop tank an added 100 bbls of FW to bring down 10.2# mud. Safety mtg 9 people about pumping mud/ pressure. Started pumping mud down tbg out csg, Csg 800 psi, Tbg 500 psi pumped pressure an Co2 on return. Blow down csg to 0 psi after pumping 100 bbl 10.2 # mud. Pumped 150 bbls, finally got return back at loop system. Circ. 20 min, lost 30 bbls, SD pump. Unloaded/ materials of dash truck. Started adding FW to mud/ bring down 10#. Added 10 sks zeogel, 6 sks stop hit, 3 sks cedar fiber, 2 sks N seal, total 8% LCM to start with. Swivel up/ PU 3 jts down to #176, 5546' and break circ. w/ 500 pump psi 3 bpm. Circ. well for hr, got back 9.8# mud return w/ no gas or CO2. Made 2 jts down 5609' #178, continue adding very little of zeogel, stop hit, N seal working slide up/ down. PU #179 & 180 working slide with no drag or any sign of CO2/ H2S. Work slide down to 5670' w/ MW 9.8#, circ. well, fluid staying @ 176 bbl in loop system, no loss or gain. Notified Craig W., OK to move on. TOOH w/ DP & bit. Slug 20 bbl with 13# mud down tbg on vac for dry trip. Started RD swivel.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
3.00	This is the report on AU H-222 Capital Injector. Key Rig # 27, Jsa safety Mtg. Crew continue flowing back well to fb tank 500 psi gas/ fluid, H2S 30 & 50 psi SWI do to wind direction to Co2 plant, SIP 450 psi
4.00	Waited for Halliburton Mud Engineer to arrive,
1.50	Engineer arrive @ 13:00, Got sample of mud/ weigh 13.25# & tested
1.00	Mtg with Craig W. about mixing/ pumping mud.
3.00	Lansing fill up 400 bbl fw in up right tanl, Continue to roll out 87 bbls mud to reserve tank, started to mix mud w/ 99 bbl in loop tank added 100 bbls of fw to bring down 10.2# mud.
0.50	Safety mtg 9 people about pumping mud/ pressure.
1.00	Started pumping mud down tbg out csg, Csg 800 psi, Tbg 500 psi pumped pressure an Co2 on return. Blow down csg to 0 psi after pumping 100 bbl 10.2 # mud. Pumped 150 bbls finally got return back at loop system, cir. about 20 min lost 30 bbl SD pump
1.50	unloaded/ materials of dash truck.
1.00	.Started adding fw to mud/ bring down 10#,
7.00	Added 10 sks zeogel, 6 sks- stop hit, 3 sks- ceder fiber, 2 sks- N seal total 8% LCM to start with. Swivel up/ pu 3 jts down to # 176 5546' an break cir. w/ 500 pump psi 3 bpm, Cir. well for hr got back 9.8# mud return w/ no gas or co2. made 2 jts down 5609' #178 continue adding very little of zeogel, stop hit, N seal working slide up/ down, Pu #179 & 180 working slide with no drag or any sign of co2/ h2s, work slide down to 5670' w/ MW 9.8# cir. well fluid staying @ 176 bbl in loop system no lost/ or gain. Notified Craig W. ok to move on tooh w/ dp & bit.
0.50	Slug 20 bbl with 13# mud down tbg on vac for dry trip, Started rd swivel Crew change at 6:00.

Report Start Date 4/23/2013	Report End Date 4/24/2013	Operations Summary Crew finished RD swivel and LD 8 jts on pipe rack. TOOH pumping 6 bbls 9.8# mud every row. TOOH w/146 jts when well start flowing. SD SWI CP @ 600 psi. Tbg dead, installed TIW valve, 9.8# mud in loop system and build up to 10.1 to top kill tbg. Started pumping down tbg 500 psi, Csg 600 psi, open to FB tank. Pump 30 bbls 10.1 mud, csg 0, tbg 0, well dead for sec. Installed string float, RIH w/1 jt, had kick, casing side 500 psi. Choke back 50%, continue RIH w/DP 172 jts 5419'. Csg flowing @ 200 psi to FB tank. SWI wait for orders from Engineers. New contact person Jeremy Ray, Engineer- Denver. Discussed and agree w/ 10.2 MW to pump, csg 600 psi and open to FB tank. Pumped 10.2 mud down tbg, 500 psi pump pressure, csg 0 psi after pumping 80 bbls 10.2 mud. Pump another 70 bbls, total mud return to shaker MW 9.8. Pump another 10 bbls, MW 10.1, total 160 mud pumped. Kick out pump well 0 psi. RD hoses off tbg, open pipe ram. TOOH w/DP standing back in derrick, PO 48 jts. Continue TOOH w/DP, pumping 10.1 mud every row, keep casing full. TOOH LD bit/ sub. Well still dead, PU 4 3/4 bit, motor, ubho, XO, flex monels. Tested motor (good). RIH 60 jts DP, XO, 18 jts hwdp + 17 jts on hwdp, total 95 jts. Tested MWD tool/ motor, pump pressure kept coming up 1700 psi to test motor, acting like plugged hole. TOOH w DP/ hwdp, monels, MWD tool, LD. Test motor at surface (good), MWD checked out good. BO ubho, found little pieces of trash, found that didn't put screen on when testing. Put BHA back together, test motor (good). RIH w/10 jts, test motor (good) but MWD not reading right. Pit hand went to mud plant to get de-former to put in mud. Crew RIH with 95 jts. Pit man came back, dumped de-former in pit and circ. 10 min. MWD tool reading good, continue RIH with DP.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
3.00	This is the report on AU H-222 Capital Injector. Key Rig # 27, Jsa safety Mtg. Crew finished rd swivel an lay down 8 jts on pipe rack. Tooh pumping 6 bbls 9.8# mud every row tooh w/ 146 when well start flowing
3.00	SD SWI CP @ 600 psi, Tbg dead installed Tiw valve, 9.8# mud in loop system an build up to 10.1 to top kill tbg. Started pumping down tbg 500 psi, Csg 600 psi open to fb tank pump 30 bbls 10.1 mud csg 0, tbg 0. well dead for sec
1.00	Installed string float rih w/ 1-jt had kick casing side 500 psi choke back 50%, Continue rih w/ dp 172 jts 5419' csg flowing @ 200 psi to fb tank.
3.00	SWI wait for orders from Engineer's.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)		Comment
		<p>1.00 New contact person Jeremy Rae- Engineer- Denver, Dicussed an agree w/ 10.2 MW to pump. Csg 600 psi an open to fb tank, Pumped 10.2 mud down tbg 500 psi pump pressure, Csg 0 psi after pumping 80 bbls 10.2 mud pump another 70 total mud return to shaker MW 9.8 pump another 10 bbls MW 10.1 total 160 mud pump, kick out pump well 0 psi.</p> <p>1.00 RD hose's off Tbg open pipe ram tooh w/ dp standing back in derrick PO 48 jts. Crew change 18:00</p> <p>2.00 Continue tooh w/ dp pumping 10.1 mud every row keep casing full. TooH lay down bit/ sub.</p> <p>1.50 Pu 4 3/4 bit, motor, ubho, ox, flex monel's. Tested motor (good)</p> <p>1.50 Rih 60 jts dp, ox, 18 jts hwdp + 17 jts on hwdp total 95 jts tested mwd tool/ motor pump pressure kept comming up 1700 psi to test motor acting like plug hole.</p> <p>2.50 TooH w dp/ hwdp monel's mwd tool ld</p> <p>2.00 Test motor at surface (good) mwd check out good. BO ubho found little peace's of trash, found that didn't put screen when testing. Put back bha together test motor (good).</p> <p>2.50 Rih w/ 10 jts test motor (good) but mwd not reading right, Pit hand went to mud plant to get de former to put in mud, crew rih with 95 jts pit man came back dump de former in pit an cir. 10 min, Mwd tool reading good, continue rih with dp. Crew change 6:00.</p>
Report Start Date 4/24/2013	Report End Date 4/25/2013	<p>Operations Summary</p> <p>Finished RIH with DP/ BHA down to 5440'm check MWD tool, motor (good). Put screen in surface jt to circ. but plugged up - trash in screen. Pressure up 1500 psi, went thru routine for about hour, finally plug up down hole. Notified Jeremy Ray, agree to POOH w/tbg. KO pump RD hoses off tbg. TOO H w/DP, BHA, wet pull. LD BHA w/motor. PU bit/sub, RIH w/DP, hwdp down to 5611', 180 jts tbg depth only. Csg started blowing gas to FB tank. Flow back well for 30 min, SWI, wind towards CO2 plant. Kick pump in, circ down tbg out csg. Csg blowing gas to FB tank 500 psi. Pump 120 bbls, csg 0 psi. Switch return to loop system and clean out well. Return a lot of LCM, made 3 poly sweeps, LCM cleared up. Mesa West agreed on mud clean, kick out pump well dead. LD 8 jts on catwalk, TOO H w/DP, hwdp. LD bit/sub, PU motor, MU bit and threads on bit twisted off when making up. LD motor, didn't have another 4 3/4 bit - CH34MRS on location. Notified Donnie T, Jeremy R. agreed on using 4 3/4" bit CH24MRS. PU another motor & 4 3/4 bit CH24MRS, ubho, XO, flex monels, tested motor- mwd tool (good). RIH w/ 60 jts DP, 18- hwdp. RIH w/rest of tbg out of derrick. PU 5 jts off rack to #177, 5599' swivel up.</p>
Dur (hrs)		Comment
		<p>1.00 This is the report on AU H-222 Capital Injector. Key Rig # 27, Jsa safety Mtg. Finished rih with dp/ bha down to 5440' check mwd tool, motor (good).</p> <p>2.50 Put screen in surface jt to cir. but plug up/ trash in screen pressure up 1500 psi went thru routine for about hour finally plug up down hole.</p> <p>4.50 Notified Jeremy Rae agree to pooh w/ tbg. KO pump rd hose's off tbg tooh w/ dp,bha. wet pull. ld bha w/ motor.</p> <p>4.00 pu bit/ sub rih w/ dp, hwdp down to 5611' 180 jts tbg depth only. csg started blowing gas to fb tank flow back well for 30 min swi wind towards co2 plant. Kick pump in cir down tbg out csg, Csg blowing gas to fb tank 500 psi pump 120 bbls csg 0 psi.</p> <p>4.00 Crew change 18:00, Jsa safety Mtg Switch return to loop system an clean out well. return a lot of lcm made 3 poly sweeps lcm clear up, Mesa West agree on mud clean, kick out pump well dead.</p> <p>3.00 LD 8 jts on cat walk tooh w/ dp, hwdp, ld bit/ sub. Pu motor mu bit an threads on bit twisted off when making up. ld motor, didn't have another 4 3/4 bit-CH34MRS on location. Notified Donnie T, Jeremy R. agree on using 4 3/4" bit CH24MRS.</p> <p>2.00 Pu another motor & 4 3/4 bit CH24MRS, ubho, xo, flex monels, tested motor- mwd tool (good).</p> <p>3.00 Rih w/ 60 jts aoh dp, 18- hwdp rih w/ rest of tbg out of derrick. pu 5 jts off rack to #177 5599' swivel up. Crew change 6:00</p>
Report Start Date 4/25/2013	Report End Date 4/26/2013	<p>Operations Summary</p> <p>Crew finished RU swivel, calibrate depth tracker (good). Break Circ, slide from 5672' to 5678'. Mule shoe packed off, had to work DP. Slide from 5678' to 5693', survey @ 5660' Inc 43.2 Az 323.1. Slide from 5693' to 5725', survey @ 5692' Inc 50.4 Az 322.4. Slide from 5725' to 5749', rotate from 5749' to 5756', survey @ 5723' Inc 56.4 AZ 321.9. Slide 5756' to 5771', slide from 5771' 5776'. Rotate from 5776' 5788', survey @ 5755' Inc 61.5 AZ 322.4. As of this morning, sliding from 5788' to 5812' w/ MW 9.9#, Vis 48, ph 7.3, temp 100, pump rate 60 SPM, soils 6.2%, sand 0.50 %, LCM 0%.</p>
Dur (hrs)		Comment
		<p>3.50 Jsa safety mtg, crew finished ru swivel, break cir. tag up at 5672' w #178. slide from 5672' to 5678' mule shoe packed off so work pipe up/ down got cir. back.</p> <p>1.75 good cir. to loop system 9.9# mud vis 47 ph 8 130 bbl no lost or gain slide from 5678' to 5693'.</p> <p>3.75 slide from 5693' to 5725' survey @ 5692' Inc 50.4 AZ 322.4 return shall/ sand. good cir.</p> <p>3.00 mud at 9.9# siding w/ good cir.</p> <p>2.25 Dash hot shot deliver 2 aoh dp, torque gage for aoh. haul back 2 aoh that were bad, 1- mud motor.</p> <p>3.75 slow drilling</p> <p>6.00 slow drilling with good return of fine sand/ shell no h2s or co2. no kick yet. no fluid lost or gain in the last 6 hrs. Crew change @ 6 am.</p>
Report Start Date 4/26/2013	Report End Date 4/27/2013	<p>Operations Summary</p> <p>Continue to slide and rotate from 5788 to 5883</p>



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
4.00	slide and rotate from 5788 to 5808
6.00	connection pick up jt 183 and continue to slide from 5808 to 5820 ROP at 5 ft an hour slide from 5820 to 5881
0.50	pick up jt 183 and establish circulation. 5818 to 5851
0.50	hold safety meeting with all contractors on location topic was keeping and eye on all fluids and report all pit gains and loss we are 11 ft away from DC2C1A had ABS safety check all monitors
1.00	continue to slide from 5851
0.50	crew change at 1800 tail gate safety meeting with contractors on location topic was high pressure lines, communication, team work, keeping an eye on fluids.
3.50	continue to slide to 5860
1.50	drilled into DC2C had an pit gain of 40 bbls pull up and shut in pipe rams and monitor pressure, pressure climbing up to 250 psi open well through choke and vent off gas to flare stack. up mud weight to 9.9 start pumping and re-condition well bore and work out gas bubble.
4.00	continue to slide and rotate from 5860 to 5878. circulate well clean make an connection on jt 185 start slide drilling from 5883.
2.50	continue to slide from 5883 to 5895 crew change at 6:00

Report Start Date 4/27/2013	Report End Date 4/28/2013	Operations Summary Slide and rotate ahead to target Depth of 7376 (TMD)
--------------------------------	------------------------------	--

Dur (hrs)	Comment
0.50	safety meeting with all contractors on location topic was watch all fluids, high pressure lines, job task
5.00	slide from 5883 to 5914 run a survey Inc at 78.5 Az 321.5 start rotating from 5914 to 5946. run a survey
0.50	make a connection with jt 187
3.00	rotate from 5946 to 5956 slide 5956 to 5968 rotate from 5968 to 5977 with 12 K down Survey at 5944 Inc at 84.4 az at 323.5
0.50	make an connection and pick up jt 188
1.00	rotate from 5968 to 5983 survey at
0.50	connection pick up jt 189 mud weight still at 10. vist at 46.
1.00	continue to rotate from 6009 to 6024 survey at
0.50	crew change at 18:00 safety meeting with contractors on location topic was high pressure lines, job task, teamwork
2.50	rotate from 5977 to 6009 survey at 5976 inc at 82.6 Az at 321.0
4.00	continue to rotate from 6041 to 6072 survey at 6039 Inc at 83.0 Az at 321.5 rotate from 6072 to 6094
2.00	shut down due to swivel pull up and lay down jt 191 while working on swivel the well started to flow pressure running up to 400 psi open well through choke and release gas to flare stack and monitors pressure circulate gas around with 10# mud. pull up on jt 190 to make sure we are no stuck work pipe up and down
1.00	pick up jt 192 and continue to rotate on down to 6104. make connection.
2.00	continue to rotate from 6104 to 6135. survey at 6039 Inc at 83.3 Az 321.6 crew change at 6:00

Report Start Date 4/28/2013	Report End Date 4/29/2013	Operations Summary Rotate to 6167 Trip for bit and motor
--------------------------------	------------------------------	---

Dur (hrs)	Comment
0.50	safety meeting with all contractors on location topic was watch all fluids, high pressure lines, job task
5.00	rotate and slide from 6135 to 6167 survey at 6134 Inc at 83.3 Az at 321.9
1.50	bring up mud weight to 10.2# circulate well bore
0.50	safety meeting with contractors topic was keeping hole full, hand placement, laying down DP, communication, job task
2.00	lay down 22 jts with power swivel to get above window at 5512
1.50	rig down power swivel and circulate well around with 9 bbls unload hotshot truck of drilling material with forklift
1.00	TOH with bit and keep hole full
0.50	safety meeting with contractors on location topic was tripping DP, keeping hole full, hand placement, teamwork
1.50	continue to TOH with tools
1.50	break down monels and break down Mesa West Directional tools. make up new (4 3/4 bit # 1333195-CH34) with new 1.75 stage motor and monels. scribe UBHO to motor
2.00	TIH with monels, and 60 jt of AOH DP, 18 jts of HWDP TIH half way to test motor
1.00	circulate well around with 10.2# mud.
1.50	finish tallying in o the top of window at 5512
1.50	rig up power swivel and circulate well around to recondition well bore
2.00	start picking up DP and go through window out lateral to 5883. circulate well
0.50	continue to pick up DP rotate from 6135 to 6167 to clean up lateral. crew change at 6:00

Report Start Date 4/29/2013	Report End Date 4/30/2013	Operations Summary (Continue to rotate ahead to target depth of 7051 TMD) 600 total ft.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
0.50	safety meeting with contractors on location topic was communication, high pressure lines, job task
2.50	calibrate depth tracker make connection and break circulation start rotating from 6167 to 6198 survey at 6165 inc 82.5 az 322.0 with rop at 14 ft an hour with good returns.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
2.50	make connection on jt 195 rotate from 6198 to 6230. survey at 6197 inc at 82.3 az 321.9 with 12 k down rop at 12 to 10 ft an hour
3.00	make connection jt 196 rotate from 6230 to 6262 loss 9 bbls circulate well clean mud weight at 10.2# vist of 46.
0.50	safety meeting with contractors on location topic was keeping an eye on fluids, communication, job task, getting ready to rotate through DC-1A formation
2.50	make connection on jt 197 rotate from 6262 to 6293 survey at 6260 inc 82.8 az 322.4 had no pit gain or loss mud weight at 10.2
0.50	make connetion on jt 198 rotate from 6293 to 6298
0.50	crew change at 18:00 hours safety topic was watch all fluids, communication, teamwork
3.00	continue to rotate from 6298 to 6325 with mud weight of 10.2 coming out and going in with vist of 45. rop at 8 to 10 ft an hour.
3.00	make connccction on jt 199 rotate from 6325 to 6356. survey at 6323 inc 82.1 az 322.4
2.50	make connection on jt 200 rotate from 6356 to 6388 had rop of 25 ft an hour from 6356 to 6374 pressure decrease torq increase pull up and shut down pups well started to flow start up pup and circulate gas pocket aroud with 10.2 mud around.survey at 6323 inc 81.7 az 321.4
2.50	make connection on jt 201 rotate fom 6388 to 6419 survey at 6386 inc 82.1 az 322.4
0.50	make connection on jt 202 start roating from 6419 to 6424 crew change

Report Start Date 4/30/2013	Report End Date 5/1/2013	Operations Summary Rotate to DC-2C and continue to rotate out to Target depth of TMD of 7047. TVD of 5912. 1400 ft of Vertical Section (593 ft to TD)
--------------------------------	-----------------------------	--

Dur (hrs)	Comment
0.50	hold safety meeting with contractors on location topic was high pressure lines, team work, job task
3.00	rotate from 6419 to 6451 with 11 k down with mud weight of 10.1 coming out and going in. pump pressure at 1750. ROP at 13 ft an hour with return of white shell formation.
2.50	circulate well clean went over to office to discuss pulling tools to put string in place
3.00	lay down 18 jt with swivel when well started to flow shut down and monitor pressure and circulate gas bubble around through choke
2.00	finish laying down DP to get back above window.circulate well around to get gas around
1.00	start out with tools
0.50	crew change at 18:00 safety meeting with contractors on location topic was keeping hole full, hand placement, tripping DP
2.50	Finish TOH to 1983 install string float New BHA Directional tool, 30 jts AOH, string float, 30 jts of AOH 18 jts of HWDP. xover and AOH
2.00	TIH to 3417 and circulate well around with 10.1# mud to re-condition well bore and circulate gas around
2.00	finish TIH to top of window at 5512. rig up swivel and circulate well around.
1.00	shut down pump to change out swab that were leaking
2.00	Staet picking up DP with swivel to 6054 circulate gas around
2.00	finish picking up DP to 6454 break circulation and calibrate depth tracker continue to circulate crew change

Report Start Date 5/1/2013	Report End Date 5/2/2013	Operations Summary Continue to rotate out to target depth of TMD of 7047', TVD of 5912', 1400' of vertical section (309' to TD).
-------------------------------	-----------------------------	---

Dur (hrs)	Comment
0.50	Crew change @ 6:00 am, Jsa safety Mtg with crew
4.00	Contiue Cir. well to get air out, MWD no reading. Kick pump out and break down pump valves. Found rocks/ pieces of vis cup in the pump. Aggitator was on in suction pit causing solids to pick up off bottom of suction pit and were sucked into pump.
1.00	Slide from 6454' to 6458' made connection.
2.00	Made connection, rotate from 6458'- 6485', survey @ 6452' Inc 81.7 Az 322.
2.00	Rotate 6485'- 6517', survey @ 6484' Inc 82 Az 321.9.
2.50	Rotate 6517'- 6548', survey @ 6515' Inc 81.9 Az 322, lost 9 bbls.
0.50	Crew Change 18:00, Jsa Safety Mtg.
1.50	Rotate 6548'- 6580', Survey @ 6547' Inc 81.7 Az 321.7.
2.00	Rotate from 6580'- 6611', Survey @ 6578', Inc 81.5 Az 321.9
2.00	Rotate 6611'- 6616', slide from 6616'- 6619', rotate 6619'- 6643', survey @ 6610' Inc 81.5 Az 321.9.
6.00	Rotate 6643'- 6675', survey @ 6642', Inc 81.7 Az 321.4. Rotate 6675'- 6706', survey 6673' Inc 81.9 Az 322.0. Rotate 6706'- 6738', survey @ 6705' Inc 81.9 Az 322.0. Lost 3 bbls last 6 hrs, pump pressure 1600 psi. Mud 10.3, 48 vis. No sign of H2S/ pressure, return of white shell formation. Rotating now from 6738'- 6770' Crew change 6:00.

Report Start Date 5/2/2013	Report End Date 5/3/2013	Operations Summary Continue to rotate/slide and reach TMD 7022' + 12' rat hole, total 7034', TVD 5909.80', Vertical Section 1387.49.
-------------------------------	-----------------------------	---

Dur (hrs)	Comment
0.50	Crew change 6:00 am, Jsa safety mtg.



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)		Comment
		6.00 Rotate from 6738'- 6741', slide 6741'- 6744' rotate 6744- 6770 survey @ 6737' Inc 81.5 Az 321.1, Rotate 6770'- 6774' lost 9 bbl of mud, Cir. well drop MW 10.2#. Continue rotate 6774'- 6801' Survey @ 6768' Inc 81.9 Az 321.3, slide 6801'- 6805' rotate 6805'- 6833' survey @ 6800' Inc 81.7 Az 322.1
		5.50 Rotate 6833'- 6864' survey @ 6831' 81.5 Az 322.1, Rotate 6864'- 6896' survey @ 6863' Inc 80.9 Az 321.6
		0.50 Crew change @ 18:00, Jsa safety Mtg.
		1.00 Rotate 6896'- 6927', Pull up 30' Cir. well for 30 min. CNJ tried to fix 1 Agitator in rig pit but no luck.
		5.50 Survey @ 6894'- Inc 81.3 Az 322.2, Rotate 6927'- 6942. Slide 6942- 6945' rotate 6945'- 6959' Cir. well, Survey @ 6926' Inc 81.6 Az 321.9, Rotate 6959'- 6975'
		3.75 Rotate 6975'- 6991' Survey @ 6958 Inc 80.5 Az 321.5, Rotate 6991'- 6999' slide 6999'- 7001' rotate 7001'- 7022 Survey @ 6989' Inc 80.6 Az 321.6, Rotate 7022'- 7034' TD Survey @ 7001' Inc 80.9 Az 321.9. MDT 7022' + 12' rat hole Total Depth 7034'
		1.25 Work hole for 30 min, Cir. well, Grey color shell return, sand Crew change @ 6:00.
Report Start Date 5/3/2013	Report End Date 5/4/2013	Operations Summary TOOH with 51 jts, lay down on cat walk. TOOH AOH HWDP BHA. RIH w/ Ph6 tail jts, packer, AOH, set packer 5490'.
Dur (hrs)		Comment
		0.50 Crew change 6:00, Jsa safety Mtg
		2.50 Kick out pump, lay down 7 jts pipe dragging up hole w/ swivel rotating
		1.50 Well kick with 350 psi at surface, bled off gas bubble. build mud 10.8# Cir. well dead.
		2.50 Continue to pull, Pipe stuck, Worked pipe for 2.50 hrs, Notified Jeremy Rae/ Craig Wright. Pump 40 bbls F/W an Continue working pipe,
		5.00 Got free an rotating swivel up the hole slowly. lay down 11 jts total.
		0.50 Crew change Jsa safety Mtg.
		0.50 Continue pulling pipe, no luck pipe stuck again worked pipe/ pump 40 bbls f/w still won't get free. pump some quick stop but no luck.
		4.00 Notified Jeremy Rae finally agree on pumping F/W an roll out mud. pump 130 bbl F/W well came flowing out to fb tank. kept pumping f/w work pipe, pipe came free.
		2.75 Continue tooh w/ pipe laying down w/ swivel rotating out, pipe dragging for 20 jts after pipe free up, pull 5 more jts. 196 jts in hole @ 6264', casing flowing to fb tank oil/ gas.
		1.25 Pump 140 bbls 10.1# mud kill well.
		3.00 Continue tooh w/ dp ld total 51 jts on cat walk. Cir. well w/ 11.0# mud crew change @ 6:00 am
Report Start Date 5/4/2013	Report End Date 5/5/2013	Operations Summary Contiue TOOH w/AOH, LD BHA. RIH w/ 5.5 packer, set 5490' w/ 362' tail pipe, Ph6.
Dur (hrs)		Comment
		0.50 Crew change @ 6:00 am. Jsa safety Mtg
		6.50 Hang back swivel, Tooh w/ aoh dp lay down hwdp, lay down motors, monel's
		4.50 PU 1- Mule shoe, 12- ph6 362' 5 1/2" packer/ on off tool. rih w/ aoh re tally 151 jts, Pu 22 more off rack, 22' subs, Set packer 5490' j-off packer.
		2.00 Roll mud out to rig pit w/ fw.
		0.50 Pressure test casing/ packer 1000 psi 30- min. (good).
		1.50 Latch on packer/ RU WL retrieve blank plug. Tbg pressure 500 psi
		8.50 open to fb tank 500 psi drop to 0 psi. FB 35 bbl by 4am, Went to H122/ G122 open back to injection. Flow back rate started to pick up. Crew change 6:00 am.
Report Start Date 5/5/2013	Report End Date 5/6/2013	Operations Summary Flow back well to LD tanks, pump 80 bbls of FW injection rate well taking fluid. FB well, acidize well w/20% acid.
Dur (hrs)		Comment
		0.50 Crew change @ 6:00 am, Jsa safety Mtg,
		11.50 Flow back well Mud/ Gas to FB Tank. Lansing haul fluid to A1. Flow back 480 bbl, pump 80 bbls f/w to get rate. pump 45 bbl well 0 psi, pump another 10 bbl pressure came up to 600 psi pump another 20 bbl pressure stay same 600 psi, total 80 bbl pump. Open back to fb tank,
		0.50 Crew change 18:00, Jsa safety Mtg
		1.50 Wait on baker w/ acid 1.5 hr
		4.00 Baker arrived with acid, Well still dead spot/ ru baker safety mtg. pump 5 bbl ahead pump 5000 gal 20% acid 2.5 bpm flush 60 bbl F/W. pump 42 bbl acid 1455 psi, 119 bbl 1210 psi, Flush F/W 60 bbl, ISIP 705 psi, 5-min 614 psi, 10-min 545 psi, 15-500 psi, SWI 500 psi. RD Baker Acid trucks
		2.00 2 hr SI,
		4.00 200 psi on Tbg, Flow well back 450 psi, Flare gas. flow back 210 bbl Crew change 6:00 am.
Report Start Date 5/6/2013	Report End Date 5/7/2013	Operations Summary Finish picking up new 2 7/8" KC TK FL injection tubing. Latch on to 5 1/2" packer, set at 5490'. Land out and schedule MIT. Rig down all equipment.
Dur (hrs)		Comment
		0.50 safety meeting with contractors on location topic was communication, high pressure lines, job task
		2.50 flow well back through choke and monitor pressure recovered a total of 100 bbls oil cut was about 50/50



Daily Activity Report

Well Name: H222 Aneth Unit

API Number 43037302420000	Section 22	Township 40S	Range 24E	Field Name Aneth	County San Juan	State/Province Utah
Ground Elevation (ft) 4,926.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 12.00	KB-Casing Flange Distance (ft)	Well Spud Date/Time 9/26/1976 00:00	Rig Release Date/Time	

Dur (hrs)	Comment
3.00	spot in and rig up Tefteller test lubricator to 1000 psi (good test) run on in and set 1.81 plug at 5470 pull up and blees off pressure through choke waited on trucks to haul out packer fluid
0.50	pressure test 1.81 plug to make sure it is seat properly for 30 mins
2.50	j-off packer and re-condition well bore with 130 bbls of packer and pressure test packer to 1000 psi (Good Test) release pressure
3.00	start laying down AOH work string and transfer to empty trailer
0.50	crew change safety meeting with contractors on location topic was hand placement, teamwork, suspended loads,
3.00	continue to lay down AOH work string and transfer to empty trailer
1.50	transfer production tubing on to pipe racks and prep. make up on and off tool to nickel coated seat nipple.started setting toque on system by slowly increase the hydraulic pressure it would reach minimum torque when it would fall off by 200 psi. tried with out no success
1.50	went through hydrilic system and add more fluid
4.50	start picking up production tubing pick up 95 jts transfer tubing from trailer to pipe racks and prep.
1.00	satert picking up tubing crew change at 6:00

Report Start Date 5/7/2013	Report End Date 5/8/2013	Operations Summary This well is landed with tubing hanger, stainless steal nipple, 1 jt of new 2 7/8" KC Fiber-lined tubing, 3 pup jts 10,8,4, 167 jts, 5 1/2" nickel-coated Arrowset 1-X packer set at 5490', 1 78 R nipple 2 3/8" x 2 7/8" crossover, 2 7/8" nickel-coated downhole swivel, 13 jts of 2 7/8" PH-6 drill pipe. This well also passed NNEPA MIT, witnessed by Jean Bia.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
0.50	Safety meeting with contractors on location topic was slip trip and falls. job task, communication
2.50	finish picking up tubing. land well with 167 jt pony subs 4,6,10,and landing jt with SS nipple and dunot set down with 20 K on compression
0.50	pressure test packer to 1000 psi (good test) for 30 mins
2.50	rig down rig floor and nipple down BOP stack put away. nipple up upper tree
1.50	rig up tefteller and pressure test lubricator to 1000 psi run on in and spear disk come out and pick up tool to recover 1.81 plug come out and rig down and move off
1.00	start rigging down equipment
1.00	had Wilson srvice on location to perform MIT with NNEPA Jean Bia rig down truck and move off
2.50	rig down service unit
1.00	finish rigging down alll equipment
11.00	have one hand watch all equipment

Report Start Date 5/8/2013	Report End Date 5/9/2013	Operations Summary Have location cleaned up and turn back over to Production.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
4.00	take pressure readings and open well to frac tanks for 4 hours shut in well.
7.00	Key hands out to work on unit and rig pump, Riley out to clean close loop system had Dawn hand watch equipment.
13.00	had one Dawn hand watch all equipment



Resolute Natural Resources

Aneth Unit (Nad 27)

Aneth Unit H222

H222 Sidetrack

Sidetrack

UWI:

WL:

Survey: Final

Standard Survey Report

06 May, 2013








Site: Aneth Unit H222
Well: H222 Sidetrack
Wellbore: Sidetrack
Plan: Final

Reference Details - WELL CENTRE
Geodetic System: US State Plane 1927 (Exact solution)
Ellipsoid: Clarke 1866
Zone: Utah Central 4302
Northing: -369691.10
Easting: 2651861.48
Latitude: 37° 17' 46.428 N
Longitude: 109° 15' 39.172 W
Grid Convergence: 1.43° West
Ground Elevation: 4933.0
KB Elevation: KB @ 4945.0usft



PLAN DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
5520.0	0.00	0.00	5520.0	0.0	0.0	0.00	0.00	0.0	
5847.3	82.65	322.00	5745.0	155.9	-121.8	25.25	322.00	197.9	
6667.7	82.65	322.00	5850.0	797.1	-622.8	0.00	0.00	1011.5	
7121.1	82.65	322.00	5908.0	1151.4	-899.6	0.00	0.00	1461.2	
7376.9	77.53	322.00	5952.0	1349.9	-1054.7	2.00	180.00	1713.1	D4_TD (H222)



Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Project	Aneth Unit (Nad 27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		Using geodetic scale factor

Site	Aneth Unit H222		
Site Position:		Northing:	-369,691.10 usft
From:	Lat/Long	Easting:	2,651,861.48 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	37° 17' 46.428 N
		Longitude:	109° 15' 39.172 W
		Grid Convergence:	1.43 °

Well	H222 Sidetrack		
Well Position	+N/-S	0.0 usft	Northing:
	+E/-W	0.0 usft	Easting:
Position Uncertainty	0.0 usft	Wellhead Elevation:	usft
		Latitude:	37° 17' 46.428 N
		Longitude:	109° 15' 39.172 W
		Ground Level:	4,933.0 usft

Wellbore	Sidetrack				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2/8/2013	10.39	63.61	50,694

Design	Final				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.0	0.0	0.0	322.00	

Survey Program	Date	5/6/2013			
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
5,512.7	7,034.0	Final (Sidetrack)	MWD	MWD - Standard	

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	-4,945.0	0.0	0.0	0.0	0.00	0.00	0.00
Top of Window at 5512.7' MD										
5,512.7	0.00	0.00	5,512.7	567.7	0.0	0.0	0.0	0.00	0.00	0.00
Bottom of Window at 5518' MD										
5,518.0	3.10	322.00	5,518.0	573.0	0.1	-0.1	0.1	58.49	58.49	0.00
5,535.0	6.60	325.25	5,534.9	589.9	1.3	-0.9	1.6	20.64	20.59	19.12
5,566.0	16.10	326.40	5,565.3	620.3	6.3	-4.3	7.7	30.65	30.65	3.71
Ismay										
5,590.1	22.57	325.33	5,588.0	643.0	12.9	-8.8	15.6	26.91	26.87	-4.43
5,598.0	24.70	325.10	5,595.3	650.3	15.5	-10.6	18.8	26.91	26.88	-2.95

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,630.0	34.10	323.30	5,623.1	678.1	28.2	-19.8	34.5	29.50	29.38	-5.63
5,660.0	43.20	323.10	5,646.5	701.5	43.2	-31.0	53.2	30.34	30.33	-0.67
LISA										
5,674.8	46.53	322.76	5,657.0	712.0	51.6	-37.3	63.6	22.56	22.50	-2.33
5,692.0	50.40	322.40	5,668.4	723.4	61.8	-45.2	76.5	22.56	22.50	-2.07
5,723.0	56.40	321.90	5,686.9	741.9	81.4	-60.4	101.4	19.40	19.35	-1.61
LISB										
5,750.1	60.72	322.33	5,701.0	756.0	99.6	-74.6	124.5	15.99	15.94	1.57
5,755.0	61.50	322.40	5,703.4	758.4	103.1	-77.2	128.8	15.99	15.94	1.49
LISC										
5,782.8	64.45	322.75	5,716.0	771.0	122.7	-92.3	153.5	10.68	10.62	1.25
5,787.0	64.90	322.80	5,717.8	772.8	125.7	-94.6	157.3	10.68	10.63	1.22
5,818.0	68.20	322.30	5,730.1	785.1	148.3	-111.9	185.8	10.75	10.65	-1.61
5,850.0	73.70	321.70	5,740.6	795.6	172.1	-130.5	216.0	17.28	17.19	-1.88
DC 1A										
5,863.0	75.71	321.62	5,744.0	799.0	182.0	-138.3	228.5	15.50	15.48	-0.65
5,881.0	78.50	321.50	5,748.0	803.0	195.7	-149.2	246.1	15.50	15.48	-0.64
5,913.0	83.90	323.10	5,752.9	807.9	220.7	-168.5	277.7	17.58	16.88	5.00
5,944.0	84.40	323.50	5,756.1	811.1	245.5	-186.9	308.5	2.06	1.61	1.29
5,976.0	82.60	321.40	5,759.7	814.7	270.7	-206.3	340.3	8.61	-5.63	-6.56
6,008.0	82.80	321.00	5,763.8	818.8	295.4	-226.2	372.0	1.39	0.63	-1.25
DC 1B										
6,034.1	82.97	321.42	5,767.0	822.0	315.6	-242.4	398.0	1.73	0.65	1.61
6,039.0	83.00	321.50	5,767.6	822.6	319.4	-245.5	402.8	1.73	0.65	1.61
6,071.0	83.10	321.50	5,771.5	826.5	344.2	-265.2	434.6	0.31	0.31	0.00
6,102.0	83.30	321.60	5,775.1	830.1	368.4	-284.4	465.3	0.72	0.65	0.32
6,134.0	83.00	321.90	5,779.0	834.0	393.3	-304.0	497.1	1.32	-0.94	0.94
DC 1C										
6,134.4	83.00	321.90	5,779.0	834.0	393.6	-304.3	497.5	0.00	0.00	0.00
6,165.0	82.50	322.00	5,782.9	837.9	417.5	-323.0	527.9	1.66	-1.63	0.33
6,197.0	82.30	321.90	5,787.1	842.1	442.5	-342.5	559.6	0.70	-0.63	-0.31
6,229.0	82.50	322.30	5,791.3	846.3	467.5	-362.0	591.3	1.39	0.63	1.25
6,260.0	82.80	322.40	5,795.3	850.3	491.9	-380.8	622.1	1.02	0.97	0.32
DC 2A										
6,288.3	82.18	322.40	5,799.0	854.0	514.1	-397.9	650.1	2.19	-2.19	0.00
6,292.0	82.10	322.40	5,799.5	854.5	517.0	-400.2	653.8	2.19	-2.19	0.00
6,323.0	81.30	321.40	5,804.0	859.0	541.1	-419.1	684.4	4.10	-2.58	-3.23
6,355.0	81.70	321.40	5,808.7	863.7	565.9	-438.8	716.1	1.25	1.25	0.00
6,386.0	81.50	321.50	5,813.2	868.2	589.9	-458.0	746.8	0.72	-0.65	0.32
6,418.0	81.40	321.40	5,818.0	873.0	614.6	-477.7	778.4	0.44	-0.31	-0.31
6,452.0	81.70	322.00	5,823.0	878.0	641.0	-498.5	812.0	1.96	0.88	1.76
6,484.0	82.00	321.90	5,827.5	882.5	665.9	-518.0	843.7	0.99	0.94	-0.31
DC 2B										
6,487.4	81.99	321.91	5,828.0	883.0	668.6	-520.1	847.1	0.45	-0.32	0.32
6,515.0	81.90	322.00	5,831.9	886.9	690.1	-537.0	874.4	0.45	-0.32	0.32

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
6,547.0	81.70	321.70	5,836.4	891.4	715.0	-556.5	906.1	1.12	-0.63	-0.94
6,578.0	81.50	321.90	5,841.0	896.0	739.1	-575.5	936.7	0.91	-0.65	0.65
6,610.0	81.70	321.30	5,845.6	900.6	763.9	-595.2	968.4	1.96	0.63	-1.88
DC 2C										
6,640.2	81.70	321.39	5,850.0	905.0	787.3	-613.8	998.3	0.31	0.00	0.31
6,642.0	81.70	321.40	5,850.3	905.3	788.7	-614.9	1,000.1	0.31	0.00	0.31
6,673.0	81.90	322.00	5,854.7	909.7	812.7	-633.9	1,030.7	2.02	0.65	1.94
6,705.0	81.50	321.10	5,859.3	914.3	837.5	-653.6	1,062.4	3.05	-1.25	-2.81
6,737.0	81.50	321.10	5,864.0	919.0	862.2	-673.5	1,094.1	0.00	0.00	0.00
6,768.0	81.90	321.30	5,868.5	923.5	886.1	-692.7	1,124.7	1.44	1.29	0.65
6,800.0	81.70	322.10	5,873.1	928.1	910.9	-712.4	1,156.4	2.55	-0.63	2.50
6,831.0	80.50	322.00	5,877.9	932.9	935.1	-731.2	1,187.0	3.88	-3.87	-0.32
6,863.0	80.90	321.60	5,883.0	938.0	959.9	-750.7	1,218.6	1.76	1.25	-1.25
6,894.0	81.30	322.20	5,887.8	942.8	984.0	-769.6	1,249.2	2.31	1.29	1.94
6,926.0	81.60	321.90	5,892.6	947.6	1,009.0	-789.1	1,280.9	1.32	0.94	-0.94
6,958.0	80.50	321.50	5,897.6	952.6	1,033.8	-808.7	1,312.5	3.65	-3.44	-1.25
6,989.0	80.60	321.60	5,902.7	957.7	1,057.7	-827.7	1,343.1	0.45	0.32	0.32
Last MWD Svy;7001' MD										
7,001.0	80.90	321.90	5,904.6	959.6	1,067.0	-835.0	1,354.9	3.51	2.50	2.50
DC III										
7,022.6	80.90	321.90	5,908.0	963.0	1,083.8	-848.2	1,376.2	0.00	0.00	0.00
Extrap to Bit;7034' MD										
7,034.0	80.90	321.90	5,909.8	964.8	1,092.7	-855.1	1,387.5	0.00	0.00	0.00

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting		
- Shape	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)	Latitude	Longitude
D4_TD (H222)	0.00	0.00	5,952.0	1,349.9	-1,054.7	-368,340.03	2,650,805.87	37° 18' 0.031 N	109° 15' 51.803 W
- survey misses target center by 328.3usft at 7034.0usft MD (5909.8 TVD, 1092.7 N, -855.1 E)									
- Point									

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well H222 Sidetrack
Project:	Aneth Unit (Nad 27)	TVD Reference:	KB @ 4945.0usft
Site:	Aneth Unit H222	MD Reference:	KB @ 4945.0usft
Well:	H222 Sidetrack	North Reference:	Grid
Wellbore:	Sidetrack	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
5,590.1	5,588.0	Ismay		0.00	
5,674.8	5,657.0	LISA		0.00	
5,750.1	5,701.0	LISB		0.00	
5,782.8	5,716.0	LISC		0.00	
5,863.0	5,744.0	DC 1A		0.00	
6,034.1	5,767.0	DC 1B		0.00	
6,134.4	5,779.0	DC 1C		0.00	
6,288.3	5,799.0	DC 2A		0.00	
6,487.4	5,828.0	DC 2B		0.00	
6,640.2	5,850.0	DC 2C		0.00	
7,022.6	5,908.0	DC III		0.00	

Survey Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
5,512.7	5,512.7	0.0	0.0	Top of Window at 5512.7' MD
5,518.0	5,518.0	0.1	-0.1	Bottom of Window at 5518' MD
7,001.0	5,904.6	1,067.0	-835.0	Last MWD Svy;7001' MD
7,034.0	5,909.8	1,092.7	-855.1	Extrap to Bit;7034' MD

Checked By: _____ Approved By: _____ Date: _____

END OF WELL REPORT



Client: Resolute Natural Resources
Well Name: Aneth Unit H222
Location: Sec.22, T40S, R24E
Job Number: 1305
Start Date: 12-Apr-13 **End Date:** 5-May-13

PERSONAL

Operator Personnel

Company Man:

Myron Dee, James Yellowman

Geologist:

Directional Personnel

David Westbrook
Shane Sligar

Survey Personnel

Ron Alexis
Greg Vlaming

WELL SUMMARY

BHA 1 - Drilled F/ 5556' - 5590' , 34 ft in 7.75 hrs - 4.4 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with no jets . Motor is a CAVO 3.75", 5/6 lobe, 3.0 stage, 1.4 rev/gal, set at 2.57°.

While sliding motor lost all reactive torque and drilling differential pressure. Tripped BHA 1 out to inspect motor. Motor drained on surface but was making grinding noises and would lock up and let free while draining on surface.

BHA 2 - Drilled F/ 5590' - 5644' , 54 ft in 5.5 hrs - 9.82 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a CAVO 3.75", 5/6 lobe, 3.0 stage, 1.4 rev/gal, set at 2.83°.

Tripped out due to coming off of whipstock @ 48° azimuth instead of 322°. On surface high side of motor was scribed to top of UBHO to insure mule shoe didn't move from original point. Motor drained and sounded good on surface and had no visual signs of wear. Motor delivered 41 9/100'.

Ran in wireline to check inc and azimuth of existing well in 200' increments to top of window. From window to end of mill depth azimuth went from 322 at top to 338 azimuth at bottom of milled depth. At the point which gyro was used to slide azimuth trended from 338 - 48 azimuth from 5556' to 5583' the point which gyro was released.

BHA 3 - Drilled F/ 5522' - 5672' , 150 ft in 11.25 hrs - 12.8 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a CAVO 3.75", 5/6 lobe, 3.0 stage, 1.4 rev/gal, set at 2.29°.

Motor delivered 26 9/100' during the build section. Motor drained well and no visible signs of wear at surface. TOOH due to gas kick.

BHA 4 - Drilled F/ 5672' - 5672'

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 2.00°.

At shallow test pressure spiked out at 2500#. Recycled pumps and brought throttle to operating range pressure was 2500# and circulating full returns. MWD was sending bad pulses. TOOH to inspect BHA.

BHA 5 - Drilled F/ 5672' - 5672'

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 2.00°.

Tested motor halfway in hole and had bad pulses due to air in mud. Conditioned mud with defoamer and tool tested fine. Continued to trip in hole to top of window and proceeded to break circulation. Pressure went to normal operating pressure but began to rise. Once pump was kicked out pressure stayed at 1600# multiple times and was bled off through pump.

BHA 6 - Drilled F/ 5672' - 6167' , 495ft in 68.25 hrs - 7.25 ft/hr

Bit - 4 3/4" Varel insert CH24MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 1.75°.

Motor averaged 18 9/100' throughout the bottom half of the build section except for the Gothic Shale where it delivered 15 9/100'.

POOH due to slow ROP and bit hours - motor had numerous stalls while rotating. All three cones were locked up on this bit.

BHA 7 - Drilled F/ 6167' - 7034' , 867ft in 57.75 hrs - 15 ft/hr

Bit - 4 3/4" Varel insert CH34MRS with No jets . Motor is a Adtech 3.75", 9/10 lobe, 3.3 stage, 1.18 rev/gal, set at 1.75°.

REPORT PREPARED BY:

David Westbrook

RECEIVED: May. 15, 2013

END OF WELL REPORT 2



Client: Resolute Natural Resources
Well Name: Aneth Unit H222
Location: Sec.22, T40S, R24E
Job Number: 1305
Start Date: 12-Apr-13 **End Date:** 5-May-13

PERSONAL

Operator Personnel
Company Man:
 Myron Dee, James Yellowman
Geologist:

Directional Personnel
 David Westbrook
 Shane Sligar

Survey Personnel
 Ron Alexis
 Greg Vlaming

WELL SUMMARY

KOP: 5525	TD: 7034	FEET DRLG.: 1600	TOTAL DRLG. HRS.: 146	AVG. ROP:
# DAYS: 22	# BITS: 3	# BHA'S: 7	NO. OF MOTORS: 6	11.0

Well Parameters

RE-ENTRY	TOTAL DEPTH	
	Leg 1	LEG 2
HOLE SIZE: 4 3/4 WHIPSTOCK SETTING: 322.18° Coordinates: MD: TVD: INC: DIRECTION: VERTICAL SECTION: N / S: E / W:	HOLE SIZE: 4 3/4 Coordinates: MD: 5644 TVD: 5640.64 INC: 28.65 DIRECTION: 32 VERTICAL SECTION: 5.47 N / S: 16.62 E / W: 12.39	HOLE SIZE: 4 3/4 Coordinates: MD: 7034 TVD: 5909.8 INC: 80.9 DIRECTION: 321.9 VERTICAL SECTION: 1387.49 N / S: 1092.65 E / W: -855.13

RE-ENTRY DATA:

TOP OF WINDOW: 5512.67 DIRECTION: 322.18
 BOTTOM OF WINDOW: 5518.49 RAT HOLE: 7

DIRECTIONAL COMMENTS

1. Slide with gyro until the azimuths match with the MWD tool.
2. Install an auto-driller to maximize weight-on-bit and penetration rate.
3. Install a stroke counter to maximize motor performance, hole cleaning and penetration rate.
4. A PDC bit might drill faster - especially in the Desert Creek formations.

REPORT PREPARED BY:

David Westbrook

RECEIVED: May. 15, 2013